



Box Hill Growth Centre Precincts

*Development Control Plan
March 2018*

March 2018

© Crown Copyright, State of NSW through its Department of Planning and Environment 2018

Disclaimer

While every reasonable effort has been made to ensure this document is correct at time of printing, the State of NSW, its agents and employees, disclaim any and all liability to any person in respect of anything or the consequences of anything done or omitted to be done in reliance or upon the whole or any part of this document.

Copyright notice

In keeping with the NSW Government's commitment to encourage the availability of information, you are welcome to reproduce the material that appears in the Box Hill Growth Centre Development Control Plan. This material is licensed under the Creative Commons Attribution 4.0 International (CC BY 4.0). You are required to comply with the terms of CC BY 4.0 and the requirements of the Department of Planning and Environment.

More information can be found at: <http://www.planning.nsw.gov.au/Copyright-and-Disclaimer>.

Contents

1.0	INTRODUCTION	11
1.1	Name of this Plan	11
1.2	The Purpose of this DCP	13
1.3	Relationship to other Plans	14
1.4	Structure of this Plan	15
1.5	Development	16
1.5.1	Exempt and Complying Development	16
1.6	Advertising & Notification Procedures	17
1.6.1	Mandatory Advertising/Notification	17
1.6.2	Notification of Development Applications	17
1.6.3	Notification Timeframes	18
1.6.4	Circumstances where Notification is not Required	18
1.6.5	Conciliation Conferences	18
1.7	Development Application Process	19
1.8	Information required for a Development Application	21
1.8.1	Development Application Form	21
1.8.2	Documentation	21
1.9	Assessment of Applications	40
1.10	Amendments	41
1.10	Amendments	41
2.0	VISION AND CHARACTER	43
2.1	Vision and Development Objectives	43
2.2	Indicative Layout Plan	44
2.3	Character Areas	46
2.3.1	Centres	46
2.3.2	Ridge	48
2.3.3	Historic View Corridor	49
2.4	Sub-precincts	50
3.0	LAND DEVELOPMENT	54
3.1	Residential Density and Subdivision	54
3.1.1	Residential Density	55
3.1.2	Block and Lot Layout	57
3.1.3	Battle-axe Lots	62
3.1.4	Corner Lots	64
3.2	Subdivision Approval Process	66
3.3	Movement Network	69
3.3.1	Street Network, Design and Hierarchy	69
3.3.2	Laneways	79
3.3.3	Shared Driveways	82
3.3.4	Public Transport	83
3.3.5	Pedestrian and Cycle Network	86
3.4	Public Domain Works	88
3.5	Residue Lots	92
4.0	RESIDENTIAL DEVELOPMENT	94
4.1	Site Responsive Design	94
4.1.1	Cut and Fill	94
4.1.2	Safety and Surveillance	95
4.1.3	Sustainable Building Design	96
4.2	Dwelling design controls	97
4.2.1	Summary of Key Controls	97
4.2.2	Streetscape and architectural design	104
4.2.3	Front setbacks	108
4.2.4	Side and rear setbacks	110

4.2.5	Dwelling Height, Massing and Siting	113
4.2.6	Landscaped Area	113
4.2.7	Private Open Space	114
4.2.8	Garages, Storage, Site Access and Parking	115
4.2.9	Visual and Acoustic Privacy	116
4.2.10	Fencing	117
5.0	Additional controls for certain dwelling types	119
5.1	Attached or abutting dwellings	119
5.2	Secondary dwellings, studio dwellings and dual occupancies	120
5.3	Multi dwelling housing	123
5.4	Controls for residential flat buildings, manor homes and shop top housing	125
5.4.1	Site Servicing	128
5.5	Adaptable housing	130
5.6	Other development in residential areas	131
5.6.1	General requirements	131
5.6.2	Exhibition homes and Exhibition Villages	132
5.6.3	Child Care Centres	134
5.6.4	Educational Establishments and Places of Worship	134
5.6.5	Neighbourhood Shops	136
5.6.6	Seniors Housing	138
6.0	EMPLOYMENT AREAS	140
6.1	Lot Subdivision	140
6.1.1	Lot Size and Orientation	140
6.1.2	Site Coverage and Landscaped Area	140
6.1.3	Strata or Community Title	141
6.2	Built form	142
6.2.1	Setbacks	142
6.3	Building Layout and Orientation	145
6.3.1	Building Separation	145
6.3.2	Floor to Ceiling Height	146
6.3.3	Sustainable Building Design	147
6.3.4	Architectural Design	148
6.3.5	Ancillary Buildings, Storage and Service Areas	150
6.3.6	Fencing	151
6.3.7	Signage and Lighting	151
6.4	Landscape Design	152
6.4.1	Common Open Space	152
6.5	Access and Parking	153
6.5.1	Pedestrian Access	153
6.5.2	Vehicular Access	153
6.5.3	Car parking	154
6.6	Safety and Surveillance	157
7.0	MANAGING THE ENVIRONMENT	159
7.1	Integrated Stormwater Management	159
7.2	Aboriginal Heritage	166
7.3	European Heritage	168
7.4	Bush Fire Hazard Management	171
7.5	Tree and Bushland Protection	174
7.6	Contamination Management	175
7.7	Geotechnical	176
7.8	Subdivision Earthworks	178
7.9	Cut and Fill	179
7.10	Salinity Management	180
7.11	Waste Management	183
7.12	Riparian Corridors and Environmental Conservation Areas	184
7.13	Noise and Vibration	192

7.14	Odour.....	199
8.0	SPECIAL AREA CONTROLS	201
8.1	Centres	201
8.1.1	Overall controls	201
8.1.2	Box Hill Town Centre	207
8.1.3	Mt Carmel Village.....	210
8.1.4	Box Hill Inn Village	212
8.1.5	Nelson Road Village	214
8.1.6	Neighbourhood Centres	216
8.1.7	Box Hill House	218
8.1.8	The Hunting Lodge	221
8.1.9	Box Hill Inn.....	223
8.1.10	Marklye	225
	APPENDIX A: Glossary	228
	APPENDIX B: List of Preferred Plant Species	231
	Table B1: Preferred Species for General Planting	231
	Table B2: Preferred Species for Street Tree Planting	239
	APPENDIX C: Materials and finishes colour palette	243

Figures

Figure 1	Land to which this DCP applies	12
Figure 2	Box Hill Growth Centre Precincts Indicative Layout Plan.....	45
Figure 3	Box Hill Growth Centre Precincts character areas	47
Figure 4	Sub-precincts	52
Figure 5	Example for calculating Net Residential Density of a subdivision application	54
Figure 6	Distinct and coherent streetscapes occur in varying proportions in density bands.....	56
Figure 7	Measurement of minimum lot widths and lot area	60
Figure 8	Two examples of lot subdivision for 'sets' of attached or abutting terraces	62
Figure 9	Examples of locations of battle-axe lots	63
Figure 10	Examples of driveways and shared driveways for battle-axe lots	64
Figure 11	Corner lots.....	65
Figure 12	Sample of a Building Envelope Plan (BEP).....	68
Figure 13	Sample of a Public Domain Plan (PDP)	68
Figure 14	Road network	70
Figure 15	Typical Sub Arterial Road	75
Figure 16	Sub-arterial Road (Terry Road between Windsor Road and Killarney Chain of Ponds).....	75
Figure 17	Sub-arterial Road (Terry Road between Killarney Chain of Ponds and Mason Road)	76
Figure 18	Typical Collector Road.....	76
Figure 19	Mt Carmel Road (between Windsor Road and the Killarney Chain of Ponds).....	76
Figure 20	Town Centre Main Street.....	77
Figure 21	Local Street	77
Figure 22	Local Street within visual corridor	77
Figure 23	Local Street within the employment area	78
Figure 24	Parallel Road to Windsor Road.....	78
Figure 25	Perimeter Road along Riparian Corridors/Parks	78
Figure 26	Laneway principles	80
Figure 27	Sample lane layouts	81
Figure 28	Sample laneways showing maximum number of secondary dwellings or strata studios	82
Figure 29	Indicative examples of shared driveways	83
Figure 30	Public transport.....	85
Figure 31	Pedestrian and cycle network	87
Figure 32	Open space	91
Figure 33	Maximum cut and fill with residential blocks	95
Figure 34	The combination of built form, lot size, garaging and landscaping creates different streetscapes	105
Figure 35	Streetscape design principles	107
Figure 36	Minimum front setback distances.....	109
Figure 37	Minimum front setbacks for dwellings fronting open space or drainage land	109
Figure 38	Minimum setbacks for corner lot dwellings	109
Figure 39	Dwelling and open space siting principles for different lot orientations	111
Figure 40	Battle axe lot (without any street frontage) example of setbacks	112
Figure 41	Battle axe lot (fronting access denied road) setbacks	112
Figure 42	Soft landscaped area and principal private open space	114
Figure 43	Location of 20 m and 21 m front setbacks in employment areas	143
Figure 44	Front setbacks in Windsor Road Business Park.....	144
Figure 45	Typical building layout in Annangrove Road Employment Area.....	145
Figure 46	Building separation	146
Figure 47	Basement parking located primarily under building footprints.....	156
Figure 48	Basement parking behind front building line and located fully below footpath.....	156
Figure 49	Semi-basement parking.....	156
Figure 50	Evacuation plan for regional PMF event.....	163
Figure 51	Flood Affected areas with Potential to be Filled.....	164
Figure 52	Catchments that bypass stormwater management devices.....	165
Figure 53	Sensitive Aboriginal archaeological areas.....	167
Figure 54	Location of heritage items.....	170
Figure 55	Indicative APZ requirements.....	173

Figure 56	Riparian corridors	189
Figure 57	Land with some Development Potential in the E2 Environmental Conservation Zone	190
Figure 58	Perimeter roads and subdivision pattern along Riparian Corridors	191
Figure 59	Location of existing and potential future noise sources	193
Figure 60	Sub-arterial and collector roads	194
Figure 61	Locating noise sensitive rooms away from the noise source	196
Figure 62	Single storey residences.....	196
Figure 63	Double storey residences	197
Figure 64	Continuous non-sensitive use frontage	197
Figure 65	Service road for buffer and access to residential premises	198
Figure 66	Indicative layout of Box Hill Town Centre	207
Figure 67	Indicative layout of Mt Carmel Village	210
Figure 68	Indicative layout plan of Windsor Road Village.....	212
Figure 69	Indicative layout plan of Nelson Road Village	214
Figure 70	Precinct Plan Control Area for Box Hill House.....	219
Figure 71	Cross section of Box Hill House to Rouse Hill House	220
Figure 72	Precinct Plan Control Area for the Hunting Lodge.....	222
Figure 73	Precinct Plan Control Area for Box Hill Inn	224
Figure 74	Precinct Plan Control Area for Marklye	226

Tables

Table 1	Development Application Process	20
Table 2	Matrix of Lodgement Requirements	23
Table 3	Description of documentation	26
Table 4	DCP Amendments	41
Table 5	Typical Characteristics of Residential Net Densities.....	55
Table 6	Minimum lot size by density bands.....	59
Table 7	Minimum lot frontages by density bands	60
Table 8	Subdivision Approval Process.....	66
Table 9	Street types	71
Table 10	Minimum Footpath Requirements	72
Table 11	Summary of lot and dwelling types.....	98
Table 12	Summary of key controls for lots with frontage width $\geq 4.5\text{m}$ for rear accessed dwellings	99
Table 13	Summary of key controls for lots with frontage width $\geq 7\text{m}$ and $< 9\text{m}$ for front accessed dwellings	100
Table 14	Summary of key controls for lots with frontage width $\geq 9\text{m}$ and $\leq 15\text{m}$ for front accessed dwellings	100
Table 15	Summary of key controls for lots with frontage width $> 15\text{m}$ for front accessed dwellings.....	102
Table 16	Summary of key controls for lots in the Ridge Area.....	103
Table 17	Key controls for secondary dwellings and studio dwellings	121
Table 18	Key controls for multi dwelling housing	124
Table 19	Key controls for residential flat buildings, manor homes and shop top housing	126
Table 20	Car parking requirements for places of public worship and educational establishments	135
Table 21	Site coverage	141
Table 22	Deep soil planting.....	141
Table 23	Front setbacks.....	142
Table 24	Side and rear setbacks	144
Table 25	Building separation	146
Table 26	Floor to ceiling height.....	147
Table 27	Open space provision	152
Table 28	Water quality and stream erosivity performance objectives for the North West Growth Centres	160
Table 29	Riparian corridors objectives and controls.....	187
Table 30	Road traffic noise planning strategies	195
Table 31	Guidelines for sensitive development.....	198
Table 32	On site car parking for commercial/retail premises.....	205
Table 33	On site bicycle parking for commercial/retail premises	205
Table B1	Preferred Species for General Planting	231
Table B2	Preferred Species for Street Tree Planting	239

1.0

Introduction



1.0 INTRODUCTION

1.1 Name of this Plan

This Plan is known as the Box Hill Growth Centre Precincts Development Control Plan 2018 (DCP 2018). It has been prepared pursuant to the provisions of Section 74(C)(2) of the *Environmental Planning & Assessment Act 1979* (EP&A Act).

This DCP 2018 applies to all development on the land shown at **Figure 1**.




Figure 1 Land to which this DCP applies

1.2 The Purpose of this DCP

The purpose of this DCP is to:

- a. Communicate the planning, design and environmental objectives and controls against which The Hills Shire Council (Council) will assess future Development Applications (DAs);
- b. Consolidate and simplify the planning controls to ensure the orderly, efficient and environmentally sensitive development of the Box Hill Growth Centre Precincts as envisaged by the North West Sector Structure Plan and refined by the Box Hill Growth Centre Precincts Indicative Layout Plan;
- c. Promote high quality urban design outcomes within the context of environmental, social and economic sustainability;
- d. Clearly set out the processes, procedures and responsibilities for the involvement of the community and key stakeholders in the development of land;
- e. Ensure that development will not detrimentally affect the environment and ensure that satisfactory measures are incorporated to ameliorate any impacts arising from the proposed development;
- f. Encourage innovative and imaginative design with particular emphasis on the integration of buildings and landscaped areas that add to the character of neighbourhoods; and
- g. Provide safe and high quality environments for the residents, workers and visitors of Box Hill Growth Centre Precincts.

1.3 Relationship to other Plans

This section should be read in conjunction with *State Environmental Planning Policy (Sydney Region Growth Centres) 2006* (Growth Centres SEPP) and other relevant State planning policies. This DCP should also be read in conjunction with the following State and Council policies and/or guidelines:

- Environmental Planning and Assessment Act 1979 (NSW) (as amended)
- Environmental Planning and Assessment Regulation 2000 (NSW) (as amended)
- Environmental Planning and Assessment Regulation 2010
- Local Government Act 1993 (NSW) (as amended)
- Threatened Species Conservation Act 1995 (NSW) (as amended)
- Relevant SEPPs
- Planning for Bushfire Protection 2006 (NSW Rural Fire Service 2006) (as amended)
- Safer By Design Guidelines (BHSC 2002)
- Design Guidelines Subdivision/Development (THSC 2011)
- Specification for the Construction of Footpath & Gutter Crossings (THSC 2010)
- Floodplain Development Manual (Department of Planning, Infrastructure and Natural Resources 2005)
- Better Urban Living – Guidelines for Urban Housing in NSW (Urban Design Advisory Service 2000)
- Growth Centres – Development Code (Growth Centres Commission 2006)
- Order to confer Biodiversity Certification on the State Environmental Planning Policy (Sydney Region Growth Centres) 2006 (December 2007)
- Draft Growth Centres Conservation Plan (January 2007)

Provisions from the following sections of The Hills Development Control Plan 2012 apply:

- The Hills Development Control Plan 2012 Part B - Section 5 Residential Flat Buildings
- The Hills Development Control Plan 2012 Part B – Section 6 Business
- The Hills Development Control Plan 2012 Part C – Section 1 Parking
- The Hills Development Control Plan 2012 Part C – Section 2 Signage
- The Hills Development Control Plan 2012 Part C – Section 3 Landscaping
- The Hills Development Control Plan 2012 Part C – Section 5 Telecommunications Facilities
- The Hills Development Control Plan 2012 Part C – Section 6 Flood Controlled Land.

In the event of any inconsistency between this DCP and any other DCP or policy of Council, this DCP will prevail to the extent of the inconsistency.

1.4 Structure of this Plan

This DCP is structured as follows:

Section 1	Introduction Sets out the aims and objectives of the DCP, identifies the land to which the DCP applies, explains the structure of the document, the relationship of the DCP to other planning documents, and explains procedures for exempt and complying development and submitting a development application.
Section 2	Vision and Character Relates to the overall layout and vision for the future development of the Precincts as well as the controls for character areas including town centres, employment areas and residential density.
Section 3	Land Development Relates to the street network including road design standards, the public transport network and the pedestrian and cycleway network, public realm including parks, street planting, signage, street furniture, lighting, public art and utilities as well as residential subdivision, integrated housing development, residue lots and the subdivision process.
Section 4	Residential Development Establishes the objectives and controls that guide residential development, including dwelling houses, semi-detached, attached and abutting dwellings, multi unit housing, secondary and studio dwellings, dual occupancies, manor homes, residential flat buildings and shop top housing. Also covers residential amenity controls such as streetscape, safety, privacy, sustainable building design and fencing. This section also contains controls applying to non-residential development in residential zones, such as child care centres, neighbourhood shops, schools and community uses.
Section 5	Additional Controls for Certain Dwelling Types Establishes additional objectives and controls to guide development of attached or abutting dwellings, secondary dwellings and studio dwellings, dual occupancies, multi dwelling housing, residential flat buildings, manor homes and shop top housing, and non-residential development types within residential zones.
Section 6	Employment Areas Relates to built form development controls for the employment areas, including lot subdivision, built form, building layout and orientation, streetscape, landscape design, access and parking, safety and surveillance.
Section 7	Managing the Environment Outlines objectives and development controls relating to management of general environmental issues occurring across the precincts.
Section 8	Special Area Controls Outlines the objectives, key controls and design principles relating to areas that require further design attention including Box Hill Town Centre, Mt Carmel Village, Box Hill Inn Village, Nelson Road Village and Neighbourhood Centres.
Appendix A	Glossary Explains the terms used in the DCP.
Appendix B	List of Preferred Plant Species Identifies trees that are subject to the tree preservation provisions of the Precinct Plans, and provides a list of plant species that are preferred for use in landscaping within the Precinct.
Appendix C	Materials and finishes colour palette

1.5 Development

The following information about the different types of development is provided as a guide. Refer to the Growth Centres SEPP for definitions.

Development falls into a number of categories: Exempt Development, Complying Development, Local Development, Integrated Development and Designated Development.

1.5.1 Exempt and Complying Development

For exempt and complying development refer to *State Environmental Planning Policy (Exempt and Complying Development) 2008*.

1.6 Advertising & Notification Procedures

The purpose of this section is to establish a clear process for public participation in the development assessment process. The notification procedures outlined below aim to balance the public's right to participate in the development assessment process whilst minimising delays in the processing of low impact development applications.

1.6.1 Mandatory Advertising/Notification

Planning legislation requires some developments to be advertised in a local newspaper and/or notified to adjoining property owners and relevant public authorities. These types of developments are generally larger scale and/or require approval from one or more public authorities.

Applications which require advertising/notification under legislation are identified below and, if applicable are required to pay an advertising fee at the time of lodgement in accordance with Council's Fees and Charges:

- Nominated Integrated Development
- Threatened Species Development
- Class 1 or Class 2 Aquaculture Development
- Designated Development
- State Significant Development

1.6.2 Notification of Development Applications

Written notification to owners of adjoining and adjacent properties will be undertaken for local development that is permissible with consent except for where identified in **Section 1.6.4** Circumstances Where Notification is not Required.

Council may also notify additional landowners in the vicinity of a development site, if it is considered the application may have a greater impact. In determining whether to extend or limit the extent of notification the following factors may be considered:

- Siting and design
- Views
- Visual and acoustic privacy
- Access
- Overshadowing
- Public interest
- Topography
- Solar access
- Drainage
- Landfill
- Traffic generation

1.6.3 Notification Timeframes

The notification period for local development is to be a minimum period of 14 days however may be reduced to 7 days in special circumstances. The period of time may also be extended depending on the circumstances of the case. Timeframes for Mandatory Advertised Development is specified in legislation however it is generally 30 days, commencing on the day after which the notice of the application is first published in a newspaper. Any notification period shall not include the last week of December and the first week of January in any year.

1.6.4 Circumstances where Notification is not Required

No notification of adjoining and adjacent properties is required for the following types of development applications, if the proposal complies with all applicable development controls (LEP, DCP & other relevant policies) and/or it is considered by Council that the development is unlikely to have a detrimental impact on those properties:

- New rural sheds ancillary to residential use
- New rural fencing
- New tennis courts ancillary to residential use
- Strata subdivisions
- Subdivisions to adjust property boundaries where no additional lots are created
- Where the development site does not adjoin a residential property

Where a development application is not notified by Council in accordance with the above provisions, adjoining and adjacent property owners will be sent a courtesy letter advising that an application has been received that is in accordance with the requirements of the development control plan. The letter will state Council will not be formally notifying or inviting submissions for the application which will be determined within the requirements of the *Environmental Planning and Assessment Act, 1979* no sooner than 14 days from the date of the letter.

1.6.5 Conciliation Conferences

If more than 10 submissions are received relating to a development application during a formal notification period, Council will host a conciliation conference. All conferences are chaired by the Mayor or the Mayor's nominee.

1.7 Development Application Process

The Hills Shire Council is the consent authority in respect of approvals to develop land (except complying development where private certification of development can occur). The development application process is summarised in **Table 1**.

Initial discussions with Council's Duty Planning Officer, Duty Building Surveyor or Duty Subdivision Officer, will help determine whether your proposal is permitted under the Growth Centres SEPP and the type of application required. Council may be contacted on 9843 0555.

VARIATIONS TO DEVELOPMENT CONTROLS

Council may grant consent to a proposal that does not comply with the DCP, providing the intent of the controls is achieved. Similarly, Council may grant consent to a proposal that varies from the Indicative Layout Plan (ILP), where the variation is considered to be minor and the proposal remains generally consistent with the ILP. As such, each Development Application will be considered on its merits. Where a variation is sought it must be justified in writing indicating how the development is consistent with the relevant objective(s) and the intention of the control to be varied and/or is generally consistent with the ILP.

PRE-LODGEMENT

Initial discussions with Council's Duty Planning Officer will help determine whether your proposal is permitted and the type of application required.

For small-scale development an informal pre-lodgement meeting with the Duty Planning Officer at Council's Customer Service Centre should be held to identify relevant issues. It is not necessary to book an appointment. Single residential developments and ancillary construction issues should be discussed with Council's Duty Building Surveyor and subdivision and engineering related enquires directed to Council's Duty Subdivision Officer.

Applicants are required to demonstrate that an appropriate planning process has been undertaken. To ensure that this process is recognised, applicants are required to attend a pre-lodgement meeting to discuss concept plans and any other issues relevant to the site before formal lodgement of the development application.

Generally, developments comprising anything other than application for detached dwellings require a formal pre-lodgement meeting. Specifically a formal pre-lodgement meeting is required prior to the submission of all major development applications for the following types of development:

- major residential;
- light industrial;
- commercial;
- subdivision applications;
- development proposals which exceed \$1 million in development costs;
- designated development; and
- telecommunications facilities.

Arrangements for a pre-lodgement meeting can be made at the Customer Service Centre of Council's Administration Building or by telephoning 9843 0555.

Table 1 Development Application Process

Process	Matters to be considered
Consultation with adjoining property owners should be considered	Consider their opinions
Mandatory consultation with Council on draft proposal	Discussion with Duty Town Planner, Duty Building Surveyor, Duty Subdivision Officer or formal Pre-lodgement
Finalise Application and consult with relevant authorities e.g. RMS, Sydney Water	Does proposal comply with Environmental Planning Instruments
Lodge Development Application with Council	Pay Fees
Referral to relevant agencies, notification and advertisement occurs – Refer to Section 1.6	Council notifies adjoining property owners and relevant agencies
Assessment of application against relevant planning instruments and DCPs, and consideration of submissions	Conciliation conference may be required
Development/Subdivision determination (Consent/Refusal)	
Development work can commence if all conditions are complied with and Construction Certificate obtained	Pay Section 94 Contributions to Council
Final Plan of subdivision released upon completion of construction and compliance with all conditions of consent	Pay Section 94 Contributions to Council

1.8 Information required for a Development Application

1.8.1 Development Application Form

All development applications must be accompanied by a completed Development Application Form for Development Consent / Construction Certificate and/or Other Approval.

OWNERS CONSENT

The consent of all owners of the property must be lodged with the development application. If the owner is a Company (a list of all Directors is required) or Owners Corporation, its Common Seal must be stamped over the signature/s, otherwise the Managing Director must sign and clearly indicate the A.C.N.

DEVELOPMENT APPLICATION FEES

All relevant fees must be paid upon lodgement of the Development Application.

STATEMENT OF ENVIRONMENTAL EFFECTS

A Statement of Environmental Effects (SEE) is the written covering documentation, which must accompany your development application. Details must include:

- A description of the site including a property description;
- A description of the proposed development including all proposed works;
- Details of compliance with the Growth Centres SEPP and any of its amendments;
- A description of how the development controls have been achieved or provide written justification to vary any development standard contained in the DCP; and
- Details of how the development satisfies the provisions of Section 79C of the EP&A Act 1979.

The following plans, studies, assessments and/or reports may also be required to accompany a development application. All plans shall include the name and contact telephone number of the person who prepared the plans. A list of minimum requirements to be submitted for each application is provided in the Matrix of Lodgement Requirements.

Two (2) copies of all plans and documentation required with an application are to be submitted with a development application, unless otherwise specified within this DCP.

All hard copy Development Applications lodged with Council are required to be accompanied by a CD, DVD or USB drive with electronic files containing all documentation. This requirement also applies to the submission of revised information during the development assessment process. In instances where such documentation is not provided in an electronic format a scanning fee in accordance with Council's Fees & Charges will be charged.

1.8.2 Documentation

A development application must be accompanied by plans which accurately reflect the layout and scale of the development proposal and a SEE which will be discussed at the pre-lodgement meeting. The type of plans depend on the land use proposed and its complexity and generally includes: a site survey/analysis plan, site plan, floor plan, elevations and cross sections, landscape plan, shadow diagrams (two storey development and as otherwise specified). The preliminary plans are to include an Isometric raised plan of proposal for residential flat buildings and attached and multi dwelling housing developments. Relevant consultants and advisors used by the applicant should also attend these meetings.

Table 2 outlines documentation that is required and documentation that may be required to be lodged as part of the development application for various types of development. **Table 3** describes in detail what is required in the preparation of each type of document mentioned in **Table 2**. This does not limit the ability of Council to require any other documentation dependent on the nature of the development and the characteristics of the site to adequately inform the merit based assessment.

Table 2 Matrix of Lodgement Requirements

Key :

✓ - Required

■ - Possibly required – Pre lodgement discussion required

	Subdivision	Dwelling house, Dual Occupancy and Semi-detached dwellings	Attached dwellings and Multi Dwelling Housing	Residential Flat Building	Commercial/Retail Premises	Light Industrial	Home Business	Open Space and Landscape	Heritage Item
Access Report			✓	✓	✓				
Architectural Plans	✓	✓	✓	✓	✓	✓	✓	✓	✓
Asbestos Management Plan	■	■	■	■	■	■	■	■	■
BASIX Certificate		✓	✓	✓					
Building Envelope Plan	■								
Bushfire Assessment	■	■	■	■	■	■	■	■	■
Construction Noise and Vibration Management Plan		✓	✓	✓	✓	✓			
Contamination Assessment	✓	✓	✓	✓	✓	✓	✓	✓	✓
Crime Risk Assessment Report	■		✓	✓	✓			✓	
Earthworks Plan	✓					✓			
Economic Analysis					■				
Emergency Evacuation Plan	✓								
Erosion and Sedimentation Control Plan	✓	✓	✓	✓	✓	✓			■

	Subdivision	Dwelling house, Dual Occupancy and Semi-detached dwellings	Attached dwellings and Multi Dwelling Housing	Residential Flat Building	Commercial/Retail Premises	Light Industrial	Home Business	Open Space and Landscape	Heritage Item
Flora and Fauna Assessment	■					✓			
Fuel Management Plan	✓								
Geotechnical Assessment	■	■	■	■	■	■	■	■	■
Heritage Impact Statement	■	■	■	■	■	■	■	■	■
Indigenous Archaeological Assessment	✓								
Landscape Plan	■	✓	✓	✓	✓	✓	■	✓	✓
Landscape Management Statement	■		■	■		■			
Loading Facilities					✓	✓			
Model			■	✓	■				■
Noise Impact Analysis (Acoustic Report)	■	■	■	■	✓	✓	■	■	■
On-site Detention (OSD) Plan	✓	■	■	■	■				
Photo Montage			✓	✓	✓				■
Public Domain Plan	■								
Preliminary Engineering Drainage Plans	✓	■	✓	✓	✓				■
Schedule of external materials		✓	✓	✓	✓	✓			✓
Services	✓	✓	✓	✓	✓	✓			✓

	Subdivision	Dwelling house, Dual Occupancy and Semi-detached dwellings	Attached dwellings and Multi Dwelling Housing	Residential Flat Building	Commercial/Retail Premises	Light Industrial	Home Business	Open Space and Landscape	Heritage Item
Shadow Diagrams		✓	✓	✓	✓	■	■		■
Signage Plan					✓	✓	✓		■
Site Plan	✓	✓	✓	✓	✓	✓	✓	✓	✓
Site Survey or Analysis Plan	✓	✓	✓	✓	✓	✓			✓
Statement of Environmental Effects	✓	✓	✓	✓	✓	✓	✓	✓	✓
Streetscape Perspective		■	✓	✓	✓	✓			✓
Traffic and Car Parking Study	✓			✓	✓	■			
Tree Management Plan	■	■	■	■	■	■		✓	■
Vegetation Management Plan	✓	■	■	■	■	■	■	■	■
Waste Management Plan	■	✓	✓	✓	✓	✓	✓		■

Key : ✓ - Required

■ - Possibly required – Pre lodgement discussion required

Table 3 Description of documentation

ACCESS REPORT	<p>An Access Report shall be prepared by a registered access consultant demonstrating compliance with the <i>Disability Discrimination Act 1992</i> (Cth) and relevant Australian Standards such as AS1428.1-2001, AS1428.2-1992, AS1428.3-1992 and AS1428.4-2002.</p> <p>A certification prepared by a registered access consultant must confirm that units identified as 'adaptable' in Multi Dwelling Housing and Residential Flat Buildings are capable of being modified.</p>
ARCHITECTURAL PLANS	
FLOOR PLAN	The internal layout of all buildings is to be illustrated on floor plans. Floor plans are to contain dimensions and floor areas for each room, window locations and other relevant internal building details.
CROSS SECTION	At least one longitudinal and one transversal cross section should be provided for buildings and/or open spaces indicating the relationship of the natural ground with existing and proposed levels.
ELEVATION PLAN	<p>The external appearance of all aspects (north, south, east, west) of a building are to be illustrated on the elevations to a minimum scale of 1:200.</p> <p>Details of the relationship of elevations to natural ground level indicating:</p> <ul style="list-style-type: none"> • Existing and proposed levels; • Proposed cut and fill; and • Fencing details fronting public streets.
BASIX CERTIFICATE	Submission of a current BASIX Certificate is required for any development to which BASIX applies. See www.basix.nsw.gov.au for further information.
BUILDING ENVELOPE PLAN	Submission of a Building Envelope Plan is required with development applications for subdivision of lots less than 300m ² and equal to or greater than 225m ² in area, and with a width equal to or greater than 9m. Refer to Section 3.2 .
BUSHFIRE ASSESSMENT	<p>Development applications for land identified as bush prone in accordance with the Council's Bushfire Prone Land Map will be prepared in accordance with <i>Planning for Bushfire Protection 2006</i> (NSW Rural Fire Service 2006).</p> <p>The Bushfire Assessment must include the following:</p> <ul style="list-style-type: none"> • Review the capability of the site to provide a safe development in accordance with <i>Planning for Bushfire Protection 2006</i>; • Review the potential to carry out hazard management over the landscape; • Review the evacuation capability of the area; • Provide advice on the adequacy of the design/construction to meet the requirement of Planning for Bushfire Protection 2006; and • Provide an emergency evacuation plan.

CONSTRUCTION NOISE AND VIBRATION MANAGEMENT PLAN (CNWMP)	<p>A Construction Noise and Vibration Management Plan should include:</p> <ul style="list-style-type: none"> • details of construction activities and an indicative schedule for construction works; • identification of nearby residences and other sensitive land uses, and the relevant noise management levels and blasting and vibration goals; • identification of construction activities, including ancillary activities, that have the potential to generate noise and/ or vibration impacts on surrounding land uses, particularly residential areas and heritage items; • an assessment of noise and vibration impacts on receivers; • detailed examination of reasonable and feasible actions and measures that would be implemented to minimise noise and vibration impacts (including negotiated agreements); • a description of how the effectiveness of these actions and measures would be monitored during the proposed works, clearly indicating how often this monitoring would be conducted, the locations where monitoring would take place, how the results of this monitoring would be recorded and reported; and, if any exceedance is detected how any non-compliance would be rectified; and • strategies to promptly deal with and address noise and vibration related complaints. <p>The following policies, guidelines and Standards should be referenced where relevant:</p> <ul style="list-style-type: none"> • DECCW 'Interim Construction Noise Guideline' (ICNG) • DECCW's 'Assessing Vibration; A Technical Guideline', February 2006 • British Standard 7385: Part 2 'Evaluation and measurement of vibration in buildings' • German standard DIN 4150 - Part 3 - 'Structural vibration in buildings - Effects on Structures'. • NSW State Environmental Planning Policy (Infrastructure) 2007 (ISEPP) • NSW Department of Planning 'Development Near Rail Corridors and Busy Roads - Interim Guideline' (the ISEPP Guideline) • NSW 'Environmental Criteria for Road Traffic Noise' (ECRTN) DECCW 1999 • AS2107:2000 'Acoustics – Recommended design sound levels and reverberation times for building interiors'
CONTAMINATION ASSESSMENT	<p>A geotechnical site contamination assessment shall be prepared by a suitably qualified consultant for all sites in the Box Hill and Box Hill Industrial Precincts. An assessment is required to identify whether the site is suitable for its intended purpose, including human occupation and any remediation measures. A review of the Land Capability, Salinity and Contamination Assessment Box Hill and Box Hill Industrial Precincts prepared by WSP Environment and Energy will be required as part of the assessment.</p>
CRIME RISK ASSESSMENT REPORT	<p>Certain developments due to their size, function or location may require the submission of a Crime Risk Assessment report and will be</p>

	<p>referred to NSW Police for comment. These types of developments include, but are not limited to:</p> <ul style="list-style-type: none"> • Transport facilities; • Residential flat buildings, attached dwellings and multi dwelling housing developments (50 or more dwellings); • Large mixed use developments (50 or more dwellings); • Major shopping centre developments; • New industrial complexes (multiple units/ major works); • New schools and hospitals; • Child care centres; • Large sport facilities; • Clubs and hotels; and • Service stations, convenience stores and other high risk businesses. <p>A Crime Risk Assessment report should detail design and other measures to be incorporated into the development to reduce the potential for crime. To assist in preparation of a Crime Risk Assessment report applicants should refer to Hills Shire Council's Designing Safer Communities: Safer by Design Guidelines (June 2002).</p>
EARTHWORKS PLAN	<p>An Earthworks Plan is to be prepared by a suitably qualified consultant. The Plan should show the existing and proposed level/contours.</p>
EMERGENCY EVACUATION PLAN	<p>The Emergency Evacuation Plan will include the following:</p> <ul style="list-style-type: none"> • Identify the ability for areas to be evacuated within acceptable time frames; • Define an integrated procedure for the evacuation of residents from premises in the event of a bushfire or flood event; • Identify appropriate evacuation assembly points and protected safe havens; and • Provide for the evacuation and care of infirm or elderly residents.
EROSION AND SEDIMENTATION CONTROL PLAN	<p>An Erosion and Sediment Control Plan is to be prepared in accordance with "Managing Urban Stormwater – Soils and Construction", produced by the NSW Department of Housing and Landcom. An Erosion and Sediment Control Plan shall include:</p> <ul style="list-style-type: none"> • locality of the site, north point and scale; • existing contours with catchment boundaries; • description and location of vegetation; • staging of works to minimise disturbance; • movement of water onto, through and off the site; • location of specific controls; • maintenance of the controls; • rehabilitation/maintenance of the works area; and • location of topsoil stockpile to be reused on-site.

FUEL MANAGEMENT PLAN	<p>The fuel management plan is to be prepared for lots where existing vegetation is required to be managed by several registered proprietors, strata corporation or community association or cluster style developments that jointly share asset protection zones. This plan may also be required for land that is:</p> <ul style="list-style-type: none"> • Subject to occupation by residents or designated as private property; • Intended for imminent development; i.e. Village style development; • Regularly managed land due to neighbouring responsibilities; or • Special habitat management that is subject to prescriptive burning requirements to maintain a desired level of habitat diversity. <p>The Fuel Management Plan will address the main priorities of fuel management planning, i.e.:</p> <ul style="list-style-type: none"> • The protection of lives and property; and • The protection of the ecological (plants and animals) and environmental elements (soil, water and air) of the landscape. <p>In determining priorities for fuel management, the land managers have a clear community obligation to protect life and property, as well as valuable natural assets.</p> <p>The Fuel Management Plan will identify:</p> <ul style="list-style-type: none"> • Hazard reduction (burning and physical removal) to protect life and property; • Hazard reduction (burning and physical removal) to protect the broad range of vegetation resources and assets from the effects of uncontrolled wildfire; and • Infrastructure works that allow fuel management to occur (e.g. construction and maintenance of fire trails).
GEOTECHNICAL ASSESSMENT	<p>A geotechnical assessment shall be prepared by a suitably qualified consultant registered with the Institute of Engineers, Australia or similar professionally recognised affiliation. An assessment is required to:</p> <ul style="list-style-type: none"> • identify that an acceptable level of risk is achieved with respect to the likelihood of movement, landslip or other geotechnical hazard adversely affecting the proposed subdivision or development or being caused by the proposed subdivision or development.
HERITAGE IMPACT STATEMENT	<p>A Heritage Impact Statement should be prepared in accordance with the Statement of Heritage Guidelines prepared by the Heritage Office and Department of Urban Affairs & Planning 1996, revised 2002.</p>
INDIGENOUS ARCHAEOLOGICAL ASSESSMENT	<p>An Indigenous Archaeological Assessment will be prepared to assess the impact of proposed development on areas identified as of Aboriginal archaeological significance in Part 6.2 of this DCP. The Indigenous Archaeological Assessment shall provide details of the ongoing management of areas of Aboriginal archaeological significance, including a conservation management plan outlining how these areas will be conserved. The assessment shall be prepared in consultation with relevant local Aboriginal groups.</p>

LANDSCAPE PLAN

A landscape plan to a minimum scale of 1:200 and accompanying documentation is to be prepared by a suitably qualified landscape architect or horticulturalist. Details to be provided include:

- site boundaries and dimensions surveyed;
- north point, scale (1:200 desirable);
- existing and proposed levels;
- all existing trees, grassed areas, landscape features and main structures on the site (buildings, car parking, driveways, walls, fences (location, height and type), paving, storage areas, elements contributing to the significance of a heritage item);
- a schedule of proposed planting, including botanic name, common name, expected mature height and staking requirements;
- details indicating a minimum of 300mm of good quality topsoil to all garden beds;
- details indicating a minimum of 150mm of good quality topsoil to all open space areas;
- all garden bed areas to be clearly defined by brick, concrete or timber edging with its top edge finishing flush with the surface of adjacent grass areas; and
- name and contact telephone number of the person who prepared the plans.

Also, where relevant, the landscape plan should address:

- outdoor recreation, seating or lunch areas for commercial and retail developments or the like;
- all proposed structures – buildings, fences, boundary lines, retaining walls and parking spaces;
- overland drainage proposals and on-site detention;
- landscape treatment of building setbacks including mounding and screen planting;
- planting proposed for privacy screening;
- delineation of the principle area of private open space for each dwelling;
- provision for rain gardens;
- outline of all hard paved areas and materials to be used (including communal streets, driveways and paths) and identification of purpose. Consideration should also be given to the most likely routes taken by pedestrians, and sited accordingly;
- details of landscaping to garbage bin storage or standing areas;
- lighting for vehicle areas, cycle and pedestrian paths, and security;
- location of underground services;
- the requirements of other authorities such as water, electricity, telecommunications and gas, should be considered in the development of the landscape proposal;
- protection of high conservation value vegetation and threatened flora and fauna habitat and hollow bearing trees;
- protection and restoration of designated riparian zones;
- fuel management for asset protection purposes;

	<ul style="list-style-type: none"> • maximum tree density and understorey cover to the standard of the required asset protection zones; • planting of key endemic foraging species for threatened fauna; and • planting of regional significant flora species.
LANDSCAPE MANAGEMENT STATEMENT	A Landscape Management Statement is to accompany the landscape plan for all developments other than where only private open space is proposed. The Landscape Management Statement is to provide the intended management and maintenance principles for non-private, community or common open space, including grassed areas, ornamental and native planting, water features, play equipment, outdoor furniture and other facilities.
LOADING FACILITIES	Plans and details are to be provided that demonstrate that the loading dock facilities are adequate to serve the development.
MODEL	As required by Table 2 a scale model at either 1:100 or 1:200 of the proposed development is to be provided. The model shall show development on immediately adjoining properties.
NOISE IMPACT ASSESSMENT (ACOUSTIC REPORT)	<p>A noise impact assessment or acoustic report is to be undertaken by a suitably qualified acoustic consultant (e.g. a member of the Australian Acoustical Society, Engineers Australia, The Association of Australian Acoustical Consultants or a person with appropriate professional qualifications).</p> <p>For noise generating development an acoustic report should include:</p> <ul style="list-style-type: none"> • description of the extent of the noise impact and all noise sources (e.g. number of vehicle movements, plant & equipment used etc.); • determination of the background (L_{A90}) and ambient (L_{Aeq}) noise levels (refer to DECCW INP Appendix B); • noise criteria, relevant guidelines or policy that has been applied and site specific noise goals; • site plan (with dimensions) not necessarily to scale; • Sound Power Level or appropriately defined sound pressure levels of all noise sources (specified in Octave bands); • prediction methods with formulae; • predicted noise levels at all relevant receiver points, including future development identified within the ILP; • comparison of predicted results to the noise goals; and • recommendations for noise control and attenuation. <p>For noise sensitive development an acoustic report should include:</p> <ul style="list-style-type: none"> • description of the noise sources impacting the site (e.g. road traffic noise, rail, aircraft noise, industrial noise etc.); • determination of the extent of noise from the relevant sources in accordance with relevant policy requirements (e.g. DECCW Environmental Criteria for Road Traffic Noise (ECRTN), ISEPP etc.); • where measurements of relevant noise cannot be carried out, undertake appropriate predictions of existing and/or future noise exposure on the site; • noise criteria, relevant guidelines or policy that has been applied and site specific noise goals;

	<ul style="list-style-type: none"> • predicted noise levels at all relevant receiver points; • comparison of predicted results to the noise goals; and • recommendations for noise control and attenuation. <p>The following policies, guidelines and Standards should be referenced where relevant:</p> <ul style="list-style-type: none"> • NSW Protection of The Environment Operations Act 1997 (POEO Act) • NSW Protection of the Environment Operations (Noise Control) Regulation 2008 • NSW State Environmental Planning Policy (Infrastructure) 2007 • NSW Department of Planning 'Development Near Rail Corridors and Busy Roads - Interim Guideline' (the ISEPP Guideline) • NSW 'Environmental Criteria for Road Traffic Noise' DECCW 1999 • AS2107:2000 'Acoustics – Recommended design sound levels and reverberation times for building interiors' • NSW 'Industrial Noise Policy' EPA (now DECCW) 2000 • AS2021 'Acoustics - Aircraft noise intrusion – Building siting and construction' • The Hills Development Control Plan 2012 Part B Section 6 – Business (Appendix E) • Office of Liquor Gaming and Racing's (OLGR) 'Standard Noise Condition' • DECCW 'Interim Construction Noise Guideline' (ICNG) • DECCW Noise Guideline for Local Government October 2010 • DECCW's 'Assessing Vibration; A Technical Guideline', February 2006 • British Standard 7385: Part 2 'Evaluation and measurement of vibration in buildings' • German standard DIN 4150 - Part 3 - 'Structural vibration in buildings - Effects on Structures'
ON-SITE DETENTION (OSD) PLANS	<p>OSD Plans are to be prepared in accordance with the Upper Parramatta River Catchment Trust OSD Handbook (with amended parameters reflective of the precinct wide stormwater management strategy referred to in Section 7.1) by a suitably qualified consultant possessing one of the following accreditations:</p> <ul style="list-style-type: none"> • National Professional Engineer Register in Civil Engineering (Institute of Engineers Australia); • Surveyors Certificate of Accreditation in OSD and Drainage Design (Institution of Surveyors of NSW and the Association of Consulting Surveyors NSW); or • Accreditation as a certifier under the EP&A Act 1979 (NSW) in the relevant discipline. <p>Reference should be made to J. Wyndham Prince Water Cycle Management Report 2012 for the Box Hill/ Box Hill Industrial Precinct. Referral should be made to the Dam Safety Committee as part of any future development application process.</p>
PHOTO MONTAGE	<p>The photo montage must indicate the appearance of the proposed development within the context of existing development and shall be no greater than A3 in size.</p>

PUBLIC DOMAIN PLAN	Applications for subdivision using approval pathways A2, B1 and B2 require a Public Domain Plan (PDP) to be submitted as part of the application. Refer to Section 3.2 .
PRELIMINARY ENGINEERING DRAINAGE PLANS	<p>Preliminary engineering plans indicating the proposed drainage design and infrastructure are to be prepared by a qualified drainage engineer. The plans shall include the following information:</p> <ul style="list-style-type: none"> • existing and proposed contours and levels (Australian Height Datum); • catchment plan including boundaries of the site and adjacent properties and any areas not able to drain to the On-site detention (OSD) system; • storage/flow calculations; • location and invert and surface level of all proposed pits, pipes and storage chambers; • High Early Discharge Control pit and orifice detail including levels and location; • proposed lawful point of discharge; and • location and extent of any floodway, overland flow path or drainage easements through the site.
SCHEDULE OF EXTERNAL MATERIALS	A schedule of the proposed external colours, including a sample of materials and finishes, description and location of colour/material in relation to the development, at a size no greater than A3. Details of alternative materials considered and reasons as to why proposed materials were selected are to be disclosed.
SERVICES	<p>Evidence of suitable arrangements with the following are required to be submitted with development applications:</p> <ul style="list-style-type: none"> • Sydney Water for potable and recycled water, sewage and drainage; • Telecommunications carrier for telephones and associated equipment; and • Integral Energy for underground electricity; Jemena for gas supplies.
SHADOW DIAGRAMS	<p>Shadow diagrams shall be submitted for all development which exceeds one storey in height and for light industry development where it adjoins residential development. Details to be shown on plans include:</p> <ul style="list-style-type: none"> • shadows cast by the proposal during mid-winter and summer (i.e. 21 June and 21 December); • shadows cast during the early morning, middle of the day and afternoon (9:00am, 12 noon and 3:00pm); • the impact of the proposal on adjoining residential properties and their open space areas, and open space areas of each dwelling within the proposed development; and • consideration of shadows from existing trees. <p>For the purpose of overshadowing requirements, fence lines are not included in shadow calculations.</p>
SIGNAGE PLAN	<p>A plan drawn to scale with the following information:</p> <ul style="list-style-type: none"> • site dimensions and area; • location of the proposed sign;


	<ul style="list-style-type: none"> • a diagram of the sign, including: <ul style="list-style-type: none"> – dimensions and area, height, construction materials, colour, wording, logos and symbols. <p>For illuminated signs, the following additional information is required:</p> <ul style="list-style-type: none"> • The type of illumination; • A light spill diagram; and • The hours of illumination.
SITE PLAN	<p>This plan is to convey the design concept and layout of the proposal. Details to be shown include:</p> <ul style="list-style-type: none"> • A scale of 1:100 or 1:200, a title and north point; • The site coverage depicting building envelopes, car parking, driveways and all other built features with supporting floor space ratio calculations; • The location of open space areas; • A schedule of calculations including site area, site coverage, floor areas and associated floor space ratios and private open space/landscape areas; • The dimensions and area of site; • The distance to all boundaries from buildings and car parking areas; • The internal layout of buildings; • The access and car parking arrangements including number of car parking spaces and bicycle parking spaces. (For light industry developments details of the proposed vehicular access and circulation, in particular vehicular movement, layout and turning circles must be provided); • The dimensions of all car parking spaces and driveway widths; • Any existing trees (and a notation to indicate whether they are to be removed or retained); • The location of service/ancillary facilities including easements and infrastructure; • The location and general description of any adjoining developments; • Building height and internal site levels; • Changes in levels – proposed spot levels and/or contours at 1m intervals; • The original ground level; and • The proposed finished ground level.
SITE SURVEY/ANALYSIS PLAN	<p>The purpose of this plan is to identify the opportunities and constraints presented by the development site. The plan must be prepared by a registered surveyor to a minimum scale of 1:200. The extent and level of detail of the analysis will depend on the application. Details to be shown include:</p> <p>A. The Site</p> <ul style="list-style-type: none"> • Site Dimensions: <ul style="list-style-type: none"> – Length, Width, Area • Topography: <ul style="list-style-type: none"> – Existing spot levels and/or contours at one metre intervals – Natural drainage

	<ul style="list-style-type: none"> - Any contaminated soils or filled areas - Any natural or man-made artefacts of archaeological significance • Services: <ul style="list-style-type: none"> - Easements, connections to drainage and utility services • Existing Vegetation: <ul style="list-style-type: none"> - Location - Height - Spread of established trees - Species - Existing threatened flora species - Existing threatened fauna habitat - Hollow bearing trees for hollow dependent fauna - All trees greater than 100 mm dbh - Significant foraging species as identified by Council and/or Consulting Ecologist • Fuel Management Zones: <ul style="list-style-type: none"> - Asset protection zones - Fuel reduction methods (hand removal, mechanical or managed landscaping) - Understorey conservation zones for threatened flora and fauna habitat (maximum 20% of understorey by cover) - Tree removal for creating discontinuous canopies (2-5 m separation) - Maximum tree density • Micro Climates: <ul style="list-style-type: none"> - Orientation, prevailing winds • The area of any land containing protected native vegetation as shown on the relevant SEPP maps • The location of existing buildings and other structures • Heritage features • Fences • Property boundaries • Pedestrian and vehicle access • Infrastructure • Views to and from the site • Overshadowing by neighbouring structures • Heritage features and items including archaeology contributing to significance – curtilage, views, archaeological features, outbuildings, garden elements etc. • Demonstration of how allotment/dwelling locations and dimensions respond to topography, site constraints and achieve solar orientation • An indication of how social and environmental issues have been considered in the design <p>B. The Surrounds</p> <p>Investigation of the surrounds should identify:</p> <ul style="list-style-type: none"> • Neighbouring buildings/developments: <ul style="list-style-type: none"> - Location, Height, Use, Type of construction materials
--	--

	<ul style="list-style-type: none"> • Privacy <ul style="list-style-type: none"> – Any adjoining private open space, windows overlooking the site (particularly those within 9 m of the site), location of any facing doors and/or windows • Walls built to the site's boundary: <ul style="list-style-type: none"> – Location, height, materials • Difference in levels between the site and adjacent properties at their boundaries • Views and solar access enjoyed by neighbouring properties • Street frontage features: <ul style="list-style-type: none"> – Poles, trees, kerb crossovers, bus stops, other services • The built form and character of adjacent development including: <ul style="list-style-type: none"> – Architectural character, front fencing, garden styles • Heritage features of surrounding locality and landscape • Direction and distance to local facilities: <ul style="list-style-type: none"> – Local shops, schools, public transport, recreation and community facilities • Public open space: <ul style="list-style-type: none"> – Location, use • Adjoining bushland or environmentally sensitive land • Source of nuisance: <ul style="list-style-type: none"> – Flight paths, noisy roads or significant noise source, polluting operations
SPECIES IMPACT STATEMENT	<p>A Species Impact Statement is to be prepared where development is on land containing critical habitat or is likely significantly affect threatened species, populations or ecological communities or if there is likely to be a significant impact on threatened fish or marine vegetation protected under the Fisheries Management Act 1994.</p> <p>A Species Impact Statement is to be prepared by a suitably qualified consultant. The Species Impact Statement must include a full description of the action proposed, including its nature, extent, location, timing and layout and, to the fullest extent reasonably practicable, the information referred to in Section 110 of the <i>Threatened Species Conservation Act 1995</i>.</p> <p>A Species Impact Statement is not required where development consent is required and on areas that have had biodiversity certification conferred.</p>
STREETSCAPE PERSPECTIVE	<p>A streetscape perspective shall be provided as a colour perspective of the proposed building(s) and streetscape including landscaping and be no greater than A3 in size.</p>
TRAFFIC AND CAR PARKING STUDY	<p>A traffic and car parking study must be prepared by a suitably qualified consultant. The traffic report must address the following:</p> <ul style="list-style-type: none"> • The existing traffic environment including recent traffic volume counts; • The traffic expected to be generated as a result of the proposed development; • The cumulative impact of the proposed development and any other nearby developments on the surrounding road network; • The need for traffic improvements to the road network as a result of the proposed development;

	<ul style="list-style-type: none"> • The impact of the proposal on intersections that access arterial/sub-arterial roads; • A detailed assessment of the proposed access arrangements including the suitability of the sight distance and any other relevant safety issues; and • An assessment of the proposed parking provision and layout.
TREE MANAGEMENT PLAN	<p>A Tree Management Plan is to be prepared by a qualified arborist. The Tree Management Plan shall be accompanied by a site plan clearly indicating which trees are to be retained and those to be removed. The Tree Management Plan shall include:</p> <ul style="list-style-type: none"> • A tree survey, including a site plan indicating the location of all trees on the site and the location of trees on adjoining properties located within close proximity of the development site. All trees should be numbered; • A schedule of all trees including species identification, dimensions, whether they are to be retained or removed and a rating of the condition of all trees, their health, aesthetic value and life expectancy as a basis for ascertaining their value for retention; • Justification for removal of any trees; • The design measures incorporated to allow trees to be retained and definitions of tree protection zones; • The design and construction techniques to be used to minimise the impact on trees to be retained. These measures must demonstrate that the on-going health of the tree has been considered; • Details indicating the position of trees in relation to proposed roads and building platforms; • Identification of hollow bearing trees and identify retention priority (High, Medium and Low quality) based on hollow dimensions and hollow dependent fauna habitat requirements; • A hollow retention strategy for any hollow bearing trees that balances the needs of hollow dependent fauna against the needs of providing a safe tree within or adjacent to buildings or services; and • An artificial hollow replacement strategy at a ratio of 2 artificial hollows to every 1 hollow removed on securely protected trees using a mix of nest box designs for a variety of fauna including microbats.
VEGETATION MANAGEMENT PLAN (VMP)	<p>Any subdivision within land identified as Riparian Corridor Protection Area, or residential sub-division on land adjacent to such an area will be required to be accompanied by a VMP and integrated with the required Landscape Plan, Bushfire Assessment, Sedimentation & Erosion Control Plan.</p> <p>The recommendations of the VMP will be imposed as conditions of any consent that may be issued.</p> <p>The following management principles are to be incorporated into a VMP consistent with NSW Office of Water guidelines for the corridor:</p> <ul style="list-style-type: none"> • The riparian corridor is to remain, or become vegetated, with native vegetation (trees, shrubs and groundcover species) according to the appropriate vegetation community. • Identify existing trees to be retained. • Indicate the location, type and size and all new plant species. • No battering is permitted within the riparian corridor unless within approved online detention areas.

	<ul style="list-style-type: none"> • The impact of salinity on the landscape and watercourses shall be managed in accordance with the Western Sydney Salinity Code of Practice. • The location of access ways to and within a riparian protection area must not compromise the environmental objectives for that watercourse or stream bed and/or bed stability and also be consistent with NSW State Government Guidelines (e.g. protection of fish habitat, water quality, waterway stability). • Measures to contain and attenuate low flow events (less than five years) are permitted providing they are fully vegetated and it can be demonstrated that the required environmental outcomes can be achieved. • Use piered crossings for Category 1 watercourses (other than for utilities) to maintain riparian connectivity. • Ensure vegetation in the CRZ is at a density that would occur naturally for the riparian ecotone.
WASTE MANAGEMENT PLAN (WMP)	<p>A WMP is to be prepared in accordance with the requirements identified in The Hills Development Control Plan Appendix A Waste Management Plan.</p> <p>A WMP demonstrates appropriate project management and construction techniques that minimise waste including the following:</p> <ul style="list-style-type: none"> • Re-use of topsoil and disposal of any excess to an approved site; • Green waste re-use in landscaping either on-site or off-site; • The re-use of materials such as bricks, tiles, plasterboard, windows, window frames, doors, joinery and concrete re-use on-site as appropriate, or recycled off-site; • The recycling of plumbing, fittings and metal elements; • The location of on-site storage facilities for material to be reused on-site, or separated for recycling off-site; and • The destination and transportation routes of all materials to be either recycled or disposed of off-site. <p>A WMP is to provide the following information:</p> <ul style="list-style-type: none"> • Construction and Demolition details <ul style="list-style-type: none"> – Types of waste to be produced; – Quantities of waste likely to be produced; – Re-use or recycling methods for waste either on-site or off-site; – Location of on-site storage facilities for waste materials; – Contractor and destination of all waste materials; – Demonstrate that waste going to landfill is not recyclable or is hazardous; and – A Waste Data File (a file containing the WMP together with records - waste receipts or dockets) of recycling and disposal of demolition and construction materials must be kept by the person/s responsible for the site. • Design of Facilities and On-going Management <ul style="list-style-type: none"> – Type of future use for the development; – Types of waste to be generated; – Estimated volume of waste to be generated per week;

- 
- Location (on plans) and description of on-site storage and/or treatment facilities for waste; and
 - Destination for waste produced.

For assistance with preparation of a Waste Management Plan, please contact Council's Waste Management Project Officer on 9843 0505.

1.9 Assessment of Applications

In assessing development proposals, Council will have regard to:

1. Section 79C of the EP&A Act 1979;
2. The Growth Centres SEPP;
3. Relevant State Environmental Planning Policies;
4. Conformity with this DCP;
5. Conformity with other Council Policies and guidelines;
6. Submissions received as a result of the notification/advertising process;
7. Any other legislation applying to the land or to the type of development proposed; and
8. Developments that fail to comply with the statutory provisions of the EP&A Act 1979 (NSW), any relevant SEPPs, or the objectives stated within this DCP are unlikely to be granted development consent.

1.10 Amendments

The Box Hill Growth Centre Precincts Development Control Plan came into force on March 2014 and has subsequently been amended as shown in **Table 4** below:

Table 4 DCP Amendments

Section	Description of amendment	Date amended DCP adopted	Date amended DCP came into force	Former file reference
3 and 4	New controls for residential development and subdivision (Housing Diversity Package)	13/08/2014	19/08/2014	
Various	Amend notification and advertising requirements to reflect The Hills Development Control Plan 2012 and minor administrative corrections	26/04/2016	24/05/2016	FP183
Various	Amendments relating to the rezoning of employment land and other administrative changes	25/08/2015	22/08/2016	6/2014/PLP
Various	Amendments relating to minimum lot size- Development Control Plan (Main Body)	29/11/2016	29/11/2016	
Various	Text and map changes to the following sections: 1.10 Amendments 2.2 Indicative layout plan 2.3 Precinct character areas 2.4 Sub-precincts 3.3 Movement network 3.4 Public domain works 5.6 Other development in residential areas 6.1 Lot subdivision 6.2 Built form 7.1 Integrated stormwater management 7.4 Bushfire hazard management 7.12 Riparian corridors and environmental conservation area 7.13 Noise and vibration 8.1 Centres			
Various	Amendments relating to shop top housing and mixed use developments and other administrative changes	13/12/2016		11/2016/PLP
2	Amendments relating to the construction and dedication of local roads.	08/06/2021	06/07/2021	FP171

2.0

Vision and Character



2.0 VISION AND CHARACTER

This section of the DCP describes the vision and objectives relating to the overall layout and character of the future development of the Precincts.

2.1 Vision and Development Objectives

VISION

The planning for the Box Hill Growth Centre Precincts promotes the development of a vibrant residential and employment urban area that responds to the Precincts' natural environment, represented in its streams, landform, heritage, environmental characteristics and landscape setting.

The planning of the Precincts seeks to promote a community that is less dependent on private vehicle use thereby contributes to a reduced carbon footprint.

A balanced mix and distribution of recreation, employment and residential uses encourage public transport, walking and cycling. A safe and permeable street network promotes accessibility, connectivity and social interaction.

Direct connections to nearby regional transport hubs, including the Rouse Hill, Riverstone, Area 20 and Schofields Road Transit Boulevard ensure regional public transport accessibility.

Retail and commercial areas complement and support surrounding centres. The centrally located Box Hill Town Centre provides the retail, commercial and community services that promote a community hub. Three villages and two neighbourhood centres service all local residential and employment areas.

A business park, an enterprise corridor and a light industrial area provide a mix of local and regional employment opportunities that meet the regional demand for jobs.

BOX HILL GROWTH CENTRE PRECINCTS OBJECTIVES

- a. To accommodate the future population, in a manner which responds to environmental constraints.
- b. To create strong pedestrian, public transport, cycleway and vehicular links with surrounding areas.
- c. To protect and enhance existing natural features.
- d. To create opportunities for the development of a variety of housing types and densities.
- e. To encourage higher densities along public transport corridors and areas of high amenity.
- f. To promote economically viable development.
- g. To create a layout plan that will assist in an equitable and manageable development process.
- h. To provide a hierarchy of centres as focal points for walkable neighbourhoods.
- i. To provide local employment areas for the North West Sector.
- j. To recognise the heritage significance of key heritage items and places.

2.2 Indicative Layout Plan

The Indicative Layout Plan (ILP) (**Figure 2**) illustrates the broad level development outcomes for the Box Hill Growth Centre Precincts. It outlines the development footprint, land uses, open space, heritage item, major transport linkages and location of community facilities and schools.

OBJECTIVES

- a. To ensure development of the Precincts is undertaken in a co-ordinated manner consistent with the North West Sector Structure Plan and the Box Hill Growth Centre Precincts Indicative Layout Plan.

CONTROLS

1. All development is to be undertaken generally in accordance with the Indicative Layout Plan at **Figure 2** subject to compliance with the objectives and development controls set out in this DCP.
2. Where variation from the ILP is proposed, the applicant is to demonstrate that the proposed development is consistent with the Vision and Development Objectives for the Precinct set out in Section 2 and the Objectives and Controls in Sections 3, 4, 5, 6 and 7 of this DCP and the Growth Centres SEPP.

AMENDMENTS

Amendments to the *State Environmental Planning Policy (Sydney Region Growth Centres) 2006* relocated Mount (Mt) Carmel Road further west to ensure a more workable road layout as the extent of required earthworks is greatly reduced. The new alignment has necessitated the amendment of adjacent land uses.

The adjustments of surrounding land uses are as follows:

- The Box Hill Inn Village Centre has subsequently been reallocated in order to maintain a central position to its residential trade catchment.
- The Mt Carmel Village Centre has been relocated so as to maintain a relationship between Mt Carmel Road and the Village Centre remains as per the 2014 ILP.
- The primary school site has been shifted to the north to accommodate the changed road network, an increase of 0.5 hectare (ha) for educational purposes as a result of the road realignment.
- Sports fields in the south of the Precinct are slightly shifted to the east and three local parks are relocated across the Precinct. There is an increase of 0.19 ha for public recreation as a result of the road realignment.
- Substation site removed as it is no longer required by Endeavour Energy.
- New roundabouts and bridges planned to support the relocation of Mt Carmel Road.

The updated version of Box Hill and Box Hill Industrial Precinct ILP and subsequent DCP maps show the updated changes to Mt Carmel Road and the surrounding land use locations.




Figure 2 Box Hill Growth Centre Precincts Indicative Layout Plan

2.3 Character Areas

Character Areas reflect the desired built form and landscape character of the area based on the physical and visual qualities of the natural landscape. They aim to give a distinct identity and sense of place for different areas within the Box Hill Growth Centre Precincts through specific built form, landscape and public domain controls (refer to **Figure 3**).

2.3.1 Centres

BOX HILL TOWN CENTRE

Box Hill Town Centre is located at the corner of Terry Road and Mason Road. It is located to the east of Terry Road and is dissected by the existing Mason Road. The existing Mason Road will be converted into a 'main street' to run through the centre of the town centre. A new by-pass road that takes away local traffic from the centre will be located to the north of the town centre to connect to Terry Road.

Box Hill Town Centre will provide the retail and community focus for the Box Hill Growth Centre Precincts, featuring a mix of residential, retail, commercial, community and recreational uses without undermining the retail offered at the Rouse Hill Town Centre.

The Town Centre comprises up to 30,000m² of shop front space which will contain one discount department store, two supermarkets, mini-majors and a range of specialty shops. (note: additional floor space for retail and commercial premises and/or other employment uses will be considered subject to an assessment of demand as part of any future application).

Residential uses are encouraged above the retail centre with a maximum height for the centre to be up to six storeys.

The town centre interface area on the western side of Terry Road is envisaged for offices and ancillary services such as child care centres and medical centres.

A passive recreation park for the Box Hill Town Centre, located between the Killarney Chain of Ponds and the southern steep slopes of Box Hill House, allows the retention of the view corridor towards Box Hill House while being close to the primary school and the residential areas.

BUSINESS PARK VILLAGE

The Business Park Village is located in the south-west of the Precincts at the intersection of Windsor Road and the proposed Mt Carmel Road. This village is positioned to service the business park as well as passing motorists along Windsor Road.

It is anticipated that the Business Park Village will contain a 3,000m² supermarket and 20-25 speciality stores.

MT CARMEL VILLAGE

Mt Carmel Village is located at the intersection of the proposed Mt Carmel Road and the proposed extension of George Street. The village is positioned to facilitate community focus and complement nearby community uses. The village comprises retail and a local park, which is directly adjacent to a medium density residential area. This village will service the northern area of the Precincts.

It is anticipated that the village centre will be approximately 5,000 to 6,000m² in size and contain a 2,000 – 3,000m² supermarket and 20-25 speciality stores.




Figure 3 Box Hill Growth Centre Precincts character areas

NELSON ROAD VILLAGE

The Nelson Road Village is located in the south-east of the Precincts at the intersection of Nelson Road and The Water Lane opposite heritage listed Marklye House. This Village will also have a strong relationship to the adjacent school and nearby playing fields, strengthening its role as a neighbourhood hub and meeting place for the local community. The Village will primarily service the south-eastern catchment area, including the employment corridor along Annangrove Road.

It is anticipated that the village centre will be approximately 5,000 to 6,000m² in size and contain a 2,000 – 3,000m² supermarket and 20-25 speciality stores.

NEIGHBOURHOOD CENTRES

The Precincts will include the potential for two neighbourhood centres that could be located on Boundary Road in the west of the Precincts and one on Old Pitt Town Road in the north-east. The Neighbourhood Centres will comprise up to 1,000m² of floor space and will service the local catchments and the passing traffic along these main roads.

WINDSOR ROAD BUSINESS PARK

The Windsor Road Business Park is characterised by six storey buildings that have good exposure to Windsor Road. Reduced heights of four storeys are located in the vicinity of the Box Hill Inn and in the Killarney Chain of Ponds.

The northern aspect and overlook to the Killarney Chain of Ponds and Box Hill House encourages a high quality built form.

ANNANGROVE ROAD EMPLOYMENT CORRIDOR

The Annangrove Road Employment Corridor is characterised by one to two storey buildings. The design controls promote the location of offices, show rooms and cafes close to the street front while ensuring that parking areas do not dominate the streetscape and can be located at the side boundaries.

Light Industrial sites fronting residential areas have a densely vegetated setback that retains remnant vegetation wherever possible. Building setbacks are increased to minimise noise and odour impacts to the residential areas.

2.3.2 Ridge

The Ridge Character Area is a residential area located along the main ridgelines running along Old Pitt Town Road.

The Ridge Character Area will have a predominately large lot residential zone, characterised by one or two storey detached housing with large setbacks. The large lot residential zone will allow the retention of the existing vegetation, the ridgeline formation and the existing views towards these ridges.

The Ridge Character Area provides a buffer between the higher density land uses in the Precinct and the rural land north of Old Pitt Town Road.

2.3.3 Historic View Corridor

The historic view corridor is located between Box Hill House and Rouse Hill House in the south-east of the Precincts. The area will be characterised by low density residential housing with wider streets that encourage heavily planted streetscapes.

The alignment of streets is perpendicular to Windsor Road to promote a dense tree canopy outlook from the heritage buildings. Appropriate tree planting will be used in this area to ensure development respects the character of this sensitive corridor.

Small lot housing is located along the Windsor Road boundary to assist in mitigating traffic noise by locating private open spaces away from the road.

A road parallel to Windsor Road provides setbacks to the houses fronting the road whilst facilitating a densely vegetated interface.

2.4 Sub-precincts

Development sub-precincts are areas bounded by fixed roads as indicated in **Figure 4**.

OBJECTIVES

- a. To allow departure from the Indicative Layout Plan; and
- b. To ensure that access, drainage and servicing is appropriately provided to all sub-precincts.

CONTROLS

An applicant may depart from the subdivision layout within a sub-precinct provided that:

1. The block layout and subdivision objectives and controls outlined in **Section 3.6** are met;
2. The level of access to fixed roads is retained;
3. The provision of drainage and service infrastructure is retained; and
4. Any variation from the Indicative Layout Plan does not limit the development potential for adjoining precincts to meet the objectives of the Indicative Layout Plan. This must be demonstrated by the submission of an indicative subdivision layout for adjoining affected properties.

VARIATIONS TO THE RESIDENTIAL STREET NETWORK

5. Where any variation to the residential street network indicated at **Figure 14** is proposed, the alternative street network is to be designed to achieve the following principles:
 - a permeable street network that is based on a grid system;
 - maximise connectivity across sub-precincts;
 - maximise connectivity between residential areas and community facilities, open space and centres;
 - encourage walking and cycling and reduce travel distances;
 - take account of topography and accommodate significant vegetation;
 - optimise solar access opportunities for dwellings;
 - provide frontage to and maximise surveillance of open space and riparian corridors;
 - provide views and vistas to landscape features and visual connections to nodal points and centres;
 - maximise the use of water sensitive urban design measures; and
 - minimise the use of cul-de-sacs. If required, the maximum number of dwellings to be served by cul-de-sac is 10.

NEIGHBOURHOOD BLOCK DESIGN

6. The size of the block must facilitate circulation on public streets through each sub precinct.
7. The subdivision layout is to create a legible and permeable street hierarchy that responds to the natural site topography, the location of existing significant trees and solar design principles.

8. Orientate blocks, wherever possible, to maximise the number of east, west and south facing lots and to minimise the number of narrow north facing blocks.
9. Variation in the size of the blocks is permitted provided that a regular layout of streets allows for ease of circulation, and that the number of streets as indicated in the Indicative Layout Plan (refer to **Figure 2**) is not reduced.
10. Maximum block lengths are not to exceed 250 metres.



3.0

Land Development



3.0 LAND DEVELOPMENT

3.1 Residential Density and Subdivision

The Growth Centres are subject to minimum residential density targets as detailed in the Residential Density Maps in the SEPP. This section provides guidance on the typical characteristics of the residential density target bands.

Net Residential Density means the net developable area in hectares of the land on which the development is situated divided by the number of dwellings proposed to be located on that land. Net Developable Area means the land occupied by the development, including internal streets plus half the width of any adjoining access roads that provide vehicular access, but excluding land that is not zoned for residential purposes. Refer to **Figure 5** and Landcom's "Residential Density Guide" and the Department of Planning and Environment's "Dwelling Density Guide" for further information.



Figure 5 Example for calculating Net Residential Density of a subdivision application

Net Residential Density is an averaging statistic. The average dwelling density target in the SEPP should be achieved across the identified area with a diversity of lot and housing types. However, this does not mean that all streets offer the same housing and lot mix. Built form intensity should vary across a neighbourhood in response to the place: more intense around centres or fronting parks, less intense in quieter back streets. In lower density areas, there will be a higher proportion of larger lots and suburban streetscapes but there may also be some streets with an urban character. In higher density areas, urban streets with more attached housing forms will be more common but there will also be some suburban streetscapes.

In recognition of different objectives and street characters at varying densities, certain built form controls vary by density bands. Refer to the Section 4.0 Residential Development.

3.1.1 Residential Density

Objectives

- a. To ensure minimum density targets are delivered.
- a. To provide guidance to applicants on the appropriate mix of housing types and appropriate locations for certain housing types.
- b. To establish the desired character of the residential areas.
- c. To promote housing diversity and affordability.

Controls

1. All applications for residential subdivision and the construction of residential buildings are to demonstrate that the proposal meets the minimum residential density requirements of the relevant Precinct Plan and contributes to meeting the overall dwelling target in the relevant Precinct.
2. Residential development is to be generally consistent with the typical characteristics of the corresponding Density Band in **Table 5**.

Table 5 Typical Characteristics of Residential Net Densities

Net Residential Density dw/Ha	Typical Characteristics
7 dw/Ha	<ul style="list-style-type: none">• Detached single and double storey dwelling houses on larger suburban lots.
10 - 12.5 dw/Ha	<ul style="list-style-type: none">• Generally located away from centres and transport.• Predominantly detached dwelling houses on larger lots with some semi-detached dwellings and / or dual occupancies.• Single and double storey dwellings.• Mainly garden suburban and suburban streetscapes. (See Figure 6).
15 -20dw/Ha	<ul style="list-style-type: none">• Predominantly a mix of detached dwelling houses, semi-detached dwellings and dual occupancies with some secondary dwellings.• Focused areas of small lot dwelling houses in high amenity locations.• At 20dw/Ha, the occasional manor home on corner lots.• Single and double storey dwellings.• Mainly suburban streetscapes, the occasional urban streetscape. (See Figure 6).
25 - 30 dw/Ha	<ul style="list-style-type: none">• Generally located within the walking catchment of centres, corridors and / or rail based public transport.• Consists of predominantly small lot housing forms with some multi-dwelling housing, manor homes and residential flat buildings located close to the local centre and public transport.• Generally single and double storey dwellings with some 3 storey buildings.• Incorporates some laneways and shared driveways.• Be designed to provide for activation of the public domain, including streets and public open space through the orientation and design of buildings and communal spaces.• Mainly urban streetscapes, some suburban streetscapes. (See Figure 6).
40+ dw/Ha	<ul style="list-style-type: none">• Generally located immediately adjacent centres and / or rail based public transport.• Consists of predominantly residential flat buildings, shop top housing, manor homes, attached or abutting dwellings and multi-dwelling housing.• Generally double and multi-storey buildings.• Predominantly urban streetscapes with minimal front setback; incorporates laneways and shared driveways. (See Figure 6).



Garden Suburban



Suburban



Urban

Figure 6 Distinct and coherent streetscapes occur in varying proportions in density bands

3. Residential development in the Ridge Area is to:

- Consist primarily of single dwellings on larger lots, reflecting the environmental sensitivity and visual character of these parts of the Precincts.
- Emphasise high quality housing design to make the most of the environmental characteristics of the surrounding area.
- Be designed and located to minimise impacts on flood prone land, and risks to property from flooding.
- Avoid impacts on Existing Native Vegetation and other remnant native vegetation.
- Consider relationships to adjoining land uses including public open space and drainage infrastructure.
- Be designed to respond to constraints from infrastructure corridors such as electricity lines, underground gas pipelines and any Sydney Catchment Authority infrastructure.
- Consider views to and from the land and surrounding parts of the Growth Centre.

4. Non-residential development in the residential areas is encouraged where it:

- Contributes to the amenity and character of the residential area within which it is located.
- Provides services, facilities or other opportunities that meet the needs of the surrounding residential population, and contributes to reduced motor vehicle use.
- Will not result in detrimental impacts on the amenity and safety of surrounding residential areas, including factors such as noise and air quality.
- Is of a design that is visually and functionally integrated with the surrounding residential area.

Note: The relevant Precinct Plan permits certain non-residential development within the residential zones. Other parts of this DCP provide more detailed objectives and controls for these types of development.

3.1.2 Block and Lot Layout

OBJECTIVES

- a. To establish a clear urban structure that promotes a 'sense of neighbourhood' and encourages walking and cycling.
- b. To efficiently utilise land and achieve the target dwelling yield for the relevant Precinct.
- c. To emphasise the natural attributes of the site and reinforce neighbourhood identity through the placement of visible key landmark features, such as parks, squares and landmark buildings.
- d. To optimise outlook and proximity to public and community facilities, parks and public transport with increased residential density.
- e. To encourage variety in dwelling size, type and design to promote housing choice and create attractive streetscapes with distinctive characters.
- f. To accommodate a mix of lot sizes and dwelling types across a precinct.
- g. To establish minimum lot dimensions for different residential dwelling types.

CONTROLS

BLOCKS

1. Residential neighbourhoods are to be focused on elements of the public domain such as a school, park, retail, or community facility that are typically within walking distance.

2. Subdivision layout is to create a legible and permeable street hierarchy that responds to the natural site topography, the location of existing significant trees and site features, place making opportunities and solar design principles.
3. Pedestrian connectivity is to be maximised within and between each residential neighbourhood with a particular focus on pedestrian routes connecting to public open space, bus stops and railway stations, educational establishments and community/recreation facilities.
4. Street blocks are to be generally a maximum of 250m long and 70m deep. Block lengths in excess of 250m may be considered by Council where pedestrian connectivity, stormwater management and traffic safety objectives are achieved. In areas around neighbourhood and town centres, the block perimeters should generally be a maximum of 520m (typically 190m x 70m) to increase permeability and promote walking.

LOTS

5. Minimum lot sizes for each dwelling type will comply with the minimum lot size provisions permitted by the Sydney Region Growth Centres SEPP, summarised here as **Table 6**. In certain density bands, variations to some lot sizes may be possible subject to clauses in the Sydney Region Growth Centres SEPP.
6. Minimum lot frontages applying to each density band will comply with **Table 7**. Lot frontage is measured at the street facing building line as indicated in **Figure 7**.

Table 6 Minimum lot size by density bands

Housing type ¹	R2 Low Density Residential	R2 Low Density Residential	R3 Medium Density Residential	R4 High Density Residential
Minimum Net Residential Target (dwellings/Ha)	7	15	18	30
Dwelling House (base control)	700	300	300	300
With BEP	N/A	250	225	225
As Integrated DA	N/A	250	225	125
Location Criteria* (BEP or Integrated DA)	N/A	225	N/A	N/A
Studio Dwelling	No minimum lot size as strata development not subject to minimum lot size controls			
Secondary Dwelling	700	450	450	In principle lot
Dual Occupancy	700	500	500	300
Semi Detached Dwelling	2000	200	150	125
Attached Dwelling	N/A	1500*	1500	375
Multi Dwelling Housing	N/A	1500*	1500	375
Manor Homes	Not permissible	Not permissible	Not permissible	600
Residential Flat Buildings	Not permissible	Not permissible	Not permissible	1000

¹ All numerical values, except minimum net residential density target, are measured in square metres.

* On land zoned R2 with a minimum residential density of 15d/ha, the minimum development lot size for the purposes of a dwelling house can be varied to 225m². Attached dwellings and Multi dwelling housing is also permissible on land zoned R2 with a minimum residential density of 15d/ha that also satisfies one of these criteria:

- adjoining land set aside for open space or recreation or is separated from that land only by a public road,
- adjoining land in Zone B1 Neighbourhood Centre, Zone B2 Local Centre or Zone B4 Mixed Use or land that is separated from land within Zone B1 Neighbourhood Centre, Zone B2 Local Centre or Zone B4 Mixed Use only by a public road.
- adjoining land that is set aside for drainage or educational purposes, or is separated from that land only by a public road; and is within 400m of land in Zone B1 Neighbourhood Centre or Zone B2 Local Centre.

Table 7 Minimum lot frontages by density bands

		Net Residential Density Target (dw/Ha)			
		7 dw/Ha	10 to 12.5dw/Ha	15dw/Ha	20 to 45dw/Ha
Minimum Lot Frontages	Front Loaded	18m	12.5m	9m	7m
	Rear Loaded	Not permitted	4.5m	4.5m	4.5m

Note: The combination of the lot frontage width and the size of the lot determine the type of dwelling that can be erected on the lot, and the development controls that apply to that dwelling.




Figure 7 Measurement of minimum lot widths and lot area

- A range of residential lot types (area, frontage, depth, zero lot and access) must be provided to ensure a mix of housing types and dwelling sizes and to create coherent streetscapes with distinctive garden suburban, suburban and urban characters across a neighbourhood.
- In areas with a minimum residential density of $\leq 20dw/ha$ no more than 40% of the total residential lots proposed in a street block may have a frontage of less than 10m wide.

Note: A street block is defined as a portion of a city, town etc., enclosed by (usually four) neighbouring and intersecting streets.

- In density bands $\leq 25dw/ha$, total lot frontage for front accessed lots greater than or equal to 7m and less than 9m should not exceed 20% of any block length due to garage dominance and on-street parking impacts.
- Lots should be rectangular. Where lots are an irregular shape, they are to be large enough and oriented appropriately to enable dwellings to meet the controls in this DCP.
- Where residential development adjoins land zoned RE1 Public Recreation or SP2 Drainage, subdivision is to create lots for the dwelling and main residential entry to front the open space or drainage land.
- The orientation and configuration of lots is to be generally consistent with the following subdivision principles:

- Smallest lots achievable for the given orientations fronting parks and open space with the larger lots in the back streets;
 - Larger lots on corners;
 - North to the front lots are either the widest or deepest lots, or lots suitable for residential development forms with private open space at the front. Narrowest lots with north to the rear.
13. Preferred block orientation is established by the road layout on the Indicative Layout Plan in the relevant Precinct Schedule. Optimal lot orientation is east-west, or north-south where the road pattern requires. Exceptions to the preferred lot orientation may be considered where factors such as the layout of existing roads and cadastral boundaries, or topography and drainage lines, prevent achievement of the preferred orientation.
14. An alternative lot orientation may be considered where other amenities such as views and outlook over open space are available, and providing appropriate solar access and overshadowing outcomes can be achieved.

Note: *The combination of the lot frontage width and the size of the lot determine the type of dwelling that can be erected on the lot, and the development controls that apply to that dwelling.*

ZERO LOT LINES

15. The location of a zero lot line is to be determined primarily by topography and should be on the low side of the lot to minimise water penetration and termite issues. Other factors to consider include dwelling design, adjoining dwellings, landscape features, street trees, vehicle crossovers and the lot orientation as illustrated at **Figure 39**.
16. On all lots where a zero lot line is permitted, the side of the allotment that may have a zero lot alignment must be shown on the approved subdivision plan.
17. Where a zero lot line is nominated on an allotment on the subdivision plan, the adjoining (burdened) allotment is to include a 900mm easement for single storey zero lot walls and 1200mm for two storey zero lot walls to enable servicing, construction and maintenance of the adjoining dwelling. No overhanging eaves, gutters or services (including rainwater tanks, hot water units, air-conditioning units or the like) of the dwelling on the benefited lot will be permitted within the easement. Any services and projections permitted under Clause 4.4 (6) within the easement to the burdened lot dwelling should not impede the ability for maintenance to be undertaken to the benefitted lot.
18. The S88B instrument for the subject (benefited) lot and the adjoining (burdened) lot shall include a note identifying the potential for a building to have a zero lot line. The S88B instrument supporting the easement is to be worded so that Council is removed from any dispute resolution process between adjoining allotments.

For more information, refer to the **Department of Planning and Environment Delivery Notes: Zero Lot Boundaries and Building Envelope Plans**.

SUBDIVISION OF SHALLOW LOTS

19. Shallow lots (typical depth 14-18m, typical area <200m²) intended for double storey dwellings should be located only in locations where it can be demonstrated that impacts on adjoining lots, such as overshadowing and overlooking of private open space, satisfy the requirements of the DCP. For lots over 225m² where development is not Integrated Assessment, the Building Envelope Plan should demonstrate in principle how DCP requirements such as solar access and privacy to neighbouring private open spaces will be satisfied.

SUBDIVISION FOR ATTACHED OR ABUTTING DWELLINGS

20. Subdivision of lots for Torrens title attached or abutting dwellings must take into account that construction will be in 'sets'. A 'set' is a group of attached or abutting dwellings built together at the same time that are designed and constructed independently from other dwellings.
21. The maximum number of attached or abutted dwellings permissible in a set is six.
22. The composition of sets needs to be determined in the subdivision design to take into account the lot width required for a side setback to the end dwellings in each set. Examples of lot subdivisions for sets are illustrated in **Figure 8**.




Figure 8 Two examples of lot subdivision for 'sets' of attached or abutting terraces.

RESIDENTIAL FLAT BUILDINGS

23. A person may not amalgamate two or more adjoining allotments after principle subdivision to create a larger lot that achieves the minimum lot size required for residential flat buildings.

3.1.3 Battle-axe Lots

OBJECTIVES

- a. To limit battle-axe lots to certain circumstances.
- b. To ensure that where a battle-axe lot without public road or open space frontage is provided, their amenity and the amenity of neighbouring lots is not compromised by their location.
- c. To enable battle-axe shaped lots or shared driveway access to lots fronting access denied roads.

CONTROLS

1. Principles for the location of battle-axe lots are illustrated at **Figure 9**.
2. Subdivision layout should minimise the use of battle-axe lots without public frontage to resolve residual land issues.




Figure 9 Examples of locations of battle-axe lots

3. In density bands 10, 15 and 20dw/Ha, the minimum site area for battle-axe lots without any street or park frontage is 500m² (excluding the shared driveway) and only detached dwelling houses will be permitted.
4. The driveway or shared driveway will include adjacent planting and trees, as indicated in **Figure 10**.
5. Driveway design, including dimensions and corner splays, is to be in accordance with Council's Engineering Specifications.




Figure 10

3.1.4 Corner Lots

OBJECTIVES

- a. To ensure corner lots are of sufficient dimensions and size to enable residential controls to be met.

CONTROLS

1. Corner lots, including splays and driveway location, are to be designed in accordance with AS 2890 and Council's Engineering Specifications.

2. Corner lots are to be designed to allow dwellings to positively address both street frontages as indicated in **Figure 11**.
3. Garages on corner lots are encouraged to be accessed from the secondary street or a rear lane.
4. Plans of subdivision are to show the location of proposed or existing substations, kiosks, sewer man holes and/or vents affecting corner lots.




Figure 11 Corner lots

3.2 Subdivision Approval Process

Objectives

- To facilitate a diversity of housing sizes and products.
- To ensure that subdivision and development on smaller lots is undertaken in a coordinated manner.
- To ensure that all residential lots achieve an appropriate level of amenity.

Controls

- The land subdivision approval process is to be consistent with the requirements of **Table 8**.
- Subdivision of land creating residential lots less than 225m² or lots less than 9m wide shall include a dwelling design as part of the subdivision development application. The dwelling design is to be included on the S88B instrument attached to the lot.

Table 8 Subdivision Approval Process

Approval pathway	DA for Subdivision <i>Pathway A1</i>	DA for Subdivision with Building Envelope Plan <i>Pathway A2</i>	DA for Integrated Housing (Integrated Assessment with subdivision prior to construction of dwellings) <i>Pathway B1</i>	DA for Integrated Housing <i>Pathway B2</i>
Application	Lots equal to greater than 300m ²	Lots less than 300m ² and equal to or greater than 225m ² in area, and with a width equal to or greater than 9m*	Dwelling construction involving detached or abutting dwellings on: lots less than 225m ² , or lots with a width less than 9m*	Dwelling construction involving common walls (i.e. attached dwellings) on: lots less than 225m ² , or lots with a width less than 9m*
Dwelling plans required	As part of future DA or CDC	As part of future DA or CDC	Yes as part of subdivision application	Yes as part of subdivision application
Dwelling Design 88B restriction required	No	Yes	Yes, only approved dwelling can be built	Yes, only approved dwelling can be built
Timing of subdivision (release of linen plan)	Pre-construction of dwellings	Pre-construction of dwellings	Prior to the issue of the CC	Post-construction of dwellings
Housing Code applicable	Yes	Yes (for 200m ² lots and above)	No	No

*Minimum lot width refer to **Figure 7**.

- Subdivision applications that create lots smaller than 300m² and larger than or equal to 225m² must be accompanied by a Building Envelope Plan (BEP). An example of a BEP is included at **Figure 12**.

The BEP should be at a legible scale (suggested 1:500) and include the following elements:

- Lot numbers, north point, scale, drawing title and site labels such as street names
- Maximum permissible building envelope (setbacks, storeys, articulation zones)
- Preferred principal private open space
- Garage size (single or double) and location
- Zero lot line boundaries

A BEP should be fit for purpose and include only those elements that are necessary for that particular lot. Other elements that may be relevant to show include:

- Special fencing requirements

- Easements and sewer lines
- Retaining walls
- Preferred entry/frontage (e.g. corner lots)
- Access denied frontages
- Electricity kiosks or substations
- Indicative yield on residue or super lots

For further information, refer to the **Department of Planning and Environment Delivery Note: Building Envelope Plans**

4. Applications for subdivision using approval pathways A2, B1 and B2 require a Public Domain Plan (PDP) to be submitted as part of the application. The purpose of the PDP is to demonstrate how the public domain will be developed as a result of future development on the proposed lots. An example of a PDP is included at **Figure 13**.

The PDP should be a legible scale (suggested 1:500) and include the following elements:

- Lot numbers, north point, scale, drawing title and site labels such as street names.
- Indicative building footprints on the residential lots.
- Location of driveways and driveway crossovers.
- Verge design (footpath, landscape).
- Surrounding streets and lanes (kerb line, material surface where special treatments proposed).
- In laneways, indicative provision for bin collection.
- Street tree locations. (Sizes and species list can be provided on a separate plan).
- Demonstrated provision and arrangements for on-street car parking particularly in relation to street tree planting, driveways and intersections.*
- Extent of kerb line where parking is not permitted.*

* In principle, not as public domain works.

Other elements that may be relevant to show include:

- Location and type of any proposed street furniture
- Location of retaining walls in the public domain
- Electricity substations
- Indicative hydrant locations at lane thresholds

Information on landscape treatment within the private lot is not required.

For further information, refer to the **Department of Planning and Environment Delivery Note: Public Domain Plans**




Figure 12 Sample of a Building Envelope Plan (BEP)




Figure 13 Sample of a Public Domain Plan (PDP)

3.3 Movement Network

3.3.1 Street Network, Design and Hierarchy

OBJECTIVES

- a. To provide a hierarchy of interconnected streets that gives safe, convenient and clear access within and beyond the Precincts.
- b. To ensure that the hierarchy of streets is clearly discernible through variations in carriageway width, on-street parking, street tree planting, and pedestrian amenities.
- c. To provide an acceptable level of access, safety and convenience for all street and road users within the Box Hill Growth Centre Precincts, whilst ensuring emergency access and egress, acceptable levels of amenity, and minimising the negative impact of traffic.
- d. To provide a legible and permeable movement network for pedestrians and cyclists along streets and paths to points of attraction within and adjoining any development.
- e. To facilitate the orientation of lots and dwellings to front public and private open spaces.
- f. To enhance the outlook, setting and amenity of subdivisions adjoining open space and other public areas.
- g. To promote passive surveillance of publicly accessible areas thereby increasing safety.
- h. To ensure sufficient carriageway and verge widths are provided to allow streets to perform their designated functions within the street network and to accommodate public utilities and drainage systems.
- i. To encourage the use of streets by pedestrians and cyclists, and to allow cars, buses and other users to proceed safely without unacceptable inconvenience or delay.
- j. To provide blocks that can accommodate a range of densities and lot sizes with appropriate solar orientation.

ROADS ADJACENT TO OPEN SPACE, TRUNK DRAINAGE AND OTHER PUBLIC AREAS

- k. To facilitate the orientation of lots and dwellings to front the open space and drainage areas.
- l. To enhance the outlook, setting and amenity of subdivisions adjoining open space, drainage areas and other public areas.
- m. To increase pedestrian accessibility to those public areas.
- n. To promote passive surveillance of publicly accessible areas thereby increasing safety.

CONTROLS

1. The street network and road hierarchy is to be provided generally in accordance with **Figure 14** and **Table 9**
2. Despite any other provision of this Development Control Plan, where a local road or proposed local road is shown in this Development Control Plan on an allotment or allotments to which a development application relates and the applicable contributions plan does not require or authorise a monetary contribution towards the acquisition of that land or the construction of the road or associated asset relocation, water management devices, footpaths, street tree planting, traffic management devices and treatment, the development must include the dedication of that part of the allotment identified as local road or proposed local road to the Council free of cost together with the construction of the road and associated asset relocation, water management devices, footpaths, street tree planting, traffic management devices and treatment on any and all road frontages.
3. No vehicular access is permitted from individual lots to Edwards Road in the location identified in **Figure 14**.



Table 9 Street types

Street Type	Description
Sub-Arterial	Sub-arterial roads mediate between regional traffic routes and local traffic routes, and link arterial routes to town centres. Vehicular access to property is not permitted along these roads, so rear access should be provided for properties fronting them. Shared paths are provided for pedestrian and cycle use and on-street parking on both sides of the street is generally provided. There are two cross sections for Terry Road, one is located between Windsor Road and Killarney Chain of Ponds and the other is located between Killarney Chain of Ponds and Mason Road. Refer to Figure 14 , Figure 15 , Figure 16 and Figure 17 .
Collector Road	Collects traffic from local streets and carries a higher volume of traffic, linking neighbourhoods and centres and accommodating public transport routes. Amenity and safety is to be maintained by restricting vehicle speeds through traffic-calming measures and intersection design. Intermittent parking with landscaping is provided on both sides of the street. The section of Mt Carmel Road between Windsor Road and the Killarney Chain of Ponds has an additional median and carriageway to accommodate traffic flows. Refer to Figure 14 , Figure 18 and Figure 19 .
Town Centre Main Street	The Box Hill Town Centre Main Street is specially designed to create a pleasant and comfortable pedestrian environment. Amenity and safety is to be maintained through wide shared footpaths, regular traffic calmed street and crossing points. Public transport routes can be accommodated along the street. On-street parking is to be provided on both sides of the street to contribute to street activity while providing a buffer between pedestrians and cars. Refer to Figure 14 and Figure 20 .
Local Streets	Provide local residential access. These streets are designed to slow residential traffic in order to give priority to pedestrians. Amenity and safety is to be maintained by introducing various traffic calming measures. On-street parking is provided on both sides of the street. Refer Figure 14 and Figure 21 .
Local Streets within visual corridor	As above with a median to accommodate additional trees. Refer Figure 14 and Figure 22 .
Local Streets within the employment area	Local streets with additional road reserve widths to allow for movement of trucks, integrated parking and trees for screening and amenity. Powerlines, gas lines, communication and other utilities will be located underground to allow for tree canopy development. Verge crossings will be limited to increase tree planting opportunities along roads. Refer Figure 14 and Figure 23 .
Local Street, parallel road to Windsor Road	Local Street located directly behind and parallel to Windsor Road. It is characterised by 21m landscape planting to create an interface between Windsor Road and residential areas. This service street will not have any direct connection to Windsor Road. Refer Figure 14 and Figure 24 .
Street along Riparian Corridors/Parks	Perimeter streets are located along riparian corridors and parks. When adjoining riparian corridors the streets form part of the Asset Protection Zone and allow the provision of shared cycleways that link the open space network. Amenity, safety and emergency access and egress for fire fighting is to be maintained by designing the road in accordance with acceptable solutions as stipulated under <i>Planning for Bushfire Protection 2006</i> . Traffic calming measures are to be introduced and parking is to be provided on the dwelling side of the street to allow access for emergency vehicles as per Figure 14 and Figure 25 .
Rear Lane	Provide access to developments fronting sub-arterial and collector roads and also to medium density developments. Rear lanes will provide access for servicing. Laneways must have splayed entrances of 3 metres to allow for garbage trucks. Refer to Figure 14 and Section 3.3.2 .

STREET DESIGN

Streets are to be provided in accordance with the minimum cross-sections in **Figure 15** to **Figure 25** and relevant cross-sections in **Section 3.3.2**.

4. Internal intersections are to be T-junctions, roundabouts or controlled by other appropriate traffic management treatments to slow and control traffic.
5. Direct vehicular access to sub-arterial roads will not be permitted where alternate access is available. Access will not be restricted to any property with existing access from arterial roads until such time as alternate access is available.
6. Roundabouts, street cross falls, longitudinal gradient, vehicle-turning movements and sight distances are to comply with Council's Design Guidelines Subdivisions/ Developments.
7. Kerb and guttering is to be provided in accordance with Council's Design Guidelines Subdivisions/ Developments.
8. An Acoustic Report prepared by a suitably qualified consultant is to be submitted with all development applications for land adjacent to existing or proposed arterial roads or bus routes and should comply with the Environmental Protection Authority publication NSW Road Noise Policy (July 2011).
9. For roads that cross natural drainage lines, the construction of bridges with raised approaches is preferred to culverts in order to maintain stream corridor function. Any works within, or alterations to, natural drainage systems will require consideration of the *Water Management Act 2000* as well as consideration of the *Fisheries Management Act 1944* for dredging or reclamation works.
10. Roads constructed across waterways are to be designed and constructed with reference to the Department of Primary Industries preferred waterway crossing design documented in "Why do Fish Need to Cross the Road? Fish Passage Requirements for Waterways Crossings" (NSW Fisheries 2003).
11. Where culverts are required to be constructed across natural drainage lines, light wells are to be provided in the centre of the road.
12. Footpath provision should follow the requirements of **Table 10** below.

Table 10 Minimum Footpath Requirements

Street type	Traffic volumes	
	(vehicles per day)	Footpath required
Local Street	Up to 3,000 vpd	Yes 1.2m path on one side only
Local Street	Over 3,000 vpd	Yes 1.2m path on both sides
Collector Road	Over 3,000 vpd	Yes 1.5m path on both sides
Town Centre Main Street	N/A	Both sides as per Figure 10

TEMPORARY ROAD CONSTRUCTION

13. Temporary public roads are permitted subject to the following criteria being satisfied:
- The temporary public road is not to be constructed upon land zoned for Local or Neighbourhood Centre, Public Recreation, Infrastructure or Environmental Management;
 - A minimum trafficable width of 6.0m is provided to cater for two-way traffic with 3.5m wide verges on both sides;
 - The allotment layout associated with temporary public road construction does not result in the creation of undevelopable residue lots;
 - The temporary public road does not compromise the safety of all road users including service and passenger vehicles, pedestrians and cyclists;
 - The temporary public road is to be constructed to a standard in accordance with Council's Design Guidelines Subdivisions/ Developments; and
 - The final road configuration is consistent with the pre-planned road network and street type as identified in **Figure 14**.
14. The following information must be submitted in support of a DA proposing temporary road construction:
- An engineering design for the partial and full width road works must be submitted including details of any necessary drainage and service utility provision requirements;
 - A traffic safety report prepared by an appropriately experienced professional must be submitted demonstrating how the partial road proposal provides for the safe usage of all road users including service and passenger vehicles, pedestrians and cyclists; and
 - Written evidence demonstrating that an attempt to cooperate with adjacent landowners has been undertaken must be submitted. Such evidence could be in the form of letters and responses (if applicable).
15. Temporary public roads are permitted subject to the following criteria being satisfied:
- The temporary public road is to be constructed upon a minimum of two (2) residential development lots, except as provided for below;
 - The temporary public road is not to be constructed upon land zoned for Open Space, Trunk Drainage, Transport Corridor or Educational Establishment, except where the land zoned Open Space is in private ownership.
16. Where a temporary public road is proposed to be constructed on private land zoned Open Space, the applicant will be required to enter into an agreement with Council that the temporary public road be removed and the land reinstated when alternate road access becomes available:
- A minimum trafficable width of 6.0m is provided to cater for two-way traffic with 3.5m wide verges on both sides;
 - The allotment layout associated with temporary public road construction does not result in the creation of undevelopable residue allotments;
 - The temporary public road does not compromise the safety of all road users including service and passenger vehicles, pedestrians and cyclists;

- The temporary public road is to be constructed to a standard in accordance with BHSC Design Guidelines for Subdivisions/Developments (Section 5.07); and
- The final road configuration is consistent with the pre-planned road layout and road type as shown on the accompanying development control plan map.

PARTIAL WIDTH ROAD CONSTRUCTION

17. Partial width road construction is permitted subject to the following criteria being satisfied:

- The site(s) located opposite the proposed partial road are zoned for residential use and are not in public ownership or identified for acquisition, that is, the site(s) opposite are not zoned for Open Space, Trunk Drainage, Transport Corridor or Educational Establishment;
- A minimum trafficable road width of 6.0 m is provided to cater for two-way traffic, and a 3.5 m verge on one side as a minimum;
- The development potential of all adjoining allotments is maintained. The proposed development shall not, in the opinion of the consent authority, render any allotment adjoining or opposite the site of the proposed development incapable of development for the purpose of residential development because the allotment would not meet minimum DCP or LEP development standards;
- The safety of all road users including service and passenger vehicles, pedestrians and cyclists is not compromised by the proposed partial road construction; and
- The final road configuration is consistent with the pre-planned road layout and road type as shown on the accompanying development control plan map.

Note: *In some circumstances where proposed partial width roads straddle existing boundaries, the alignment of the road may need to be slightly offset to ensure the partial road is wholly contained on the applicant's land.*

SUBMISSION REQUIREMENTS

PARTIAL WIDTH ROADS

18. An engineering design for the partial and full width road works must be submitted including details of any necessary drainage and service utility provision requirements.
19. A traffic safety report prepared by an appropriately experienced professional must be submitted demonstrating how the partial road proposal provides for the safe usage of all road users including service and passenger vehicles, pedestrians and cyclists.
20. Partial width construction of existing and proposed roads is permitted subject to the following criteria being satisfied:
- The site(s) located opposite the proposed partial road are zoned for residential or business use and are not in public ownership or identified for acquisition, that is, the site(s) opposite are not zoned for Local Centre or Neighbourhood Centre, Public Recreation or Infrastructure;
 - A minimum trafficable road width of 6.0m is provided to cater for two-way traffic;
 - The development potential of all adjoining allotments is maintained. The proposed development shall not, in the opinion of the consent authority, render any allotment adjoining or opposite the site of the proposed development incapable of development for the purpose of residential development because the allotment would not meet minimum DCP or SEPP development standards;

- The safety of all road users including service and passenger vehicles, pedestrians and cyclists is not compromised by the proposed partial road construction; and
- The final road configuration is consistent with the pre-planned road layout and road type as shown in the Box Hill and Box Hill Industrial Indicative Layout Plan and Part 3.1 of this DCP.

Note: In some circumstances where proposed partial width roads straddle existing boundaries, the alignment of the road may need to be slightly offset to ensure the partial road is wholly contained on the applicant's land.

TEMPORARY ROADS

21. An engineering design for the proposed road works, as well as plans demonstrating the future road configuration after closure of the temporary road must be submitted including details of any necessary drainage and service utility provision requirements.
22. A traffic safety report prepared by an appropriately experienced professional must be submitted demonstrating how the temporary road proposal provides for the safe usage of all road users including service and passenger vehicles, pedestrians and cyclists.

Written evidence demonstrating that an attempt to cooperate with adjacent landowners has been undertaken must be submitted. Such evidence could be in the form of letters and responses (if applicable).




Figure 15 Typical Sub Arterial Road




Figure 16 Sub-arterial Road (Terry Road between Windsor Road and Killarney Chain of Ponds)




Figure 17 Sub-arterial Road (Terry Road between Killarney Chain of Ponds and Mason Road)




Figure 18 Typical Collector Road




Figure 19 Mt Carmel Road (between Windsor Road and the Killarney Chain of Ponds)




Figure 20 Town Centre Main Street




Figure 21 Local Street




Figure 22 Local Street within visual corridor




Figure 23 Local Street within the employment area




Figure 24 Parallel Road to Windsor Road




Figure 25 Perimeter Road along Riparian Corridors/Parks

3.3.2 Laneways

Laneways are public roads that are shareways, utilitarian thoroughways of the street network that provide rear vehicular access to compact or restricted access lots. The primary purpose of rear laneways is to create attractive front residential streets by removing garages and driveway cuts from the street frontages, improving the presentation of houses and maximising on street parking spaces and street trees. Laneways are a 'sacrificial' network device: while they should be neat and tidy, they should not be confused with streets in width, character or function.

A laneway is a shareway, designed to be shared by all users whether they are pedestrians, cyclists or drivers. Equal priority between all users reinforces the distinctive, slow speed environment for drivers.

In their design and subdivision of lots, laneways should be provided with casual surveillance from some second floor rooms and balconies over garages. Various building forms can provide this casual surveillance along the lane such as studio dwellings, secondary dwellings and rooms of the principal dwelling or lofts over garages. Separate titling of studio dwellings may affect servicing requirements. Generally there will be no underground services in the laneway (except for streetlights) as the studios will be strata titled so power, water, gas, sewer and communications will be located in the front street and reticulated from the front of the allotment through the lot to the rear studio.

Objectives

- a. To provide vehicular access to the rear or side of lots where front access is restricted or not possible, particularly narrow lots where front garaging is not permitted.
- b. To reduce garage dominance in residential streets.
- c. To maximise on-street parking spaces and landscaping in residential streets.
- d. To provide opportunities for affordable housing options.
- e. To reduce vehicular conflict through reduced driveway cross overs and focusing of traffic to known points.
- f. To enable garbage collection.
- g. To facilitate the use of attached and narrow lot housing to achieve overall higher neighbourhood densities.
- h. To create a slow speed shared zone requiring co-operative driving practices for the very low volume and frequency of vehicle movements that is distinctly different in character and materials to residential streets.

CONTROLS

1. The design and construction of laneways is to be consistent with Figure 26 and Growth Centres Practice Note: Laneways.




Figure 26 Laneway principles

2. The laneway is a public “shareway” as the paved surface is for cyclists, pedestrians, garbage collection, mail deliveries, cars etc., with a 10 km speed limit and driveway-style crossovers to the street rather than a road junction.
3. The minimum garage doorway widths for manoeuvrability in this laneway section are 2.4m (single) and 4.8m (double).
4. The configuration of the laneway, associated subdivision and likely arrangement of garages arising from that subdivision should create ordered, safe and tidy laneways by designing out ambiguous spaces and unintended uses such as casual parking, the storage of trailers, bin stacking etc.
5. The layout of laneways should take into account subdivision efficiency, maximising favourable lot orientations, intersection locations with streets, topography, opportunities for affordable housing, legibility and passive surveillance.
 - Generally, straight layouts across the block are preferred for safety and legibility, but the detailed alignment can employ subtle bends or secondary or studio dwellings over garages to add visual interest and avoid long distance monotonous views. “C” shaped layouts with the laneway length parallel to the front street can limit the views of laneways from residential streets to short sections. However, if the laneway is

used for garbage collection, any bends or intersections are to be sized for garbage truck movements. Suggested layouts are in **Figure 27**.

- Lanes on sloping land with significant longitudinal and/or cross falls require detailed design consideration to demonstrate functionality.




Figure 27 Sample lane layouts

- Laneways that create a 'fronts to backs' layout (front addressed principle dwellings on one side and rear accessed garages on the other side) are to be avoided.
- All lots adjoining a laneway should utilise the laneway for vehicular/garage access.
- Passive surveillance along the laneway from the upper storey rooms or balconies of secondary dwellings, studio dwellings, principal dwelling or lofts over rear garages is encouraged. Ground floor habitable rooms on laneways are to be avoided unless they are located on external corners (laneway with a street) and face the street to take advantage of the residential street for an address, shown in **Figure 28** as lane entry/street corner lots. **Figure 28** indicates mid-lane lots and internal corner locations (lane with another lane) where ground floor habitable rooms in secondary dwellings or strata studios (marked 'S') are to be avoided.
- A continuous run of secondary dwellings or strata studios along the lane is to be avoided, as it changes the character, purpose and function of the lane. No more than 25% of the lots adjoining lanes (excluding street corner lots with studio at the lane entry) are to have secondary dwellings or strata studios. See **Figure 28**.
- All lot boundaries adjoining the lane are to be defined by fencing or built form. The garage setback to the lane is minimal (0.5m) to allow overhanging eaves or balconies to remain in the lot without creating spaces where people park illegally in front of garages and/or on the laneway. Deeper balconies requiring larger garage setbacks (up to 2m) may be permitted occasionally along the laneway provided the application demonstrates how the setback space will not create an opportunity for illegal parking, such as the presence of a supporting post or bollard.




Figure 28 Sample laneways showing maximum number of secondary dwellings or strata studios

3.3.3 Shared Driveways

Shared driveways are privately owned and maintained driveways that serve two or more dwellings through a titling arrangement such as a reciprocal right of way or community title. Shared driveways are usually of minimal dimensions for vehicle access to lots with only a single access to the street network. Garbage collection is usually not a function. Shared driveways are a useful subdivision device for a small number of dwellings with otherwise difficult access or unavoidable block configurations, but are not a substitute in blocks designed with significant numbers of dwellings requiring rear access by laneways.

OBJECTIVES

- To minimise the impact of vehicle access points on the quality of the public domain and pedestrian safety.
- To provide safe and convenient access to garages, carports and parking areas.
- To clearly define public and private spaces, such that driveways are for the sole use of residents.
- To permit casual surveillance of private driveways from dwellings and from the street.

CONTROLS

- Shared driveways are to be constructed as one of three general types, depending on block geometry and garages to be accessed. Refer to examples in **Figure 29**.
- Shared driveways are to have the smallest configuration possible to serve the required parking facilities and vehicle turning movements.
- The driveway crossing the verge between the property boundary and the kerb is to have a maximum width of 5.4 metres.

4. The location of driveways is to be determined with regard to dwelling design and orientation, street gully pits and tree bays and is to maximise the available on-street parking.
5. The maximum travelling distance from a public road to a garbage collection area within a shared driveway is 70m. Where garbage collection is required to occur within the shared driveway (i.e. when an alternative collection point is not available), the layout is to be designed such that no reversing movements are required to be undertaken to enable a garage truck to enter and leave in a forward direction. A minimum pavement width of 5m and a turning circle with sweep turning paths overlaid into the design plan shall be submitted to demonstrate compliance with this requirement.
6. Access to allotments in the vicinity of roundabouts and associated splinter islands shall not be provided within 10m of the roundabout.
7. Driveways are not to be within 0.5m of any drainage facilities on the kerb and gutter.
8. Shared driveways are to have soft landscaped areas on either side, suitable for infiltration.
9. Shared driveways must be in accordance with the shareway principles and vehicle manoeuvring requirements of the **Department of Planning and Environment Delivery Note: Laneways**.




Figure 29 Indicative examples of shared driveways

3.3.4 Public Transport

OBJECTIVES

- a. Encourage the use of public transport through the provision of integrated bus, pedestrian and cycle routes.

- b. To encourage the provision and use of public transport within Box Hill and Box Hill Industrial Precincts.
- c. To ensure clear, safe pedestrian links to public transport stops.
- d. To ensure that the majority of residential lots are within 400 metres distance from an existing or proposed bus stop.

CONTROLS

1. Bus stops should be provided generally in accordance with **Figure 30** and be indicated on the subdivision DA drawings where the bus route is known. The final location of bus stops will be determined by Council's Local Traffic Committee.
2. Bus stops should be provided on-street and not within indented bays. Bus shelters are to be provided at key stops and installed at the subdivision construction stage by the developer.




Figure 30 Public transport


3.3.5 Pedestrian and Cycle Network

OBJECTIVES

- a. To provide a convenient, efficient and safe network of pedestrian and cycleway paths for the use of the community, within and beyond the site.
- b. To encourage residents to walk or cycle, in preference to using motor vehicles, as a way of gaining access to the schools, shops, and local community and recreation facilities.
- c. To avoid duplication by allowing pedestrian pathways and cycleways to be located within parks and corridors wherever practical.

CONTROLS

1. Footpaths and cycle paths are to be provided in accordance with street sections provided in **Section 3.3.1** Street Network and Design.
2. All pedestrian and cycle routes are to be consistent with the Planning Guidelines for Walking and Cycling (DIPNR & RTA 2004), Austroads guides, Australian Standards, RTA supplements and Council's Pedestrian Access and Mobility Plan 2003.
3. Pedestrian paths, cycle routes and facilities in public spaces are to be safe, well lit, clearly defined, functional and accessible to all.
4. Pedestrian paths, cycle paths and pedestrian refuge islands are to be designed to be fully accessible by all in terms of access points and gradients, generally in accordance with Australian Standard 1428:1-4.
5. Pedestrian and cycle pathways are to be constructed as part of the infrastructure works for each residential stage with detailed designs to be submitted with the construction certificate application. Concept approval will be required at DA stage.
6. Pedestrian and cycle routes shall be in accordance with **Figure 31**.
7. Minimum footpath width is to be 1.2m for local streets, 1.5m for other street types (sub-arterial, collector and town centre main street) and a shared cycle/pedestrian path is to be 2.5m.



3.4 Public Domain Works

OBJECTIVES

- a. To meet the public open space and recreational needs of residents.
- b. To provide an equitable distribution of public open space and recreation opportunities.
- c. To ensure a high quality of design and embellishment of all public open space.
- d. To ensure environmentally and visually sensitive land contributes to the landscape character of the Precincts.
- e. To ensure that all the public domain elements like street trees, paving, street furniture, lighting, and signage contribute to a consistent street character.
- f. To ensure that adequate provision is made for utilities.
- g. To ensure that all utilities are integrated into the development and are unobtrusive.
- h. To ensure that all parks are managed to the extent required to provide acceptable asset protection to adjoining dwellings.

CONTROLS

PUBLIC PARKS AND LANDSCAPE

1. Parks should be located and designed to accommodate remnant vegetation and where appropriate, should be linked to and integrated with riparian corridors. Refer to **Figure 32**.
2. Parks should be generally bordered by streets on all sides with houses oriented towards them for surveillance. Smaller lot housing is encouraged around parks.
3. Riparian corridors and conservation areas are to provide opportunities for pedestrian and cycle ways, fitness trails and additional open space in a manner that maintains the environmental significance of these areas. A range of themed elements such as boardwalks, eco-pathways, and educational tracks should be utilised in appropriate locations (i.e. within the riparian corridor buffer).
4. A Landscape Plan is required to accompany a subdivision DA creating any park and is to provide details on elements such as:
 - asset protection zones;
 - earthworks;
 - furniture;
 - plant species and sizes (with consideration for bush fire risks);
 - play equipment;
 - utilities and services;
 - public art;
 - hard and soft landscaping treatments;
 - signage;
 - any entry statements;
 - waste facilities; and
 - any other embellishment.

STREET PLANTING

5. Street trees are required for all streets. Street planting is to:

- Be consistently used to distinguish between public and private spaces and between different classes of street within the street hierarchy;
 - Minimise risk to utilities and services;
 - Be durable and suited to the street environment and, wherever appropriate, include endemic species;
 - Maintain adequate lines of sight for vehicles and pedestrians, especially around driveways and street corners;
 - Provide appropriate shade; and
 - Provide an attractive and interesting landscape character and clearly define public and private areas, without blocking the potential for street surveillance.
6. Street trees will be required to be planted at the time of subdivision construction. Street trees will be protected with tree guards and a 12-month bond will be imposed to ensure the preservation of each tree.
 7. Street tree planting is to be provided to all streets with a spacing of between 7 and 10 metres, with a minimum of one tree per lot frontage. Corner lots will have a minimum of two street trees and normally three trees. The location of street trees must complement proposed driveway locations and have regard to surrounding infrastructure.
 8. Street tree species must be in accordance with Council's list of preferred street tree planting species in Appendix B – Table B2.
 9. Landscape works in roundabout islands may include low-maintenance groundcover planting and native grasses with a mature height of up to 0.5 metres as well as clear-stemmed tree planting. A metered water supply point and subsurface drainage is required in all small island planter beds.
 10. Access streets located adjacent to arterial roads are to include landscape treatment of the verge adjoining the arterial road. Road verges provide opportunities for unifying the appearance and landscape character of the area and should be provided as a continuous design feature along the length of the arterial road.

SIGNAGE, STREET FURNITURE, LIGHTING AND PUBLIC ART

11. Signage, street furniture and lighting is to be:
 - Consistent with The Hills DCP 2012 Part C Section 3 - Landscaping;
 - Designed to reinforce the distinct identity of the development;
 - Coordinated in design and style;
 - Located so as to minimise visual clutter and obstruction of the public domain; and
 - Of a colour and construction agreed by Council.
12. The integration of artworks into the design of public spaces is encouraged.
13. Artworks should, where possible, serve a dual role, e.g. as play equipment for children, informal seating or a marker for a meeting place.
14. Locating entry signage and the like within a public road reserve is subject to Council agreement.
15. The location and design of signage and street furniture is to be indicated on engineering construction drawings.
16. All lighting proposed is to be identified with the engineering plans accompanying an application for a Construction Certificate. The level of street lighting is to be designed to meet the current Australian Standards AS/NZS 1158 series.

UTILITIES

17. Gas and water services may be located in a shared trench on one side of the street and electricity power and telephone located in a shared trench on the other side of the street.
18. All development shall incorporate underground electricity reticulation and telecommunications.
19. Any existing aboveground electricity reticulation services shall be relocated underground with the exception of main transmission lines.
20. Where agreement to develop shared trench practices cannot be met, or location of services are unable to be limited to one side of the road, the alignment of services shall be to a standard acceptable to Council.
21. Utilities and services are to be supplied and constructed in accordance with the requirements of the relevant authority.
22. Details of the location of all sewer reticulation mains are to be supplied to Council for assessment of environmental and property considerations.
23. Pipes and conduits through bushland areas and areas with significant vegetation cover are to be avoided. Where it cannot be avoided, pipes are to be or under-bored with the aid of small machinery, causing minimal disturbance to vegetation and exposed rock outcrops.
24. Development is to have a water supply for fire-fighting purposes in accordance with the NSW Rural Fire Service's Planning for Bushfire Protection 2006 (as amended).



Figure 32 Open space

3.5 Residue Lots

OBJECTIVES

- a. To ensure that any residue lot created as part of the subdivision can meet the requirements of the DCP.

CONTROLS

Any development proposal including creation of residue lots for future subdivision must:

1. Include documentation demonstrating how the minimum density can be achieved across each residue lot through future subdivision.
2. Demonstrate how the future development of each residue lot can be consistent with the character statement for the local area in terms of the built form, dwelling types, bulk and scale, height and other public domain considerations.
3. Demonstrate that the residue lot can be serviced and accessed in accordance with **Figure 2**.
4. Demonstrate that development of the residue lot can be undertaken without compromising the other objectives and controls of this DCP.
5. Demonstrate that the residue lot shall be connected to the reticulated public sewer.

Any tank or vessel that was used for on-site sewage management shall be destroyed removed or reused in accordance with NSW Health Advisory Note 3 - Destruction, Removal or Reuse of Septic Tanks, Collection Wells, Aerated Wastewater Treatment Systems and other Sewage Management Facility Vessels.

4.0

Residential Development

4.0 RESIDENTIAL DEVELOPMENT

4.1 Site Responsive Design

4.1.1 Cut and Fill

OBJECTIVE

- a. To minimise the extent of cut and fill within residential allotments.
- b. To protect and enhance the aesthetic quality of the area by controlling the form, bulk and scale of land forming operations.
- c. To ensure that filling material is satisfactory and does not adversely affect the fertility or salinity of soil, or the quality of surface water or groundwater.
- d. To ensure that the amenity of adjoining residents is not adversely affected by any land forming operation.

CONTROLS

1. Development Applications are to illustrate where it is necessary to cut and/or fill land and provide justification for the proposed changes to the land levels.
2. Proposals requiring significant moving and filling of earth will be considered if they contribute to the overall quality of the development and the urban design outcomes for the area. A Validation Report will be required to be submitted to Council prior to the placement of imported fill on site. All fill shall comply with the Department of Natural Resources (now OEH) – “Site Investigation for Urban Salinity” and the DECC (now OEH) Contaminated Sites Guidelines – “Guidelines for the NSW Site Auditor Scheme (2nd edition) - Soil Investigation Levels for Urban Development Sites in NSW.”
3. Earth moved from areas containing noxious weed material must be disposed of at an approved waste management facility, and transported in compliance with the *Noxious Weeds Act 1993*.
4. No earthworks shall be undertaken whereby excavation exceeds 500mm or fill exceeds 500mm from the present surface level of the property without approval from Council.
5. On sloping sites, site disturbance is to be minimised by use of split level or pier foundation housing designs. Council will consider greater cut for basement garages.
6. Retaining walls within residential allotments are to be no greater than 500mm high at any point on the edge of any residential allotment. A combined 1m maximum retaining wall height is permissible between residential lots (2 x 500mm).
7. Where terraced walls are proposed the minimum distance between each step is 0.5m.
8. A variation to the retaining wall heights can be considered with supporting justification.
9. The maximum height of voids within individual allotments is 3m (see **Figure 33**).
10. All retaining walls proposed for the site are to be identified.




Figure 33 Maximum cut and fill with residential blocks

4.1.2 Safety and Surveillance

OBJECTIVES

- a. To ensure that the siting and design of buildings and spaces decreases the opportunities for committing crime through casual surveillance.
- b. To ensure that development encourages people to use streets, parks and other public places without fear of personal risk.

CONTROLS

1. Dwellings should be designed to overlook streets, lanes and other public or communal areas to provide casual surveillance. In the case of corner lots habitable windows are to be oriented to overlook the side street.
2. The design of all development, in particular, the public domain and community facilities is to enhance public surveillance of public streets and open space/conservation areas.
3. Encourage a sense of community ownership of open and public spaces (e.g. parks, footpaths, etc.) through appropriate design of publicly accessible areas.
4. Use of roller shutters other than garages is not permitted on doors and windows facing the street. Any security railings must be designed to complement the architecture of the building.
5. Developments are to avoid the creation of areas for concealment and blank walls facing the street.
6. Pedestrian and communal areas are to have sufficient lighting to ensure a high level of safety. These areas must be designed to minimise opportunities for concealment.
7. All development should aim to provide casual surveillance of the street as a means of passive security. This should be achieved by maximising outlooks and views, but minimising the overlooking of neighbouring properties. Opportunities for casual surveillance from dwellings / studios are to be incorporated into the design of shared driveways and where rear access is proposed from laneways.
8. All developments are to incorporate the principles of Crime Prevention through Environmental Design (CPTED).

4.1.3 Sustainable Building Design

OBJECTIVES

- a. To ensure that developments are environmentally sustainable in terms of energy and water use.
- b. To reduce consumption of potable water and waste water discharge.
- c. To maximise opportunities for natural ventilation in residential development.
- d. To prevent further air pollution or disturbance to amenity of nearby residents from the use of open fire places and slow combustion stoves.

CONTROLS

1. New residential dwellings, including a residential component within a mixed use building and serviced apartments intended or capable of being strata titled are to be accompanied by a BASIX Certificate and are to incorporate all commitments stipulated in the BASIX Certificate.
Box Hill Growth Centre Precincts Development Control Pan 2018
2. Buildings and developments not affected by BASIX are to achieve a 40% reduction of baseline potable water consumption. Where the building or development is water intensive (i.e. high water user), specific water conservation objectives must be resolved with Council.
3. Building envelopes, depths and internal layouts of all residential development is to facilitate natural ventilation.
4. Open fire places and slow combustion stoves are prohibited.

4.2 Dwelling design controls

Under the provisions of the Precinct Plan, development consent is generally required for all dwellings in all residential zones, except where applications meet the criteria for complying development. This section establishes objectives and controls for the following types of residential accommodation as defined in the Growth Centres SEPP:

- dwelling houses;
- semi-detached dwellings;
- attached dwellings;
- abutting dwellings;
- multi-dwelling housing;
- dual occupancy dwellings;
- manor homes;
- residential flat buildings;
- secondary dwellings; and
- studio dwellings.

Additional controls for attached or abutting dwellings, secondary dwellings, studio dwellings, dual occupancies, multi-dwelling housing, manor homes, residential flat buildings and shop top housing are contained in **Section 5.0**.

It is acknowledged that innovative dwelling designs are evolving particularly on lots <300m², and design solutions may be developed that meet the objectives but do not comply with the relevant controls. In density bands ≥25dw/Ha, there is the opportunity to vary the dwelling design controls where agreed to as part of an integrated housing development application at subdivision approval.

Note: Reference should be made to the Glossary for descriptions of the various dwelling types, and to the relevant Precinct Plan for statutory definitions of land uses.

4.2.1 Summary of Key Controls

The following **Table 11** summarises the types of lots and housing. **Table 11** is diagrammatic only and directs readers to the relevant **Tables 12 to 16** containing the main development controls.

The key controls should be read in conjunction with the controls in the clauses that follow.

Table 11 Summary of lot and dwelling types








Access	Lot Width	Detached	Zero lot	Abutting/Attached	Controls Table
Rear access	≥4.5m				Table 12
	7>9m				Table 13
	≥9≥15m				Table 14
	>15m				Table 15
Front access	Ridge Area				Table 16

Table 12 Summary of key controls for lots with frontage width $\geq 4.5\text{m}$ for rear accessed dwellings

Element	Control	
Front setback (min)	4.5m to building façade line; 3.5m to building façade fronting open space 3.0m to articulation zone; 2.0m to articulation zone fronting open space.	In density bands $\geq 25\text{dw}/\text{Ha}$ 3.0m to building façade line, 1.5m to articulation zone.
Side setback (min)	Zero Lot, Attached or Abutting Boundary (benefited lot) Ground floor: 0m Upper floor: 0m	Detached Boundary 0.9m. If lot burdened by zero lot boundary, side setback must be within easement: 0.9m (single storey zero lot wall) 1.2m (double storey zero lot wall)
Maximum length of zero lot line on boundary	Attached/abutting house: 15.0m (excludes rear loaded garages) upper levels only. No limit to ground floor.	Zero lot house: 15.0m (excludes rear loaded garages)
Rear setback (min)	0.5m (rear loaded garages to lane)	
Corner lots secondary street setback (min)	1.0m	
Building height, massing and siting	In density areas $\leq 20\text{dw}/\text{Ha}$: 2 storeys maximum (3rd storey subject to clause 4.2.5 (1))	In density areas $\geq 25\text{dw}/\text{Ha}$: 3 storeys maximum
Site Coverage	Upper level no more than 40% of lot area. Refer also clause 5.2(3)	
Soft landscaped area	Minimum 15% lot area. The first 1.0m of the lot measured from the street boundary (excluding paths) is to be soft landscaped.	
Principal Private Open Space (PPOS)	In density areas $\leq 20\text{dw}/\text{Ha}$: Min 16.0m ² with minimum dimension of 3.0m.	In density areas $\geq 25\text{dw}/\text{Ha}$: Min 16.0m ² with minimum dimension of 3.0m. 10.0m ² per dwelling if provided as balcony or rooftop with a minimum dimension of 2.5m.
Solar access	In density areas $\leq 20\text{dw}/\text{Ha}$: At least 3 hours of sunlight between 9am and 3pm at the winter solstice (21 June) to at least 50% of the required PPOS of both the proposed development and the neighbouring properties.	In density areas $\geq 25\text{dw}/\text{Ha}$: At least 3 hours of sunlight between 9am and 3pm at the winter solstice (21 June) to at least 50% of the required PPOS of: <ul style="list-style-type: none"> all affected neighbouring properties; and at least 70% of the proposed dwellings.
	For alterations and additions to existing dwellings in all density areas, no reduction in the existing solar access to PPOS of the existing neighbouring properties.	
Garages and car parking	Rear loaded garage or car space only for lots of this type. Minimum garage width 2.4m (single) and 4.8m (double). 1-2 bedroom dwellings will provide at least 1 car space. 3 bedroom or more dwellings will provide at least 2 car spaces.	

Table 13 Summary of key controls for lots with frontage width $\geq 7\text{m}$ and $< 9\text{m}$ for front accessed dwellings

Element	Control	
Front setback (min)	4.5m to building façade line; 3.5m to building façade fronting open space 3.0m to articulation zone; 2.0m to articulation zone fronting open space 5.5m to garage line and minimum 1m behind the building line	
Side setback (min)	Zero Lot, Attached or Abutting Boundary Ground floor: 0m Upper floor: 0m	Detached Boundary 0.9m. If lot burdened by zero lot boundary, side setback must be within easement: 0.9m (single storey zero lot wall) 1.2m (double storey zero lot wall)
Maximum length of zero lot line on boundary	15.0m	
Rear setback (min)	4.0m (ground level) and 6.0m (upper levels)	
Corner lots secondary street setback (min)	1.0m	
Building height, massing and siting	In density areas $\leq 20\text{dw}/\text{Ha}$: 2 storeys maximum (3rd storey subject to clause 4.2.5 (1))	In density areas $\geq 25\text{dw}/\text{Ha}$: 3 storeys maximum
Site Coverage	Upper level no more than 50% of lot area	
Soft landscaped area	Minimum 15% lot area. The first 1.0m of the lot measured from the street boundary (excluding paths) is to be soft landscaped.	
Principal Private Open Space (PPOS)	In density areas $\leq 20\text{dw}/\text{Ha}$: Min 16.0m ² with minimum dimension of 3.0m.	In density areas $\geq 25\text{dw}/\text{Ha}$: Min 16.0m ² with minimum dimension of 3.0m. 10.0m ² per dwelling if provided as balcony or rooftop with a minimum dimension of 2.5m.
Solar access	In density areas $\leq 20\text{dw}/\text{Ha}$: At least 3 hours of sunlight between 9am and 3pm at the winter solstice (21 June) to 50% of the required PPOS of both the proposed development and the neighbouring properties.	In density areas $\geq 25\text{dw}/\text{Ha}$: At least 3 hours of sunlight between 9am and 3pm at the winter solstice (21 June) to at least 50% of the required PPOS of: <ul style="list-style-type: none"> all affected neighbouring properties; and at least 70% of the proposed dwellings.
	For alterations and additions to existing dwellings in all density areas, no reduction in the existing solar access to PPOS of the existing neighbouring properties.	
Garages and car parking	Single width garage or car space only. Carport and garage minimum internal dimensions: 3.0m x 5.5m. 1-2 bedroom dwellings will provide at least 1 car space. 3 bedroom or more dwellings will provide at least 2 car spaces. The garage must be less than 40% of the total area of the front façade.	
Layout	Driveway locations must be paired to preserve on-street parking spaces in front of lots. In density bands $\leq 25\text{ dw}/\text{Ha}$, total lot frontage of this lot type not to exceed 20% of the block length due to garage dominance and on-street parking impacts.	

Table 14 Summary of key controls for lots with frontage width $\geq 9\text{m}$ and $\leq 15\text{m}$ for front accessed dwellings

Element	Control	
Front setback (min)	4.5m to building façade line; 3.5m to building façade fronting open space or drainage land 3.0m to articulation zone; 2.0m to articulation zone fronting open space or drainage land 5.5m to garage line and 1m behind the building line	
Side setback (min)	Detached boundary: Ground Floor: 0.9m Upper Floor: 0.9m	Lots with a zero lot boundary (side A): Ground Floor: 0m (Side A), 0.9m (Side B) Upper Floor: 1.5m(Side A), 0.9m (Side B)
Length of zero lot line on boundary	11.0m	
Rear setback (min)	4.0m (ground level) and 6.0m (upper levels)	
Corner lots secondary street setback (min)	2.0m	
Building height, massing and siting	2 storeys maximum (3rd storey subject to clause 4.2.5 (1))	
Site coverage	Single storey dwellings: 60% Lot $\leq 375\text{m}^2$, upper level no more than 40% of lot area. Lot $> 375\text{m}^2$, upper level no more than 35% of lot area.	
Landscaped area	Minimum 25% of allotment area	
Principal Private Open space (PPOS)	Minimum 20.0m ² with minimum dimension of 4.0m. 50% of the area of the required PPOS (of both the proposed development and adjoining properties) should receive at least 3 hours of sunlight between 9am and 3pm at the winter solstice (21 June)	
Garages and car parking	Lots $\geq 9.0\text{m}$ and $< 12.5\text{m}$: Where front accessed, single width garages only. Rear lane or side street accessed double garages permitted. Max. carport and garage door width not to exceed 3.0m (single) or 6.0m (double)	Lots $\geq 12.5\text{m}$ and $\leq 15.0\text{m}$: Front or rear accessed single, tandem or double garages permitted. Triple garages are not permitted.
	1-2 bedroom dwellings will provide at least 1 car space. 3 bedroom or more dwellings will provide at least 2 car spaces.	

Table 15 Summary of key controls for lots with frontage width > 15m for front accessed dwellings

Element	Control
Front setback (min)	4.5m to building façade line 3.5m to building façade fronting open space or drainage land 3.0m to articulation zone 2.0m to articulation zone fronting open space or drainage 5.5m to garage line and 1m behind the building line
Side setback (min)	Ground Floor: 0.9m (Side A), 0.9m (Side B) Upper Floor: 0.9m (Side A), 1.5m (Side B)
Rear setback (min)	4.0m (ground level) and 6.0m (upper levels)
Corner lots secondary street setback (min)	2.0m
Building height, massing and siting	2 storeys (3rd storey subject to clause 4.2.5 (1))
Site coverage	Single storey dwellings: 50% Two storey dwellings: 50% at ground floor and 30% at upper floor
Landscaped area	Minimum 30% of the allotment area
Principal Private Open Space (PPOS)	Minimum 24.0m ² with minimum dimension 4.0m 50% of the area of the required principal private open space (of both the proposed development and adjoining properties) should receive at least 3 hours of sunlight between 9am and 3pm at the winter solstice (21 June).
Garages and car parking	Front or rear loaded double and tandem garages permitted Maximum garage door width 3.0m (Single) and 6.0m (Double) Triple garages are not permitted. 1-2 bedroom dwellings will provide at least 1 car space. 3 bedroom or more dwellings will provide at least 2 car spaces.

Table 16 Summary of key controls for lots in the **Ridge Area**

Element	Control
Front setback (min)	7.5m to building façade line Façade articulation is to be behind the front setback Garage setback 1.0m behind the building façade line
Side setback (min)	Ground Floor: 1.5m Upper Floor: 1.5m (Side A), 3.0m (Side B)
Rear setback (min)	10.0m
Corner lots secondary street setback (min)	4.5m
Building height, massing and siting	2 storeys (3rd storey subject to clause 4.2.5 (1))
Site coverage	Single storey dwellings: 35% Two (or more) storey dwellings: 25% ground floor and 15% upper floors
Landscaped area	Single storey dwellings: Minimum 55% of the allotment area Two or more storey dwellings: Minimum 60% of the allotment area
Principal Private Open Space (PPOS)	Minimum 24.0m ² with minimum dimension 4.0m 50% of the area of the required principal private open space (of both the proposed development and adjoining properties) should receive at least 3 hours of sunlight between 9am and 3pm at the winter solstice (21 June).
Garages and car parking	Front or rear loaded double and tandem garages permitted Maximum garage door width 3.0m (Single) and 6.0m (Double) where garages front a public road. Triple garages permitted where at least one garage door is not visible from the street or where the total width of the garages is less than 50% of the total width of the building façade. 1-2 bedroom dwellings will provide at least 1 car space. 3 bedroom or more dwellings will provide at least 2 car spaces.

4.2.2 Streetscape and architectural design

Growth Centres neighbourhoods will be composed of a variety of streets with different but equally appealing characters and built form intensity. In low density precincts, suburban streetscapes will be most common but there will also be some streets with a more urban village character. In higher density precincts, urban village streets will be more common but there will also be some suburban streetscapes. The objective is to avoid a monoculture of the one type of street which is neither a successful suburban or urban street.

Figure 34 illustrates how the designed combination of built form, lot size, setbacks, garaging and landscaping can create distinctive streetscape characters ranging from the low intensity 'garden suburban' character based on landscaped private space around buildings to the built form intensity and public landscapes of urban streets.



Garden Suburban



Suburban



Urban

Figure 34 The combination of built form, lot size, garaging and landscaping creates different streetscapes

OBJECTIVES

- a. To ensure that buildings are designed to enhance the built form and character of the neighbourhood by encouraging innovative and quality designs that contribute to unified streetscapes.
- b. To encourage a diversity of house types.
- c. To provide a clear distinction between private and public space and to encourage casual surveillance of the street.
- d. To reinforce significant street intersections particularly on open space and other key strategic areas through articulation of corner buildings.


CONTROLS

1. The primary street façade of a dwelling should address the street and must incorporate at least two of the following design features:
 - entry feature or porch;
 - awnings or other features over windows;
 - balcony treatment to any first floor element;
 - recessing or projecting architectural elements;
 - open verandah;
 - bay windows or similar features; or
 - verandahs, pergolas or similar features above garage doors.
2. Corner lot development should emphasise the corner. The secondary street façade for a dwelling on a corner lot should address the street and must incorporate at least two of the above design features. Landscaping in the front setback on the main street frontage should also continue around into the secondary setback.
3. Modulation of the façade should be integral to the design of the building, rather than an unrelated attached element.
4. Eaves are to provide sun shading and protect windows and doors and provide aesthetic interest. Except for walls built to the boundary, eaves should have a minimum of 450mm overhang (measured to the fascia board). Council will consider alternative solutions to eaves so long as appropriate sun shading is provided to windows and display a high level of architectural merit.
5. The pitch of hipped and gable roof forms on the main dwelling house should be between 22.5 degrees and 35 degrees. Skillion roofs, roofs hidden from view by parapet walls, roofs on detached garages, studios and ancillary buildings on the allotment are excluded from this control.
6. Front façades are to feature at least one habitable room with a window onto the street.
7. Carports and garages are to be constructed of materials that complement the colour and finishes of the main dwelling.
8. Streets should be fronted with similar housing types to create a consistent street character. For example, a 'garden suburban' street character will be created where most dwellings are detached on lot widths $\geq 15\text{m}$, perhaps with deeper lots allowing for larger front setbacks and generous landscaping around dwellings. A suburban street character will be created where most dwellings are front loaded, detached or zero lotted on lot widths between 9-15m. An urban street character will be created where most dwellings are zero lotted,

attached/abutting on lot widths less than 9m with rear garages. Streetscape design principles are illustrated at **Figure 35**.



Garden Suburban streetscape principles



Suburban streetscape principles



Urban streetscape principles

Figure 35 Streetscape design principles

4.2.3 Front setbacks

OBJECTIVES

- a. To enable the integration of built and landscape elements to create an attractive, visually consistent streetscape.
- b. To encourage simple and articulated building forms.
- c. To ensure garages do not dominate the streetscape.

CONTROLS

1. Dwellings are to be consistent with the front setback controls and principles in the relevant **Table 12 to Table 16, Figure 36** and **Figure 37**.
2. On corner lots, front setback controls are to be consistent with **Figure 38**.
3. To achieve a desired streetscape character, the building façade front setback for a series of lots can be more or less than the setbacks shown in **Tables 12 to 16** where agreed to as part of the preparation of a Building Envelopes Plan or integrated housing development application at subdivision approval and the front setbacks are attached to the lot titles. However, the front setback to garages must be a minimum of 5.5m.
4. Elements permitted in the articulation zone (shown on **Figure 36, Figure 37 & Figure 38**) include those items listed in Control Streetscape and architectural design 4.2.2 (1).
5. Except for rear loaded garages, garages are to be setback at least 5.5m from the street boundary and at least 1m behind the building line of the dwelling.
6. Any building along Windsor Road must have a minimum setback of 20m from this road.




Figure 36 Minimum front setback distances




Figure 37 Minimum front setbacks for dwellings fronting open space or drainage land




Figure 38 Minimum setbacks for corner lot dwellings

4.2.4 Side and rear setbacks

OBJECTIVES

- a. To create an attractive and cohesive streetscape that responds to the character areas.
- b. To minimise the impacts of development on neighbouring properties.
- c. To provide appropriate separation between buildings.
- d. To create opportunities for articulation on the side walls.

CONTROLS

1. All development is to be consistent with the side and rear setback controls in the relevant **Table 12 to Table 16** and principles in **Figure 39**.
2. The location of a zero lot line (Side A) is to be determined primarily by topography and should be on the low side of the lot to minimise water penetration and termite issues. Other factors to consider include dwelling design, adjoining dwellings, landscape features, street trees, vehicle crossovers and the lot orientation as illustrated at **Figure 39**.
3. For attached or semi-detached dwellings the side setback only applies to the end of a row of attached housing, or the detached side of a semi-detached house.
4. Pergolas, swimming pools and other landscape features/structures are permitted to encroach into the rear setback.
5. The minimum setback to dwellings from a side boundary that adjoins Public Recreation or Drainage land shall be:
 - 3.0m in the R2, R3 and R4 zones.
 - 4.5m in the Ridge Area.
6. For dwellings with a minimum 900mm side setback, projections permitted into side and rear setback areas include eaves (up to 450 millimetres wide), fascias, sun hoods, gutters, down pipes, flues, light fittings, electricity or gas meters, rainwater tanks and hot water units.
7. No overhanging eaves, gutters or services (including rainwater tanks, hot water units, air-conditioning units or the like) of the dwelling on the benefited lot will be permitted within the easement. Any services and projections permitted under **Clause 4.2.4 (6)** within the easement to the burdened lot dwelling should not impede the ability for maintenance to be undertaken to the benefitted lot.




Figure 39 Dwelling and open space siting principles for different lot orientations

8. For battle-axe lots without a street facing elevation setbacks are to be determined in the context of surrounding lots, built form and the location of private open space. An example is shown in **Figure 40**.
9. The upper floor of dwellings on battle-axe lots must be setback so as not to impact adversely on the existing or future amenity of any adjoining land on which residential development is permitted, having regard to overshadowing, visual impact and privacy.
10. For a battle-axe lot with direct frontage to land zoned for a public purpose or a street facing elevation (such as access denied lots), the front setback controls in **Section 4.2.3** are to apply to the lot boundary adjoining the public purpose zone, and side and rear setbacks are to apply to lot boundaries determined relative to the front setback boundary as shown in **Figure 41**.
11. For corner lots $\geq 15\text{m}$ lot width with shallow depths (i.e. approximately square corner lots), the rear setback can be varied to be consistent with the side setback in **Table 14** and **Table 15** provided the minimum private open space and solar access requirements to the proposed and adjoining properties are met.



Figure 40 Battle axe lot (without any street frontage) example of setbacks



Figure 41 Battle axe lot (fronting access denied road) setbacks

4.2.5 Dwelling Height, Massing and Siting

OBJECTIVES

- a. To ensure development is of a scale appropriate to protect residential amenity.
- b. To ensure building heights achieve built form outcomes that reinforce quality urban and building design.

CONTROLS

1. Dwellings are to be generally a maximum of 2 storeys high. Council may permit a 3rd storey if it is satisfied that:
 - the dwelling is located on a prominent street corner; or
 - the dwelling is located adjacent to a neighbourhood or local centre, public recreation or drainage land, a golf course, or a riparian corridor; or
 - the dwelling is located on land with a finished ground level slope equal to or more than 15%, and is not likely to impact adversely on the existing or future amenity of any adjoining land on which residential development is permitted, having regard to overshadowing, visual impact and any impact on privacy; or
 - the third storey is within the roof line of the building (i.e. an attic).

Note: Reference should be made to clause 4.2.3 of the relevant Precinct Plan for statutory height limits.

2. All development is to comply with the maximum site coverage as indicated in the relevant **Table 12 to Table 16**.
3. Site coverage is the proportion of the lot covered by a dwelling house and all ancillary development (e.g. carport, garage, shed) but excluding unenclosed balconies, verandahs, porches, al fresco areas etc.
4. The ground floor level shall be no more than 1m above finished ground level.
5. Dwellings on a battle-axe-lot without public open space or street frontage are to be a maximum of 2 storeys high.

4.2.6 Landscaped Area

Landscaped area is defined as an area of open space on the lot, at ground level, that is permeable and consists of soft landscaping, turf or planted areas and the like.

OBJECTIVES

- a. To encourage the use of native flora species and low maintenance landscaping.
- b. To contribute to effective stormwater management, management of micro-climate impacts and energy efficiency.
- c. To ensure a balance between built and landscaped elements in residential areas.
- d. To create the desired street character.

CONTROLS

1. The minimum soft landscaped area within any residential lot is to comply with the controls and principles in the relevant **Table 12 to Table 16**. **Figure 42** illustrates areas of a lot that can contribute towards the provision of soft landscaped area and principal private open space.
2. Plans submitted with the development application must indicate the extent of landscaped area and nominate the location of any trees to be retained or planted.
3. Surface water drainage shall be provided as necessary to prevent the accumulation of water.
4. Use of low flow watering devices is encouraged to avoid over watering. Low water demand drought resistant vegetation is to be used for the majority of landscaping, including native salt tolerant trees.




Figure 42 Soft landscaped area and principal private open space

4.2.7 Private Open Space

OBJECTIVES

- a. To provide a high level of residential amenity with opportunities for outdoor recreation and relaxation.
- b. To enhance the spatial quality, outlook, and usability of private open space.
- c. To facilitate solar access to the living areas and private open spaces of the dwelling.

CONTROLS

1. Each dwelling is to be provided with an area of Principal Private Open Space (PPOS) consistent with the requirements of the relevant **Table 12 to Table 16**.
2. The location of PPOS is to be determined having regard to dwelling design, allotment orientation, adjoining dwellings, landscape features and topography.
3. The PPOS is required to be conveniently accessible from the main living area of a dwelling or alfresco room and have a maximum gradient of 1:10. Where part or all of the PPOS is permitted as a semi-private patio, balcony or rooftop area, it must be directly accessible from a living area.

4. Open space at the front of the dwelling can only be defined as PPOS where this is the only means of achieving the solar access requirements of control 1 above. PPOS at the front of a dwelling must be designed to maintain appropriate privacy (for example raised level above footpath or fencing or hedging) and be consistent with the streetscape design controls in **Section 4.2.2**.

4.2.8 Garages, Storage, Site Access and Parking

OBJECTIVES

- a. To control the number, dimensions and location of vehicle access points. To reduce the visual impact of garages, carports and parking areas on the streetscape.
- b. To provide safe, secure and convenient access to parking within garages, carports and parking areas, with casual surveillance of private driveways from dwellings and from the street.
- c. To minimise conflict between pedestrians and vehicles at the junction of driveways and footpaths.
- d. To provide predominantly on-site parking for residents.

CONTROLS

1. 1-2 bedroom dwellings will provide at least 1 car space.
2. 3 bedroom or more dwellings will provide at least 2 car spaces.
3. At least one car parking space must be located behind the building façade line where the car parking space is accessed from the street on the front property boundary.

Note: A car space may include a garage, carport or other hard stand area constructed of materials suitable for car parking and access. The required car parking spaces specified above may be provided using a combination of these facilities, including use of the driveway (within the property boundary only) as a parking space.

4. Vehicular access is to be integrated with site planning from the earliest stages of the project to eliminate/reduce potential conflicts with the streetscape requirements and traffic patterns, and to minimise potential conflicts with pedestrians.
5. Driveways are to have the smallest configuration possible (particularly within the road verge) to serve the required parking facilities and vehicle turning movements and shall comply with AS2890.
6. The location of driveways is to be determined with regard to dwelling design and orientation, street gully pits and trees and is to maximise the availability of on-street parking.

Notes: **Section 3.2** requires plans of subdivision to nominate driveway locations and preferred building envelopes. The design of dwellings should refer to the approved subdivision plans and be consistent with the nominated driveway locations to the greatest practical extent.

Controls for driveways and access to corner lots are contained in **Section 3.1.4 and Figure 11**.

7. Driveways are not to be within 1m of any drainage facilities on the kerb and gutter.
8. Planting and walls adjacent to driveways must not block lines of sight for pedestrians, cyclists and motorists.
9. Driveways are to have soft landscaped areas on either side, suitable for water infiltration.
10. Garages are to be designed and located in accordance with the controls in relevant **Table 12 to Table 16**.

11. Garage design and materials are to be consistent with the dwelling design.

FOR FRONT LOADED GARAGES:

12. Single garage doors should be a maximum of 3m wide and double garage doors should be a maximum of 6m wide.
13. Minimum internal dimensions for a single garage are 3m wide by 5.5m deep and for a double garage 5.6m wide by 5.5m deep.
14. Garage doors are to be visually recessive through use of materials, colours, and overhangs such as second storey balconies.
15. Three car garages are only permitted in the Ridge Area where:
 - At least one of the garage doors is not directly visible from a public road; or
 - One of the car spaces is in a stacked configuration; or
 - The total width of the garage is not more than 50% of the length of the building façade.

FOR GARAGES ACCESSED FROM A LANEWAY OR SHARED DRIVEWAY:

16. Minimum garage door width of 2.4m (single) and 4.8m (double).
17. All garages, site access and parking will be designed in accordance with the **Growth Centres Practice Note: Laneways**.
18. All garages, site access and parking will be designed in accordance with the **Department of Planning and Environment Delivery Note: Laneways**.

4.2.9 Visual and Acoustic Privacy

OBJECTIVES

- a. To site and design dwellings to meet projected user requirements for visual and acoustic privacy, whilst minimising visual and acoustic impacts of development on adjoining properties.

CONTROLS

1. Direct overlooking of main habitable areas and private open spaces should be minimised through building layout, window and balcony location and design, and the use of screening devices, including landscaping.
2. Habitable room windows with a direct sightline to the habitable room windows in an adjacent dwelling within 9 metres are to:
 - be obscured by fencing, screens or appropriate landscaping; or
 - be offset from the edge of one window to the edge of the other by a distance sufficient to limit views into the adjacent window; or
 - have a sill height of 1.7 metres above floor level; or

- have fixed obscure glazing in any part of the window below 1.7 metres above floor level; or
 - second storey windows on side elevations are only to be located at the rear or front of the dwelling.
3. The design of dwellings must minimise the opportunity for sound transmission through the building structure, with particular attention given to protecting bedrooms and living areas.
 4. In attached dwellings, bedrooms of one dwelling are not to share walls with living spaces or garages of adjoining dwellings, unless it is demonstrated that the shared walls and floors meet the noise transmission and insulation requirements of the Building Code of Australia.
 5. Living areas and service equipment such as air conditioning units must be located away from bedrooms of neighbouring dwellings.
 6. Dwellings along arterial and sub-arterial roads should be designed to minimise the impact of traffic noise.

4.2.10 Fencing

OBJECTIVES

- a. To ensure boundary fencing is of a high quality and does not detract from the streetscape.

CONTROLS

1. Front fencing shall be in harmony with the street, consistent in design and style with its dwelling and a maximum of 1m high. Front fences shall not be made of Colorbond. Separate application is to be made for fences higher than 1m and for courtyard walls. Side and rear fencing are to be a maximum of 1.8m high. Front fences and walls are to not impede safe sight lines for traffic.
2. On corner lots the preferred outcome is for the dwelling to front both street frontages providing a better overall streetscape presentation. Where fencing to the secondary street frontage is proposed, it is not to exceed 1.8m high for more than one third of the length of the secondary road frontage, if relevant.
3. On corner lots the front fencing style is to be continued along the secondary street frontage to at least 1m behind the building line of the dwelling. Side fences higher than 1m are not to extend past the Building Façade Line or Garage Building Line.
4. Where a dwelling is located adjacent to open space, boundary fencing is to be of a high quality material and finish. The design of the fencing is to permit casual surveillance of the open space and provide the dwelling with outlook towards the open space. Fencing that adjoins mews or rear access ways is to permit casual surveillance. Colorbond or timber paling or lapped/capped fencing can only be used internally between dwelling lots.
5. Where cut is proposed on the boundary of a lot, retaining walls are to be constructed with side fence posts integrated with its construction (relevant construction details are required with retaining wall approval). Otherwise retaining walls must be located a minimum of 450mm from the side or rear boundary of the lot containing the cut.

5.0

Additional controls for certain dwelling types

5.0 Additional controls for certain dwelling types

5.1 Attached or abutting dwellings

Additional controls for attached or abutting dwellings are outlined below, and should be read in conjunction with those in **Section 4.1.2**.

OBJECTIVES

- a. To ensure that the development of attached or abutting dwellings creates an architecturally consistent street character.

CONTROLS

1. It is preferred that garages for attached dwellings are located at the rear of the lot. Where attached dwellings have frontage to a collector road, all vehicle access and parking is to be located at the rear of the lot.
2. Attached or abutting dwellings should have a pleasing rhythm and order when seen together as a group, rather than appear as a random arrangement of competing dwellings. Each dwelling should benefit from the unified design of the whole form, a co-ordinated style and base colour palette. Individuality can be added as small details or accent colours, rather than strikingly different forms.

5.2 Secondary dwellings, studio dwellings and dual occupancies

Controls for secondary dwellings, studio dwellings or dual occupancies are in part determined by whether the secondary, principal or dual occupancy dwelling is proposed at the time of the application or at some point in the future to be strata subdivided. Strata subdivisions create the need for separate or common property dwelling entries, parking and open space to service each dwelling.

The **Glossary** of this DCP provides further explanation and examples of secondary dwelling, studio dwellings or dual occupancy types. The controls that follow apply to all forms of secondary dwellings, studio dwellings and dual occupancies.

OBJECTIVES

- a. To enable the development of a diversity of dwelling types.
- b. To contribute to the availability of affordable housing.
- c. To promote innovative housing solutions that are compatible with the surrounding residential environment.
- d. To provide casual surveillance to rear lanes.

CONTROLS - SECONDARY DWELLINGS AND STUDIO DWELLINGS

1. Secondary dwellings and studio dwellings are to comply with the controls in **Section 4**, except where the controls in this clause differ, in which case the controls in this clause take precedence.
2. Secondary dwellings and studio dwellings are to comply with the key controls in **Table 17**.
3. The maximum site coverage control for upper floors in the relevant **Table 12 to Table 16** may be exceeded by the combined upper floor coverage of the secondary or studio dwelling and principal dwelling, providing that:
 - The privacy of the principal dwelling and dwellings on adjoining land is not compromised; and
 - Solar access to the principal private open space of neighbouring lots is not significantly reduced.
4. The maximum gross floor area of a studio dwelling is 75m².
5. The finishes, materials and colours of the secondary dwelling or studio dwelling are to complement the principal dwelling in its construction features.
6. For secondary dwellings, windows and private open spaces must not overlook the private open space of any adjacent dwellings. For studio dwellings, windows and private open spaces must not overlook the private open space of any adjacent dwellings including the principal dwelling. Windows that potentially overlook adjacent lots must either have obscured glazing, be screened or have a minimum sill height of 1.5m above floor level.
7. Secondary or studio dwellings and associated garages may have a zero lot setback to one side boundary and may be attached to another garage/secondary dwelling on an adjoining lot, particularly where the secondary or studio dwelling is associated with an attached or semi-detached dwelling.

Table 17 Key controls for secondary dwellings and studio dwellings

Element	Secondary Dwelling	Studio Dwelling (strata)
On-site car parking	No additional car parking space required.	One additional dedicated on-site car parking space. Car parking space to be located behind building façade line of principal dwelling. Car parking space not to be in a stacked configuration.
Principal Private open space	No separate private open space required.	Balcony accessed directly off living space having minimum size of 8.0m ² with minimum dimension of 2m.
Subdivision	Subdivision from principal dwelling not permitted.	Strata title subdivision only from the principal dwelling on the land
Access	Separate direct access to a street, laneway or shared driveway way not required.	Access to be separate from the principal dwelling and is to front a public street, lane or shared private access way. or Combined access for the principal dwelling and secondary dwelling to be through communal land as shown on the strata plan.
Services and facilities	No separate services or facilities required.	Provision for separate services, such as mail delivery and waste collection, and an on-site garbage storage area so that bins are not visible from public street or laneway. To be located on a street address that is able to be accessed by garbage collection and mail delivery services. May be serviced from the front residential street via the principal dwelling lot.

8. Where the secondary or studio dwelling is built to a zero lot line on a side boundary, windows are not to be located on the zero lot wall unless that wall adjoins a laneway, public road, public open space or drainage land.
9. Studio dwellings are to have balconies or living areas that overlook laneways for casual surveillance.
10. Rear garages with secondary or studio dwellings may have first level balconies facing the lane provided the balcony remains within the lot boundary. Where 2m deep, overhanging balconies for private open space requirements of studio dwellings are located along a lane, the application must demonstrate how garages setback underneath avoid creating an overly wide lane and ambiguous space opportunities for illegally parked cars, trailers, bins, etc.
11. Where a secondary or studio dwelling is built over a rear garage and separated from the upper levels of the principal dwelling, there must be a minimum separation of 5m between the upper floor rear façade of the principal dwelling and the secondary or studio dwelling.
12. Studio dwellings are to be located at the rear of the lot only where the lot has access from a rear lane or secondary street on a corner lot.
13. Studio dwellings must comply with separation controls nominated in Australian Standards and the National Construction Code.
14. Studio dwellings are not permitted where the principal dwelling is an attached dwelling, unless:

- The studio dwelling is located above a rear loaded garage; and
- The studio dwelling has direct access to a public road or laneway; and
- Garbage and mail facilities are accessible by residents and by service vehicles.

CONTROLS – DUAL OCCUPANCIES

15. Dual occupancies are to comply with the controls in **Section 4**, except where the controls in this clause differ, in which case the controls in this clause take precedence.
16. The maximum site coverage control for second storeys in the relevant **Table 12 to Table 16** may be exceeded by the combined 2nd storey coverage of both dwellings in a dual occupancy, providing that:
 - The privacy of the principal dwelling and dwellings on adjoining land is not compromised; and
 - Solar access requirements for the principal private open space can be met for the principal dwelling and dwellings on adjoining lots.
17. The design of both dwellings in a dual occupancy development is to be consistent in construction features, finishes, materials and colours.
18. Detached dual occupancy dwellings are not to include zero lot lines for the second dwelling where the second dwelling is located at the rear of the lot.
19. Dual occupancy development is not permitted on a lot that contains an attached dwelling.
20. Dual occupancy dwellings are permitted at the rear of lots (i.e. behind a dwelling that has frontage to a principal street, whether attached or detached to that dwelling) only where:
 - Each dwelling has direct pedestrian and vehicle access to a public road; and
 - Garbage and mail facilities are accessible by service vehicles and by the occupants of the dwellings.
21. Dual occupancy development referred to in control 6 above is preferred to be located on corner lots.
22. For dual occupancies on corner lots, the rear setback can be varied to be consistent with the side setbacks in **Section 4.2.4** provided the minimum private open space and solar access requirements to the proposed and adjoining properties are met.
23. Where the dual occupancy dwellings are to be strata subdivided:
 - private open space is to be provided for each dwelling in accordance with the relevant controls in **Table 12 to Table 16**, or
 - shared private open space is to be provided equivalent to 15% of the site area and shown as communal space on the strata plan, and a minimum area of private open space of 10m² with a minimum dimension of 2.5m is to be provided for each dwelling.
24. The minimum landscaped area on a lot containing a dual occupancy development is to be 20% of the site area.
25. Where practical for front loaded driveway access, shared driveway crossings of the nature strip are to be provided to service both dwellings.

5.3 Multi dwelling housing

OBJECTIVES

- a. To ensure that the design of multi-dwelling housing is consistent with the character of residential areas within the Precinct.
- b. To ensure the quality of multi-dwelling housing is of a high quality and contributes to the amenity of residents.

CONTROLS

1. Multi-dwelling housing sites are to have direct frontage to a public road (i.e. not on battle-axe lots).
2. Multi-dwelling housing is to comply with the controls in **Table 18**.
3. Controls for adaptable dwellings (requirement triggered by minimum number of dwellings in development, located elsewhere in DCP) also apply to multi-dwelling housing. Adaptable dwellings are preferably to be single level accommodation at ground level and be located on the street frontage.
4. A landscape plan is to be submitted with every application for multi-dwelling housing.
5. Where a multi dwelling housing development includes a studio dwelling with rear lane vehicle access, the controls for a studio dwelling shall apply.

Table 18 Key controls for multi dwelling housing

Element	Controls
Site coverage (maximum)	50%
Landscaped area (minimum)	30% of site area
Principal Private open space (PPOS)	Min 16m ² with minimum dimension of 3m. 10m ² per dwelling if provided as balcony or rooftop with a minimum dimension of 2.5m.
Front setback (minimum)	4.5m to building façade line; 3.0m to articulation zone
Corner lots secondary street setback (min)	2m
Side setback (minimum)	Ground floor 0.9m. Upper floor 0.9m
Rear setback (minimum)	4m (excluding rear lane garages or studio dwellings) 0.5m to rear lane (garages or studio dwellings)
Zero lot line (minimum)	Not permitted on adjacent lot boundaries (except rear lane garages and studio dwellings)
Internal building separation distance (minimum)	5m (unless dwellings are attached by a common wall)
Car parking spaces	1 car parking space per dwelling, plus 0.5 spaces per 3 or more bedroom dwelling, plus 1 visitor space per 5 dwellings. Car parking spaces to be behind building line or garages fronting the street to be set back a minimum of 1m from the building setback. Where garages front the street, the maximum width of a garage door is 6m and each garage is to be separated by a dwelling façade or landscaped area.
Garages and car parking dimensions (minimum)	Covered: 3m x 5.5m Uncovered: 2.5m x 5.2m Aisle widths must comply with AS 2890.1 1-2 bedroom dwellings will provide at least 1 car space. 3 bedroom or more dwellings will provide at least 2 car spaces.

5.4 Controls for residential flat buildings, manor homes and shop top housing

The controls in **Clause 5.3** do not apply to residential flat buildings, manor homes and shop top housing, unless specifically referenced in the provisions that follow. The following clauses set out the controls for these types of housing. Additional controls for residential flat buildings and shop top housing may be contained in *SEPP 65 – Design Quality of Residential Apartment Development*.

OBJECTIVES

- a. To establish a high quality residential environment where all dwellings have a good level of amenity.
- b. To encourage a variety of housing forms within residential areas.
- c. To ensure the provision of housing that will, in its adaptable features, meet the access and mobility needs of any occupant.
- d. To ensure shop top housing and mixed use developments are appropriate in terms of form and scale for their location.
- e. To ensure shop top housing and mixed use developments reflect the role of centres as articulated within Council's Centres Direction.

CONTROLS

1. In density areas of 20dw/Ha and 25dw/Ha, manor homes may only be located on corner lots.
2. Residential flat buildings are to:
 - be located on sites with a minimum street frontage of 30m;
 - have direct frontage to an area of the public domain (including streets and public parks); and
 - not adversely impact upon the existing or future amenity of any adjoining land upon which residential development is permitted with respect to overshadowing impact, privacy impact or visual impact.
3. All residential flat buildings are to be consistent with:
 - the guidelines and principles outlined in *SEPP No. 65 – Design Quality of Residential Apartment Development*; and
 - the primary controls set out in **Table 19**, which take precedence over the above where there is any inconsistency.
4. In all residential flat building developments containing 10 dwellings or more, a minimum of 10% of all apartments are to be designed to be capable of adaptation for access by people with all levels of mobility. Dwellings must be designed in accordance with the *Australian Adaptable Housing Standard (AS 4299-1995)*, which includes 'pre-adaptation' design details to ensure visitability is achieved.
5. Where possible, adaptable dwellings are to be located on the ground floor. Dwellings located above the ground level of a building may only be provided as adaptable dwellings where lift access is available within the building. The lift access must provide access from the basement to allow access for people with disabilities.
6. The development application must be accompanied by certification from an accredited Access Consultant confirming that the adaptable dwellings are capable of being modified, when required by the occupant, to comply with the *Australian Adaptable Housing Standard (AS 4299-1995)*.

7. Car parking and garages allocated to adaptable dwellings must comply with the requirements of Australian Standards for disabled parking spaces.
8. A landscape plan is to be submitted with every application for residential flat buildings.

Table 19 Key controls for residential flat buildings, manor homes and shop top housing

Element	R1 and R4 zones (shop top housing and residential flat buildings as mixed use developments)	R4 zone (residential flat buildings)	R4 zone (manor homes)	B2 zone (shop top housing)
Building and ceiling height	Minimum floor to ceiling heights are: 3.3m for commercial floors 2.7m for residential floors	N/A	N/A	The applicable height of buildings standard under Clause 6.8 of The Hills Growth Centre (Box Hill) Precinct Plan equates to the following maximum building heights in storeys: 10 metres: 3 storeys 20 metres: 6 storeys Minimum floor to ceiling heights are: 3.3m for commercial floors 2.7m for residential floors
Site coverage (maximum)	N/A	50%	50% of site area	N/A
Landscaped area (minimum)	Required within setbacks and common open space areas	30% of site area	30% of site area	Required within setbacks and common open space areas
Communal open space	20m ² per dwelling where the development includes 5 or more dwellings 75% must be provided at ground level and well landscaped Common open space must only be accessible by the residents of the development	15% of site area	Not required.	20m ² per dwelling where the development includes 5 or more dwellings 75% must be provided at ground level and well landscaped Common open space must only be accessible by the residents of the development

Element	R1 and R4 zones (shop top housing and residential flat buildings as mixed use developments)	R4 zone (residential flat buildings)	R4 zone (manor homes)	B2 zone (shop top housing)
Principal Private open space (PPOS)	Ground level 4m x 3m Min 10m ² per dwelling with minimum dimension 2.5m	Min. 10m ² per dwelling with min. dimension of 2.5m	Minimum 16m ² per dwelling with min. dimension of 3.0m; or Min. 8m ² per dwelling with min. dimension of 2.0m if provided as balcony or rooftop.	Ground level 4m x 3m Min 10m ² per dwelling with minimum dimension 2.5m
Front setback (minimum)	Zero if active frontage provided 3m if no active frontage provided 3m for residential floors above the first level	6m Balconies and other articulation may encroach into the setback to a maximum of 4.5m from the boundary for the first 3 storeys, and for a maximum of 50% of the façade length.	4.5m to building façade line. 3m to articulation zone. 5.5m to garage line and 1m behind the building line.	Zero if active frontage provided 3m if no active frontage provided 3m for residential floors above the first level
Corner lots secondary street setback (minimum)	As per front setbacks	6m	2m	As per front setbacks
Side setback (minimum)	6m where adjoining low density residential development 3m where not adjoining low density residential development	Buildings up to 3 storeys: 3m Buildings above 3 storeys: 6m	Buildings up to 2 storeys 1.5m	6m where adjoining low density residential development 3m where not adjoining low density residential development
Rear setback (minimum)	As per side setbacks	6m	4m (excluding rear garages)	As per side setbacks
Zero lot line (minimum)	N/A	Not permitted	Not permitted to adjacent lots	N/A
Habitable room/balcony separation distance (minimum) for buildings 3 storeys and above	12m	12m	N/A	Refer to Other Part of DCP regarding B zonings.
Access and entries	Separate site and building access points are to be provided for the residential and commercial components of developments.	N/A	N/A	Separate site and building access points are to be provided for the residential and commercial components of developments.

Element	R1 and R4 zones (shop top housing and residential flat buildings as mixed use developments)	R4 zone (residential flat buildings)	R4 zone (manor homes)	B2 zone (shop top housing)
Car parking spaces	<p>In accordance with The Hills DCP 2012 Part C Section 1 – Parking</p> <p>Preferred location for parking is within a basement or to the rear of developments</p>	<p>1 space per dwelling, plus 0.5 spaces per 3 or more bedroom dwelling.</p> <p>May be in a 'stack parking' configuration.</p> <p>Car parking spaces to be located below ground or behind building line</p> <p>1 visitor car parking space per 5 apartments</p> <p>Bicycle parking spaces: 1 per 3 dwellings</p>	<p>1-2 bedrooms: 1 space (min)</p> <p>3 bedrooms or more: 2 spaces (min) – may be provided in a 'stack parking' configuration.</p>	<p>In accordance with The Hills DCP 2012 Part C Section 1 – Parking</p> <p>Preferred location for parking is within a basement or to the rear of developments</p>
Garage Dominance	N/A	A maximum of two garage doors per 20m of lot frontage facing any one street frontage.	A maximum of two garage doors facing any one street frontage.	N/A
Garages and car parking dimensions (min)	<p>Covered: 3m x 5.5m</p> <p>Uncovered: 2.5m x 5.2m</p> <p>Aisle widths must comply with AS 2890.1</p>			
Other controls	Refer to the Residential Flat Building or Business Sections of The Hills DCP 2012 for controls relating to unit size/mix, visual privacy, solar access, private open space, ventilation, storage and waste management.	N/A	N/A	Refer to the Residential Flat Building or Business Sections of The Hills DCP 2012 for additional controls relating to unit size/mix, visual privacy, solar access, private open space, ventilation, storage and waste management.

5.4.1 Site Servicing

OBJECTIVES

- To ensure that site facilities are functional and accessible to all residents and are easy to maintain.
- To ensure that site facilities are thoughtfully integrated into the development and are visual and physically unobtrusive.
- To minimise the impact of service access on pedestrians and retail, commercial and residential frontage.
- To minimise the visual and acoustic impact of site servicing.

CONTROLS FOR RESIDENTIAL FLAT BUILDINGS AND MULTI DWELLING HOUSING:

1. Garbage, mail box structures, service meters and the like are to be integrated with the overall design of the buildings and/or landscaping. Garbage storage areas are not permitted at the front of the development.
2. Provide communal or individual laundries to every dwelling and at least one external clothes drying area per building. Laundries are not permitted in front setbacks and must be appropriately screened from view if located in the side setback.
3. Loading facilities must be at the rear of each development.
4. Service access is permitted from rear lanes, side streets or right of ways.

5.5 Adaptable housing

OBJECTIVES

- a. To ensure a sufficient proportion of dwellings include accessible layouts and features to accommodate changing requirements of residents.
- b. To ensure the provision of housing that will, in its adaptable features, meet the access and mobility needs of any occupant.

CONTROLS

1. 10% of all apartments, multi dwelling housing and Residential Flat Buildings are to be designed to be capable of adaptation for disabled or elderly residents. Dwellings must be designed in accordance with the Australian Adaptable Housing Standard (AS 4299-1995).
2. Where possible, adaptable dwellings are to be located on the ground floor, for ease of access. Dwellings located above the ground level of a building may only be provided as adaptable dwellings where lift access is available within the building. The lift access must provide access from the basement to allow access for people with disabilities.
3. The development application must be accompanied by certification from an accredited Access Consultant confirming that the adaptable dwellings are capable of being modified, when required by the occupant, to comply with the Australian Adaptable Housing Standard (AS 4299-1995).
4. Car parking and garages allocated to adaptable dwellings must comply with the requirements of the relevant Australian Standard for disabled parking spaces.

5.6 Other development in residential areas

The residential zones within the Precinct Plan permit a range of non-residential land uses which, depending on their scale, suitability, location and design, may be compatible with adjoining residential uses. The Precinct Plan recognises that allowing non-residential development in the residential zones is appropriate providing controls are in place to minimise the negative impacts of noise, loss of privacy, traffic, and parking on residential amenity.

The controls for non-residential development consist of:

- General requirements, which apply to all non-residential development in residential zones.
- Specific provisions covering land uses such as child care centres, neighbourhood shops, educational establishments and places of public worship, in addition to, or overriding, the general requirements.

Notes: *In the event of an inconsistency between the general and specific provisions in this section of the DCP, the specific controls will prevail.*

These controls are not intended to apply to home occupations.

Council may require the submission of additional information to demonstrate that the development will not adversely affect the existing or future amenity of the surrounding residential area. Such information may include a noise impact assessment, advice on traffic generating potential and parking provision, solar access and evidence that the proposed land use will contribute to the amenity, character and liveability of the residential area in which it is to be located. Applicants should consult with Council prior to submitting a development application to determine specific information requirements.

5.6.1 General requirements

OBJECTIVES

- a. To establish appropriate controls to minimise the adverse effects of non-residential development on surrounding residential development.
- b. To maintain consistency in development standards between non-residential and residential land uses and ensure that buildings are similar in height, bulk and scale to surrounding buildings.
- c. To ensure that non-residential development is appropriately located.
- d. To avoid concentrations of non-residential uses in any particular area where the cumulative impact on residential amenity would be unacceptable.

CONTROLS

1. Except as provided for in the specific controls below, non-residential development on residential zoned land is to be located on allotments that have a frontage width of greater than 15 metres.

Note: *The relevant Precinct Plan specifies minimum site area development standards for some non-residential land uses within residential zones.*

2. Non-residential development on residential zoned land is to comply with the requirements of **Section 4.11** of this DCP in relation to sustainable building design.
3. For all non-residential development, the controls relating to lots with frontages greater than 15 metres in the following clauses of this DCP apply:
 - Clause 4.2.3 Front setbacks;
 - Clause 4.2.5 Dwelling massing and siting; and
 - Clause 4.2.6 Landscape area.

4. Non-residential development is not permitted on battle-axe allotments.
5. The maximum site coverage of buildings is 60% of the total site area.
6. The minimum landscaped area for non-residential development is 20% of the total site area of the allotment.
7. Provision of car parking for non-residential uses will be assessed by Council on an individual basis, and with reference to local policies that may establish relevant parking requirements, but must be sufficient to meet demand generated by staff and visitors.
8. Where a non-residential use is proposed as part of, or in association with, a dwelling (e.g., a home business):
 - Parking and storage areas are to be located behind the building façade or be screened from view from the street by landscaping.
 - Parking and storage areas are not to encroach on the private open space or landscaped area of the dwelling.
9. Council will have particular regard to the effects of non-residential development in the residential zones. Council will consider whether:
 - the proposed development will be out of character with surrounding residential development, particularly in relation to the height and/or scale of any proposed buildings the proposed development will contribute to an undesirable clustering of that type of development, or non-residential uses in general, in the area;
 - an undesirable effect on the amenity of the surrounding area will be created;
 - the proposed use will draw patronage from areas outside of the surrounding neighbourhood, and the extent to which that patronage might impact on the amenity of residents through factors such as traffic generation, noise or the overall scale of the non-residential use;
 - a noise nuisance will be created;
 - the development will generate traffic out of keeping with the locality;
 - adequate facilities are provided for the purposes of parking, loading and deliveries;
 - adequate provision is made for access by disabled persons.
10. Non-residential development in residential zones should be similar in bulk, scale, height and siting to the surrounding buildings
11. Finishes, materials, paving and landscaping are to be consistent with those of surrounding residential development.

5.6.2 Exhibition homes and Exhibition Villages

OBJECTIVES

- a. To ensure that exhibition homes and exhibition villages operate with minimal impact on surrounding residential areas.
- b. To ensure that exhibition homes and exhibition villages operate for a limited time after which they revert to a conventional residential environment.

CONTROLS

1. Any subdivision of land shall be in accordance with the requirements for dwellings in this DCP.
2. Any proposed street within an exhibition village may be held as one lot within the development until the cessation of the operation of the exhibition village. Subdivision and dedication of roads to Council must be completed prior to the use of dwellings for residential accommodation.
3. Exhibition villages should be located on Collector Roads or as close to Collector Roads as possible, with vehicle access from a Collector Road.
4. Exhibition homes / exhibition villages are not permitted:
 - where access is from a street with a carriageway width of less than 9.0 metres.
 - on streets which are cul-de-sacs.
5. Car parking for exhibition homes shall be provided off street. However, on-street car parking may be considered where there are no privately occupied dwellings opposite or adjoining the individual exhibition homes.
6. Internal streets may be closed out of hours of operation only where the streets are not yet dedicated as public roads.
7. During the operation of an exhibition home / exhibition village additional measures to maintain the privacy of adjoining residential development may be required.
8. The hours of operation shall be limited to 7am to 7pm each day.
9. Buildings used for such uses as providing home finance, materials display or take-away food and the like shall cease to operate when the exhibition home / exhibition village ceases unless separate approval is obtained to enable the continued operation of these uses.
10. Temporary buildings used for providing home finance, materials display or take-away food shall be removed and the site made good.
11. When the use of the dwelling ceases to be an exhibition home, any garage that has been used as a sales office is to be reinstated as a functioning garage with an appropriate garage door and associated driveway, prior to the occupation of the dwelling for residential purposes.
12. When the exhibition village / home ceases to operate, all signs and structures etc. associated with the exhibition home / village shall be removed to ensure the site has a residential appearance.
13. Security lighting shall be provided in such a way to minimise any adverse impact on adjoining residential areas.
14. The operation of the exhibition village (including the use of designated off-street car parks) shall not cause offensive noise or affect the acoustic amenity of adjoining residents.
15. Waste disposal facilities shall be provided. These shall be located adjacent to the driveway entrance to the site.
16. Any structure involving waste disposal facilities shall be located as follows:
 - Set back one metre from the front boundary to the street.
 - Landscaped between the structure and the front boundary and adjoining areas to minimise the impact on the streetscape.
 - Not be located adjacent to an adjoining residential property.

17. All works affecting public roads, including new driveways, access roads and intersection works are to be in accordance with the requirements of this DCP and Council's engineering specifications.
18. Landscaping of streets is to be in accordance with the requirements of this DCP, and street landscaping is to be maintained for the duration of operation of the exhibition home / village.
19. Dedication of public roads to Council will be subject to satisfactory provision and maintenance of street landscaping.
20. Dwellings located near future sources of noise are to incorporate appropriate noise attenuation measures when designed and constructed, to ensure that future residents are afforded an appropriate level of amenity.
21. Details of proposed signage are to be submitted with the Development Application. Signage is to be located on public roads at or near the entry to the exhibition home / village. Internal signage within the exhibition village is to be visible only from within the village (not from surrounding residential properties). When considering applications including signage, Council will refer to controls in other Council policies and planning controls that may be applicable.

5.6.3 Child Care Centres

Please refer to The Hills DCP 2012 Part B Section 6 - Business (Appendix E).

5.6.4 Educational Establishments and Places of Worship

OBJECTIVES

- a. To ensure appropriate provision and equitable distribution of educational establishments and places of public worship within the Precinct.
- b. To ensure that buildings are not out of character with the type, height, bulk and scale of surrounding buildings.
- c. To encourage the appropriate location of facilities to create community focal points, centres of neighbourhood activity and enhance community identity.
- d. To mitigate the impacts of noise, privacy, increased traffic and nuisance on surrounding residential development.
- e. To foster iconic and landmark building design within each Precinct.

CONTROLS

1. Places of worship are to be located within centres or co-located with other community facilities in residential areas so as to create a community focal point, to share facilities such as parking, and to minimise impacts on residential areas.
2. Places of public worship and educational establishments are preferably to be located on land with frontage to a collector road and must not be located on land that has a direct frontage to a classified road. Corner sites are preferred.
3. In assessing applications, Council will consider the following:

- the privacy and amenity of adjoining developments;
 - the need and adequacy for provision of buffer zones to surrounding residential development;
 - urban design;
 - location;
 - the size of the land where the development is proposed;
 - traffic generation and the impacts of traffic on the road network and the amenity of nearby residents;
 - the availability of parking;
 - the scale of buildings and their capacity; and
 - hours of operation and noise impacts.
4. traffic and transport report/statement is to accompany the Development Application addressing the impact of the proposed development on the local road system and defining car parking requirements.

Note: Due to the high level of traffic generation and peak nature of traffic volumes accessing these types of land uses, assessment of traffic impacts and pedestrian requirements is required and mitigation measures may need to be incorporated in the design. Such measures may include pedestrian crossings, speed control devices, pedestrian refuges on streets to which the development fronts and the provision of bus and drop off bays. School zones will require additional safety measures such as school crossings, 40 km/h school speed zones and flashing lights in accordance with RMS requirements.

5. A landscape plan and associated documentation is to be submitted with the Development Application identifying existing vegetation and community plant species and/or existing design elements of the site layout, and the proposed landscaping treatment of the development.
6. Car parking spaces shall be provided on site in accordance with **Table 20**, unless the applicant can demonstrate to the satisfaction of Council that lower rates of parking are reasonable for the particular development.

Table 20 Car parking requirements for places of public worship and educational establishments

Land Use	Parking requirement
Places of Public Worship	1 space per 6 seats, plus 1 bicycle and 1 motorcycle space per 25 car parking spaces in excess of the first 25 car parking spaces
Schools	1 space per staff member Plus 1 space per 100 students Plus 1 space per 5 students in Year 12 (based on estimated capacity for year 12 students to be specified in the Development Application)
Tertiary and Adult Educational Establishments	1 space per 5 seats Or 1 space per 10m ² of floor area (whichever is greater)

7. For certain uses, the provision of overflow parking may be necessary particularly where such developments incorporate halls used for social gatherings. Overflow parking areas could be provided on open grassed areas and need not be formally sealed or line-marked. Proposed overflow parking areas are to be clearly shown on plans submitted with the Development Application.

8. Development must be designed to minimize the possibility of noise impacts to the occupants of adjoining or neighbouring dwellings.
9. Where it is likely that a development may cause an adverse noise impact on nearby residential areas, an acoustic report will be required to be submitted to council with the Development Application,
10. Development must comply with Office of Environment and Heritage noise guidelines.
11. Where appropriate, buffers should be put in place to limit noise impacts on the surrounding area. Extensive noise walls along most or all of a property boundary are not appropriate and other measures should be used to mitigate noise.
12. Sources of noise such as garbage collection, machinery, parking areas and air conditioning plants are sited away from adjoining properties and screened / insulated by walls or other acoustic treatment. Noise levels are not to exceed specified limits at the most affected point of the property boundary.
13. The general hours of operation for places of public worship and educational establishments are between 7am and 9pm.
14. Variation to the approved hours of operation may be approved by Council subject to other requirements or a merit assessment.

Note: Legislation covering noise impacts and hours of operation is the *Protection of the Environment Operations Act 1997* and the *Protection of the Environment (Noise Control) Regulation 2000*. Applicants should also refer to the Office of Environment and Heritage website (<http://www.environment.nsw.gov.au>) for more information regarding noise control.

5.6.5 Neighbourhood Shops

OBJECTIVES

- a. To ensure the appropriate provision of retail uses to serve the needs of the local community.
- b. To minimise the impacts of retail activities on surrounding residential areas.
- c. To ensure that retail activities in residential areas do not detract from the function or viability of nearby centres.
- d. To ensure the appropriate location of neighbourhood shops.

CONTROLS

1. Neighbourhood shops in the R2 and R3 zones may only be developed on an allotment of land with a frontage width of 15 metres or more.
2. Neighbourhood shops in the R2 and R3 zones are to be located:
 - adjoining land zoned RE1 or SP2 or that is separated from land zoned RE1 or SP2 only by a public road, or
 - with frontage to a collector road, or
 - within 90 metres of public transport stop, or

- adjoining an educational establishment or a community facility or separated from an educational establishment or a community facility only by a public road.
3. For neighbourhood shops, the controls relating to lots with frontages greater than 15 metres in the following clauses of this DCP apply:
 - Clause 4.2.2 Architectural design and streetscapes;
 - Clause 4.2.3 Front setbacks;
 - Clause 4.2.5 Dwelling massing and siting; and
 - Clause 4.2.6 Site coverage and landscape area.
 4. Shops fronts are to encourage active and interactive street frontages that are sympathetic to the streetscape with similar materials to adjoining buildings to be used.
 5. Any area of land between the front property boundary and the building alignment, exclusive of approved driveways and parking areas, is to be landscaped to the satisfaction of Council.
 6. Address and entry points for any residential use on the same allotment of land are to be separate from the retail use access points and be readily identifiable.
 7. Design of the building frontage, front and side setbacks are to include safe and convenient pedestrian facilities such as weather protection, shade, seating and landscaping.
 8. On corner sites, shop fronts are to wrap around the corner and zero setbacks are permitted.
 9. Entrances are to be visible from the street and well lit.
 10. The site should not gain direct access to:
 - A road with clearway or other parking restrictions; or
 - A restricted access road (sub-arterial, arterial or Transit Boulevard). Any proposed development should not to create a traffic hazard. However, corner sites are preferred in terms of reducing potential for impacts on neighbouring properties, and for allowing side access for customer parking and deliveries.
 11. One car parking space is to be provided for every 30m² of Gross Floor Area.
 12. Parking spaces are to be provided on site or in dedicated on street parking constructed to Council's standards.
 13. The design of the building and parking areas is to provide suitable access for people with disabilities and service deliveries.
 14. Bicycle parking must be provided in a location that is secure and accessible with weather protection for employees.
 15. Car parking must be clearly signposted to indicate its availability from the street.
 16. Plant and equipment (particularly cooling or heating plant), is to be located so as to not cause noise annoyance to neighbours) - noise impact assessment may be required to be prepared and submitted to Council.
 17. Waste storage areas must be designed to minimise visual impact and should be screened and properly positioned so as to not to attract pests and cause odour problems for neighbours.

18. All goods storage is to be internal.

5.6.6 Seniors Housing

SEPP (Housing for Seniors or People with a Disability) 2004 is the primary environmental planning instrument controlling seniors housing. Applicants considering development of this kind should refer to that SEPP for specific controls and to determine the permissibility of seniors housing.

6.0

Employment Areas

6.0 EMPLOYMENT AREAS

6.1 Lot Subdivision

6.1.1 Lot Size and Orientation

OBJECTIVES

- a. To ensure adequate opportunity for landscape design that accommodates perimeter planting and attractive buildings located around entrances and visible areas.
- b. To allow for a range of allotment sizes that caters for a diversity of land uses and employment opportunities within the Precincts.
- c. To ensure allotments are oriented to ensure buildings appropriately address the public domain.

CONTROLS

1. Lots are to be relatively regular in shape to meet a range of land uses. These may range from those requiring wide street frontages and a minimum depth to those that require less frontage but a greater depth. Irregular shaped allotments with narrow street frontages should be avoided, particularly where several of these are proposed in an adjoining manner.

Lots should be orientated and aligned:

- so that future buildings can face the local streets to increase visual surveillance and to avoid streetscapes with loading docks and long blank walls;
 - to facilitate solar efficiency;
 - to encourage building design that has frontage to landscaped areas and riparian corridors.
2. Access to lots shall be sited to ensure that sight lines are unimpeded when entering and exiting the lot.
 3. Subdivisional roads should incorporate road hierarchies that will accommodate the anticipated traffic volumes and heavy vehicle types and be practical, safe and legible for all road users.
 4. Where a residue lot is created through subdivision, the applicant must demonstrate that future development of that residue lot can meet the controls in this DCP.

6.1.2 Site Coverage and Landscaped Area

OBJECTIVES

- a. To ensure a balance between built form and landscape in order to provide a high level of amenity and landscape character.
- b. To ensure an integrated design solution which takes into consideration the provision of deep soil planting, shade/solar access and drainage.
- c. To allow for future tree planting.

CONTROLS

The site coverage for any development must comply with **Table 21**.

Table 21 Site coverage

Employment Area	Maximum site coverage
B7 Business Park zones	50%
IN2 Light Industrial / B6 Enterprise Corridor zones	65%

1. For buildings in the Windsor Road Business Park, the minimum building footprint shall be 1,500m².
2. Deep soil planting must be provided in accordance with **Table 22** below.

Table 22 Deep soil planting

Employment Area	Minimum Deep Soil Planting Area
B7 Business Park zones	25% of total site area
IN2 Light Industrial / B6 Enterprise Corridor zones	10% of total site area

3. The minimum width of landscaped areas is 2m, with the exception of landscaping within battle axe handles. The minimum width of landscaped areas within battle axe handles is 0.5m on each side of the handle.
4. For development in the Windsor Road Business Park, one area of at least 20m x 20m must be provided as part of the deep soil planting requirement.
5. Landscaped areas are required between buildings (i.e. within the building separation zone).

6.1.3 Strata or Community Title

CONTROLS

1. Where a Strata or Community Title subdivision is proposed, any space for parking or other purposes forming part of a sole occupancy unit required by Council must be included in the same strata lot as the unit. All landscaping, access areas and directory board signs not forming part of an individual unit will be required by Council to be included in any strata plan of subdivision as common property.

6.2 Built form

6.2.1 Setbacks

OBJECTIVES

- a. To define building envelopes within each allotment by specifying minimum setbacks.
- b. To achieve attractive streetscapes.
- c. To ensure buildings present an acceptable scale and bulk when viewed from the public domain.

CONTROLS

GENERAL

1. In employment areas, no building or hardstand area (concrete or bitumen pavement) other than a public utility undertaking shall be erected within any setback.
2. All setback areas should be landscaped and maintained.
3. Pedestrian access should be provided to all landscaped setback areas for maintenance and security purposes, but is not to be included in the designated landscape setback area.
4. No storage of any kind is permitted within the landscaped setback areas.
5. The landscape setback areas should be designed to create attractive views from the public domain and reduce the bulk and scale of development.
6. Council may increase the minimum setback where the proposed development is of a bulk and scale out of character with existing development within the zone, or where the proposed landscape techniques are not sufficient to ameliorate the visual impact of the proposed development.

FRONT SETBACKS

7. All development is to be consistent with the front setback controls and principles **Table 23**, **Figure 43** and **Figure 44**.

Table 23 Front setbacks

Employment Area	Building façade line	Articulation zone
R1 General Residential	Zero setback to Terry Road	
B7 Business Park zones	20m from Annangrove Road 21m setback for all buildings with direct frontage to Windsor Road (refer Figure 43) 5m setback to all other streets	
IN2 Light Industrial / B6 Enterprise Corridor zones	20m from roads fronting residential areas and Annangrove Road (refer Figure 43) 7m to all other boundaries	Offices and showrooms may be set back a minimum of 2m from the boundary as shown in Figure 43

8. Front setback areas to public roads are to be landscaped and maintained as open areas only, so as to enhance the streetscape appearance of all employment areas.



Figure 43 Location of 20m and 21m front setbacks in employment areas




Figure 44 Front setbacks in Windsor Road Business Park

SIDE AND REAR SETBACKS

9. All development is to be consistent with the side and rear setback controls in **Table 24**.

Table 24 Side and rear setbacks

Employment Area	Side setback	Rear setback
R1 General Residential* and B7 Business Park zones	6m	6m
IN2 Light Industrial / B6 Enterprise Corridor	3m	3m
IN2 Light Industrial / B6 Enterprise Corridor adjoining a residential street	20m	6m

*Applies to developments comprising only commercial uses. Refer to Table 19 for controls relating to shop top housing in the R1 General Residential zone.

10. A maximum 2m width of paved area will be permitted within side and rear setbacks for the purposes of providing for pedestrian links through properties.

6.3 Building Layout and Orientation

OBJECTIVES

- To provide a variety of building orientation.
- To ensure buildings maximise aspect and take advantages of views within and beyond the Precincts.
- To optimise building orientation and siting to natural elements such as topography, wind and sunlight.
- To create defined streetscapes.
- To activate streets with building frontages.

CONTROLS

R1 GENERAL RESIDENTIAL AND B7 BUSINESS PARK ZONES

- West facing elevations must provide for effective sun shading.

IN2 LIGHT INDUSTRIAL AND B6 ENTERPRISE CORRIDOR ZONES

- The layout and orientation of buildings should be in a manner that minimises lengthy or deep areas of car parking along the street front, as well as lengthy loading areas facing residential areas. Refer to **Figure 45**.




Figure 45 Typical building layout in Annangrove Road Employment Area

6.3.1 Building Separation

OBJECTIVES

- To allow solar access to buildings and communal areas.
- To allow for deep soil planting between buildings.

- c. To provide a visual break between buildings and reduce the perceived bulk and scale of the built environment.
- d. To provide outlook from buildings.
- e. To allow for adequate air flow between buildings particularly in odour affected areas.

CONTROLS

1. Building separation must comply with the following **Table 25**:

Table 25 Building separation

Employment Area	Minimum Building Separation
B6 Enterprise Corridor, B7 Business Park zones and IN2 Light Industrial zone	<p>20m separation between buildings facing each other within a site.</p> <p>12m separation between buildings perpendicular to each other within a site where the width of the facing façades does not exceed 26m.</p> <p>10m separation between buildings perpendicular to each other within a site where the width of the facing façades is 20m or less.</p>

2. Separation between buildings must be sufficient so as to enable solar access, as shown in **Figure 46**.




Figure 46 Building separation

6.3.2 Floor to Ceiling Height

OBJECTIVES

- a. To encourage creative and innovative building design of a high architectural standard that reflects the natural, functional and aesthetic opportunities.
- b. To encourage quality and consistency in the treatment of façades, external finishes and the like.
- c. To ensure sufficient visual relief is achieved on façades visible from adjoining sites and the public domain, including major thoroughfares.
- d. To achieve an appropriate mix of scale and form.

CONTROLS

The minimum floor to ceiling height of buildings are to comply with **Table 26**.

Table 26 Floor to ceiling height

Employment Area	Minimum Ceiling Height
R1 General Residential and B7 Business Park zones	Ground level – 3.6m Upper levels – 2.7m
IN2 Light Industrial zone and B6 Enterprise Corridor zones	Ground level – 3.6m

6.3.3 Sustainable Building Design

OBJECTIVES

- To ensure that developments are environmentally sustainable in terms of energy and water use.
- To minimise consumption of potable water and waste water discharge.
- To maximise opportunities for natural ventilation where appropriate in the Windsor Road Business Park.
- To ensure that development incorporates water conservation and re-use measures into design and operation.
- To ensure building depth allows for adequate solar access.

CONTROLS

- New commercial buildings must achieve a minimum 4 star Green Star rating from the Green Building Council of Australia. Refer to both GBCA's 'Green Star – Office As Built Technical Manual' and the 'Green Star Office As Built Technical Manual'.
- New industrial and light industrial buildings must achieve a minimum 4 star Green Star rating from the Green Building Council of Australia from such time that an Industrial Tool has been adopted.
- Buildings must install rainwater tanks to meet a portion of supply such as outdoor use, toilets or laundry. Tanks should provide a minimum of 85 litres per square metre of vegetated areas (including grass).
- The roof area should be directed to a rainwater tank and should be maximised to both increase the effectiveness and reliability of the reuse system.
- Development shall incorporate water efficient fixtures such as taps, showerheads, and toilets. The fixtures must be rated to at least AAA under the National Water Conservation Rating and Labelling Scheme. Where the building or development is water intensive (i.e. high water user), specific water conservation objectives must be resolved with Council.
- Appropriate use of energy efficient materials during construction is to be demonstrated.
- Development should incorporate energy efficient hot water systems, air-conditioning, lighting and lighting control systems.
- Any commercial building with a depth greater than 20m shall have an atrium to permit solar access and natural ventilation, unless it is demonstrated that at least 60% of the Net Lettable Area (NLA) has a Daylight Illuminance (DI) of 250 lux.

6.3.4 Architectural Design

OBJECTIVES

- a. To enhance the visual quality of development in the Precincts through the selection of appropriate materials and colours.
- b. To encourage the use of materials that minimise impact on the environment.
- c. To ensure that any reflective materials are used with sensitivity to neighbouring development, vehicular traffic and public domain areas.
- d. To ensure that ancillary buildings, storage and service areas are considered part of the overall design, and do not detract from the amenity and appearance of the development.
- e. To create distinctive high quality gateways to the Precincts.
- f. Create identifiable, attractive and safe entrances to buildings.
- g. To use fencing to define boundaries and provide security, as well as contribute to streetscape and amenity of the Precincts.
- h. To ensure that signage and lighting supports the visual appearance of the building and the visual appeal of the Precincts.

CONTROLS

BUILDING DESIGN AND SITING

1. Building designs within the Windsor Road Business Park and Annangrove Road Employment Area will be assessed based on aesthetic merit and technology, based on the following design principles:
 - Buildings should provide variety to façades by the use of projecting upper storeys over building entries, upper storey display windows, emphasising street corners and varying roof forms;
 - Buildings should provide effective sunshading for windows, wall surfaces and building entries (other than loading docks) by the use of design elements such as overhanging eaves and awnings, undercrofts, colonnades and external sunshading devices including screens;
 - Building design should be integrated with landscape elements;
 - The bulk and scale of the building should minimise impact on district views;
 - Building façades should be articulated by elements such as:
 - . External structures, finishes, etchings and recessed patterns;
 - . Decorative features, textures and colours;
 - . Locating offices and highlighting entries within front façades;
 - . Emphasised customer entries and service access doors; and
 - . Protrusions and penetrations in building elements;
 - Buildings with dual street frontage should be designed to ensure:
 - . The building addresses the primary street frontage; and

- Distinctive identifying architectural elements are incorporated to provide sufficiently interesting and varied façades;
 - The building design should consider the amenity of any adjoining landscaped areas;
 - The location of roller shutters, loading docks and other building openings should be so that they do not detract from the overall appearance of the building. Where possible, roller shutters and the like should not be located on the primary street frontage; and
 - Roof design should be visually interesting and provide for natural lighting, and compatibility with the overall building design. Where visible from a public area, all rooftop or exposed structures (lift motor rooms, plant rooms etc.), must be suitably screened and integrated with the building.
2. Blank building façades facing the primary street frontage are not permitted.

EXTERNAL BUILDING MATERIALS AND COLOURS

3. Applicants are required to submit with all Development Applications a materials sample board detailing external colours and finishes.
4. External finishes should be constructed of durable, high-quality and low maintenance materials.
5. All external walls of buildings used for office/showroom purposes should be constructed of brick, glass, steel, concrete, textured block work, pre-cast exposed aggregate panels or other materials approved by Council.
6. External finishes should contain a combination of materials.
7. Any wall visible from the public domain must be finished with a suitable material to enhance the appearance of that façade.
8. Building materials should be selected such that reflection is minimised and will not adversely affect adjacent development, vehicular traffic and public domain areas.
9. The following should be considered in the choice of building materials in all developments:
 - energy efficiency;
 - use of renewable resources;
 - low maintenance;
 - recycled or recyclable;
 - non-polluting; and
 - minimal PVC content.
10. Materials that are likely to contribute to poor internal air quality and those containing Volatile Organic Compounds (VoCs) should be avoided.
11. Any application for development within the light industrial area must provide details of proposed external colours, materials, finishes and landscaping and any other supporting documentation in order to demonstrate how the development will minimise visual impact upon Rouse Hill House and views between Rouse Hill House and Box Hill House.

ENTRANCE TREATMENT

12. Entrances should be clearly visible, well sign posted, well lit and landscaped.

13. Entries to buildings should be clearly visible to pedestrians and motorists and be integrated into the form of the building.
14. Architectural features are to be provided at ground level giving an entrance element to the building and addressing the primary street frontage.
15. All entrance treatments, such as directory boards, must be located on private property, with appropriate positive covenants and restrictions on title to ensure the ongoing management of such treatments.
16. No form of advertising will be permitted on any entrance treatment facility.

6.3.5 Ancillary Buildings, Storage and Service Areas

OBJECTIVES

- a. To ensure that site facilities are functional and accessible and are easy to maintain.
- b. To ensure that site facilities are thoughtfully integrated into the development and are visual and physically unobtrusive.
- c. To minimise the impact of service access on pedestrians and industrial, commercial and retail frontage.
- d. To minimise the visual and acoustic impact of site servicing.

CONTROLS

1. Ancillary buildings and storage sheds are to be located behind the setback lines and be consistent with the design of the main building.
2. Details of any proposed ancillary buildings, open storage and services areas must be submitted with all Development Applications.
3. Where possible, storage areas should be located within the confines of the primary building. Appropriate screening must be provided otherwise.
4. Above ground open storage areas visible from the public domain are not permissible.
5. Above ground open storage areas should not compromise truck or vehicle manoeuvring and car parking areas.
6. Vehicular access to loading facilities is to be provided from secondary and tertiary streets where possible.
7. Rubbish and recycling areas must be provided in accordance with Site Waste Management and Minimisation provisions contained in The Hills Development Control Plan. These areas must:
 - be integrated with the development;
 - minimise the visibility of these facilities from the street; and
 - be located away from openable windows to habitable rooms.
8. Barrier free access is to be provided to all shared facilities.
9. Provide at least one shower and changing facility that is accessible to the building users.
10. The following information must be provided at Development Application stage for outdoor storage areas:
 - Size of outdoor storage area;

- Maximum storage height;
- Types of goods, materials and equipment being stored outdoors; and
- Details on landscaping and screening structures.

11. Sunken loading docks should be avoided.

12. A minimum 225mm clearance is required between finished floor level and finished ground level.

13. Above ground water tanks must not be located forward of the front façade of the primary buildings. They should not be visible from the public domain and must be suitably screened. Details (including elevations) of all water tanks must be submitted with the Development Application.

6.3.6 Fencing

- a. Low feature walls are encouraged at entry driveways. These walls should be used for retaining purposes, as garden beds or as landscaped features and should be integrated into the overall design of the development.
- b. Front and side boundary fences forward of the building line shall consist of an open wrought iron palisade style fence, finished in either dark green or black.
- c. Side fencing behind the building line may comprise chain wire mesh or similar open style fence, plastic coated in dark green or black.
- d. Pre-painted solid metal fencing and other solid fencing is not permissible.
- e. Fencing must be set back 1m from the property boundary.
- f. Fencing should be sited so it does not impede sightlines for drivers.
- g. Fencing along boundaries should not exceed a height greater than 3m, measured from finished ground level.
- h. Pedestrian fencing within the road reserve is to be RMS Type 1, without embellishment and black in colour.
- i. The use of timber fencing or bollards within public reserves or roads is not permitted.

6.3.7 Signage and Lighting

Refer to The Hills Development Control Plan for Signage and Lighting.

6.4 Landscape Design

Refer to The Hills Development Control Plan 2012 Part C Section 3 – Landscaping for Landscape Design.

6.4.1 Common Open Space

OBJECTIVES

- a. To ensure adequate open space areas are provided within development sites for the use and enjoyment of employees and visitors; and
- b. To ensure the size, location, configuration and embellishment of common open space areas encourages use by employees and visitors.

CONTROLS

1. Each development shall be provided with at least 1 common open space area for the use and enjoyment of employees and visitors to that development. The area shall be suitably landscaped and accessible from the main office component of the development.
2. Provision of common open space must comply with **Table 27**.
3. Open spaces must include soft landscaping and a deep soil area of at least 40% of its area.

Table 27 Open space provision

Employment Area	Open spaces area as % of total site area
R1 General Residential* and B7 Business Park zones	5%
IN2 Light Industrial zone and B6 Enterprise Corridor zones	1%

*Applies to developments comprising only commercial uses. Refer to Table 19 for controls relating to shop top housing in the R1 General Residential zone.

4. Small pockets of open space designed to enhance the appearance of the development will not be counted in the common open space allocation, neither will car parking areas, manoeuvring areas, or landscaped setback areas.
5. In locating common open space areas, consideration should be given to the outlook, natural features of the site and neighbouring buildings.
6. Common open space areas shall be embellished with appropriate shade, paving, tables, chairs and the like.
7. Common open space areas shall be relatively flat and not contain impediments which divide the area or create physical barriers which may impede use.
8. The area should be screened so it is not directly visible from the public domain but is provided with adequate sunlight access.
9. Appropriate shading is to be provided so that common open spaces are useable during summer.
10. Common open spaces are to incorporate the primary deep soil area where possible. The planting of courtyard spaces is to provide for the growth of mid- to large size trees.

6.5 Access and Parking

6.5.1 Pedestrian Access

OBJECTIVES

- a. To ensure pedestrian permeability throughout the Employment Areas, particularly in the Windsor Road Business Park.

CONTROLS

1. The following controls apply only to the Windsor Road Business Park:
 - The vertical clearance for pedestrian links is to be a minimum of 3.6 metres.
 - Pedestrian through site links are to be publicly accessible between the hours of 6am and 7pm.
 - Pedestrian through-site links are to be continuous, straight and with clear views from street to street.
2. Where pedestrian through-site links are adjacent to a courtyard or public space, the design of the pedestrian link is to be integrated with the design of the open space and access is provided between the two spaces.
3. Where pedestrian through-site links are provided between and through buildings, a high level of transparency is to be provided between the internal ground floor space of the building and the pedestrian link.
4. Active ground level uses are encouraged along pedestrian through-site links.
5. Disabled access must be provided along through-site links.
6. Through-site links that encourage a diverse built form and create interesting ground floor spaces are encouraged.

6.5.2 Vehicular Access

OBJECTIVES

- a. To ensure that vehicles can enter and exit premises in a safe and efficient manner in a forward direction.
- b. To minimise the impact of vehicle access points on the quality of the public domain and pedestrian safety.
- c. To provide off-street manoeuvring, loading and docking facilities that are adequate for the operational needs of the activity and use.

CONTROLS

1. A site specific Traffic and Car Parking Study must be prepared in accordance with **Tables 2 and 3** in **Section 1.8.2** of this DCP.
2. Vehicular driveway access is denied along Mt Carmel Road and Terry Road.

BUSINESS PARKS

3. Vehicular access should be designed to avoid conflicts with pedestrians.
4. Adequate space shall be provided within any development site for the loading and unloading of service vehicles. The standard of loading facilities required will depend upon the nature of the development and the uses to be carried out.

5. For certain developments Council may require the provision of parking for courier vehicles. Where possible loading facilities should be located at the rear of developments.
6. Vehicular movements associated with loading facilities and customer parking should be separated wherever possible and all pedestrian movements should be segregated from vehicular movements to avoid possible conflict and congestion.
7. Ingress to and egress from a site should be located where they will cause least interference with vehicular and pedestrian movement on public roads. Direct access will not be permitted off higher order roads. Road access to parking areas will not be permitted in close proximity to traffic signals, intersections or where sight distance is inadequate.
8. The potential for on-street queuing should be eliminated by the provision of sufficient standing areas on-site for vehicles entering the car parking and loading areas. Provision is to be made for all vehicles to enter and leave a site in a forward direction.

INDUSTRIAL AND ENTERPRISE CORRIDOR AREAS

9. Applicants are required to submit plans and details of proposed vehicular access and circulation for Council's approval with the Development Application. Details must specifically relate to vehicular movement, layout and turning circles.
10. Adequate vehicular entry to and exit from the development is to be provided and designed in order to provide safety for pedestrians and vehicles using the site and adjacent roadways. In some cases combined ingress and egress will be permitted.
11. Vehicular ingress and egress to the site must be in a forward direction at all times.
12. Driveway crossover accesses by heavy vehicles should be a minimum of 9m wide, when measured at the kerb alignment.
13. Turning circles will not be permitted to encroach upon any building.
14. Adequate space is to be provided within the site for the loading, unloading and fuelling (if applicable) of vehicles. These areas may need to be screened from the road.
15. All parking areas and access roadways must be provided with a drainage system comprising surface inlet pits. Details of pipe sizes (with calculations) and drainage layouts (including discharge points) must be submitted with the Development Application.

MANOEUVRING, LOADING AND DOCKING

16. Loading and docking facilities should be located and designed to minimise interference with internal traffic circulation.
17. Loading and docking facilities are to allow the forward entry to and exit from the site for all vehicles.

6.5.3 Car parking

OBJECTIVES

- a. To provide an appropriate level of on-site car and bicycle parking provision in Box Hill and Box Hill Industrial Precincts.

- b. To minimise the visual impact of on-site parking.
- c. To integrate parking facilities with the overall site planning and landscape.
- d. To encourage the use of other modes of transport including bicycles and public transport.

CONTROLS

1. The provision of car parking must comply with The Hills Development Control Plan 2012 Part C Section 1 – Parking.
2. Two male and two female showers are to be provided for cyclists in buildings above 1000m². One male and one female shower is to be provided for cyclists in buildings under 1000m².
3. Refer to The Hills Development Control Plan 2012 for general guidelines and principles for car parking, including design, materials, signs and monetary contributions.
4. Safe and secure 24 hour access to car parking areas is to be provided for building users.

AT-GRADE PARKING

5. At-grade parking areas are to be located so as to minimise visual impacts from the street, public domain and communal open space areas, using site planning and appropriate screen planting or structures.
6. Large parking areas are to be located generally behind front building lines.
7. In the Windsor Road Business Park and Annangrove Road Employment Area, parking areas must not be located within the front setback area.
8. In the Windsor Road Business Park and Annangrove Road Employment Area, parking will not be permitted forward of the front façade line of the building unless it can be demonstrated that parking will be appropriately located so as to not dominate the streetscape and will occupy a maximum of 40% of the front setback.
9. Provide safe and direct access from parking areas to building entry points.
10. Provide appropriate mature vegetation between parking bays to provide shade and enhance visual impact.

BASEMENT PARKING

11. Basement parking areas are to be located primarily under building footprints to maximise opportunities for deep soil areas. Refer to **Figure 47**.
12. Basement parking areas must not extend forward of the building line along a street. Refer to **Figure 48**.
13. Along active frontages, basement parking must be located fully below the level of the footpath. Refer to **Figure 48**.
14. The minimum level at the apex of the driveway into the basement should be above 17.9m to protect the entry of rain and surface water (1:100 year flood or overland flow).
15. Semi-basement parking must protrude no more than 1.2m above ground level for no more than 60% of the building frontage along a public street. Refer to **Figure 49**.
16. Ventilation grills or screening devices of car park openings are to be integrated into the overall façade and landscape design of the development.
17. An Emergency Flood Evacuation Warning System must be installed.

18. The lowest basement level must not be lower than the natural ground water level.
19. The basement level stormwater pumps must discharge via a stormwater treatment device to prevent the discharge of pollutants into streams.




Figure 47 Basement parking located primarily under building footprints




Figure 48 Basement parking behind front building line and located fully below footpath




Figure 49 Semi-basement parking

6.6 Safety and Surveillance

OBJECTIVES

- a. To ensure personal safety for workers and visitors to the development.
- b. To ensure design minimises the opportunity for crime and maximises opportunities for passive surveillance.

CONTROLS

1. A Crime Risk Assessment Report must be prepared for each development in accordance with **Table 2** and **Table 3** in **Section 1.8.2** of this DCP.
2. Buildings should be designed to overlook public domain areas and provide casual surveillance.
3. Building entrances should be orientated towards the street to ensure visibility between entrances, foyers, car parking areas and the street.
4. Appropriate lighting should be provided to all cycle and pedestrian paths, bus stops, car parks and buildings.
5. Development should provide clear sight lines and well-lit routes between buildings and the street, and along pedestrian and cycle networks within the public domain.
6. Consideration should be given to the use of landscape elements so as to not compromise the perceived level of safety.

7.0

Managing the Environment

7.0 MANAGING THE ENVIRONMENT

This section outlines the objectives and development controls relating to general Environmental Management of issues that apply across the entire Box Hill and Box Hill Industrial Precincts including conservation areas, integrated stormwater management, Aboriginal and European heritage, bushfire hazard management, tree and bushland protection, contamination, earthworks, soils and salinity, waste, riparian corridors and acoustics.

7.1 Integrated Stormwater Management

OBJECTIVES

- a. To ensure that appropriate stormwater management measures are implemented to maximise opportunities.
- b. To maintain and enhance the quality and integrity of urban waterways through both the construction and occupation phases of development.
- c. To encourage and create an urban form where risks to life and property, as a result of either minor or major flooding, are minimised.
- d. To maximise opportunities for a best practice Water Sensitive Urban Design approach at the individual lot, overall development and regional scales.
- e. To ensure urban development within the Precincts meets the required water quality objectives prior to discharge to the receiving waterways.
- f. To ensure that stormwater runoff is treated as a valuable resource and that its use for non-potable purposes is maximised.
- g. To minimise the impact of nuisance flooding to a level acceptable to the community.
- h. To reduce the impacts typically associated with urbanisation on receiving waterways, including a reduction in streamflow erosion potential.

CONTROLS

1. All development proposals are to provide for integrated stormwater management measures in accordance with the publication "Box Hill and Box Hill Industrial Precincts - Water Cycle Management Strategy Report" (BHBI WCMSR) (J. Wyndham Prince, February 2011) and updated by Water Cycle Management Post Exhibition Strategy Report (J. Wyndham Prince, May 2012) (BHBI PEWCMSR) and Water Cycle Management Post Re-Exhibition Strategy Report (J. Wyndham Prince, November 2012) (BHBI PREWCMSR). These documents embody the Floodplain Management Strategy referred to in the Box Hill & Box Hill Industrial Precinct Plan under the Growth Centres SEPP.
2. All habitable rooms shall have floor levels of a minimum of 500mm above the Post Climate Change 1 in 100 year Annual Recurrence Level (ARI) flood levels indicated in the Development Control Map in the Growth Centres SEPP.
3. All stormwater drainage designs are to comply with the most up to date revision of Council's "Design Guidelines Subdivisions/Developments".
4. Post-construction (occupation) phase stormwater management objectives are to be achieved by all development through implementation of the Water Sensitive Urban Design (WSUD) strategy outlined in the BHBI WCMSR, BHBI PEWCMSR, BHBI PREWCMSR. Alternative innovative application of WSUD is permitted as long as it meets the performance objectives outlined in **Table 28** below.

5. WSUD is to be adopted throughout all development to provide sustainable and integrated management of land and water resources, incorporating best practice stormwater management, water conservation and environmental protection measures.
6. The WSUD strategy prepared for all development is to take into account water quality and stream erosivity objectives, together with attenuating flow rates and runoff volumes to acceptable levels following urban development.
7. Design methodologies for WSUD infrastructure elements are to generally be consistent with the following publications:
 - Australian Runoff Quality (Engineers Australia 2005)
 - Water Sensitive Urban Design Technical Guidelines for Western Sydney (NSW Government Stormwater Trust and UPRCT, May 2004)
8. The overall water quality and stream erosivity performance objectives applicable to the Box Hill and Box Hill Industrial Precincts have been provided by the NSW OEH. Those performance objectives are set out in **Table 28**.

Table 28 Water quality and stream erosivity performance objectives for the North West Growth Centres

	WATER QUALITY % reduction in pollutant loads ¹				ENVIRONMENTAL FLOWS Stream Erosion Control Ratio
	Gross Pollutants (>5mm)	Total Suspended Solids	Total phosphorus	Total Nitrogen	Post-development duration of above 'stream forming flow': Natural duration of above 'stream forming flow' ¹
Stormwater management objective	90	85	65	45	3.5 – 5.0:1 ²
'Ideal' stormwater outcome	100	95	95	85	1:1

Source: DECCW, 2010

1. For the purposes of these objectives, the 'stream forming flow' is defined as 50% of the 50% AEP flow rate estimated for the catchment under natural conditions.
2. This ratio should be minimised to limit stream erosion to the minimum practicable. Development proposals should be designed to achieve a value as close to one as practicable, and values within the nominated range should not be exceeded. A specific target cannot be defined at this time.

9. Water quality modelling undertaken to support development proposals within the Precincts shall utilise MUSIC Version 5 (or later) and adopt the modelling parameters outlined in Attachment B of the BHBI WCMSR.
10. All buildings must install rainwater tanks to meet a portion of supply such as outdoor use and toilets. All residential dwellings are required to provide a (minimum) 3,000 litre (3 KL) rainwater tank as part of the WSUD strategy, and such tank is to be connected for use in toilet flushing and external uses. Larger tanks than the minimum requirement are permitted.
11. Each rainwater tank is to be provided with potable water trickle top-up with a back flow prevention device, complying with Sydney Water requirements.

12. In accordance with the recommendations made in the publication "Guidance on the Use of Rainwater Tanks" (enHealth, Commonwealth Government 2004), diversion of the "first flush" of up to 180 litres is to be incorporated into the design of the rainwater tank and associated plumbing based on a minimum first flush of 1L/m² of roof area.
13. Fencing within the riparian corridors has the potential to collect debris and inhibit the free passage of flood waters. Fences crossing the riparian corridor within the Ridge Area and the E2 Environmental Conservation must be designed so as not to impede the free passage of flood water either through the materials used in their construction or by providing sufficient open area within their form that the waterway area within corridor is not significantly reduced.
14. Industrial/commercial developments within the Precincts are required to manage the pollutant loads from each separate allotment to ensure compliance with the performance objective listed in **Table 28** above prior to discharge to any adjoining drainage system.
15. The design of the road systems within the areas of the Precincts that are affected by a Regional Probable Maximum Flood (i.e. Below R.L 26.4m AHD), should provide a "continuous rising grade" to ensure the safe evacuation of affected occupants within these areas. All designated evacuation routes as identified in **Figure 50** are to be designed to ensure that they remain functional and safe during a 500 year ARI local storm event.
16. The filling of flood affected land as shown in **Figure 51** is required to facilitate the urban development of the Precinct and shall to be to a minimum of 100 year ARI flood levels in the adjacent creeks. Habitable floor levels are to be in accordance with control 2 above.
17. For these flood affected areas shown in **Figure 51**, a site specific investigation may be required to demonstrate that the localised site filling does not have adverse impacts on adjoining land(s) or result in a localised flood levels increase within the adjoining creeklines. Potential impacts are to be assessed against The Hills Shire Council guidelines and industry standards. There may be a need to advance the riparian corridor upgrades works as part of any development that results in offsite impacts (localised changes to flood depth, flow velocity or flood hazard) or if a development adjoins a riparian corridor as defined in the ILP.
18. Gross pollutant traps to be provided prior to discharge to any of the Precinct's water quality devices or riparian corridors.
19. Pipe outlets to bio-retention devices should provide for a minimum 50mm drop to the devices bed levels.
20. If at the time of the development, the Water Cycle Management strategy that formed part of the BHBI WCMSR, BHBI PEWCMSR or BHBI PREWCMSR, is not fully implemented or development is proposed that is not in sequence with the anticipated development scenario as presented in Figure 9.1 of BHBI PEWCMSR, then a site specific assessment will be needed. The assessment will need to demonstrate that the development does not adversely affect adjoining land or the downstream receiving waters from a flood depth, flow velocity or flood hazard perspective. Flows, flood depth and flood hazards are to be reported at the discharge point from the development, Precinct discharge point (Confluence of Boundary Road and Killarney Chain of Ponds or Second Ponds creek) and any at major confluence points within the catchment relevant to the development. This assessment is to ensure impacts are in accordance with The Hills Shire Council guideline(s) or industry standards. The mitigation of any potential adverse impacts may be achieved by interim measures until upstream controls are implemented.

21. For those areas shown in **Figure 52** that do not drain directly to Precinct based water quality devices, the existing / interim devices that are present within the catchment at the time of the development, are to be assessed to ensure stormwater runoff from that development meets the water quality targets list in **Table 28**. An assessment of water quality targets is required at the Precinct's discharge point (i.e. at Boundary Road or discharge point to Second Pond Creek). The mitigation of any potential adverse water quality impacts may be achieved by interim measures until upstream controls are implemented. Any interim assessment need to demonstrate compliance with this requirement.
22. Flow management may be implemented as per Section 6.10 BHBI WCMSR or Section 9.0 of BHBI PEWCMSR. Council can provide the applicant with the Precinct wide base water quality and water quantity models to facilitate the assessment process.
23. During the construction phase of development, the relevant Stormwater Management Objectives for New Development as set out in the most up to date revision of "Managing Urban Stormwater: Soils and Construction" (NSW Department of Housing) must be complied with in full.
24. Erosion and sediment control measures are to be implemented and regularly maintained on site, while sediment trapping measures are to be located at all points where stormwater runoff can enter inlets to stormwater systems, or where runoff may leave the construction site.




Figure 50 Evacuation plan for regional PMF event



Figure 51 Flood Affected areas with Potential to be Filled




Figure 52 Catchments that bypass stormwater management devices

7.2 Aboriginal Heritage

OBJECTIVES

- a. To protect and manage the known and potential Aboriginal heritage values of the Box Hill and Box Hill Industrial Precincts.

CONTROLS

1. Known Aboriginal archaeological sites within the Precincts are shown in yellow in **Figure 53**. An Aboriginal Heritage Impact Permit (AHIP) issued under Part 6 of the *National Parks and Wildlife Act 1974* (NPW Act) is required for any works which directly affect these sites.
2. Previously recorded areas of Potential Archaeological Deposit (PAD) within the Precincts are shown as black-hatched in **Figure 53**.
3. Development within these areas should not proceed without archaeological test excavation. Test excavation is to be carried out in accordance with the relevant code of practice stipulated in the *National Parks and Wildlife Regulation 2009* (NPW Regulation). If Aboriginal objects are encountered during test excavation, an AHIP issued under Part 6 of the NPW Act will be required. Consultation with Aboriginal stakeholders is required under DECCW policy when an application for an AHIP is considered.
4. Areas of high archaeological sensitivity as shown in **Figure 53** warrant archaeological test excavation. Test excavation is to be carried out in accordance with the relevant code of practice stipulated in the NPW Regulation. If Aboriginal objects are encountered during test excavation, an AHIP issued under Part 6 of the NPW Act will be required. Consultation with Aboriginal stakeholders is required under OEH policy when an application for an AHIP is considered.
5. Areas of moderate archaeological sensitivity as shown in **Figure 53** warrant an Aboriginal archaeological due diligence assessment. This assessment is to be conducted in accordance with the relevant code of practice stipulated in the NPW Regulation.
6. Areas of low archaeological sensitivity as shown in **Figure 53** do not contain any known Aboriginal heritage constraints. However, Aboriginal objects may still occur in these areas. If any Aboriginal objects are encountered during development, an AHIP issued under Part 6 of the NPW Act will be required. Excluded from this control are those areas of low sensitivity that fall within the boundaries of previously recorded areas of PAD.




Figure 53 Sensitive Aboriginal archaeological areas

7.3 European Heritage

OBJECTIVES

- a. To conserve and protect identified items of heritage significance and a building, relic or structure that is considered by Council to be of heritage significance.
- b. To protect the archaeological potential of the area.
- c. To ensure the archaeological potential is adequately managed.

CONTROLS

1. Development on land within 50 metres of a heritage site is not to detract from the identified significance of the place, its setting, nor obstruct important views to and from the site.
2. New structures proposed on land adjoining a heritage building should be of similar scale and proportions to the heritage building.
3. Where development is proposed within 50 metres of a heritage site, the following matters must be taken into consideration:
 - the character, siting, bulk, height and external appearance of the development;
 - the visual relationship between the proposed development and the heritage site;
 - the potential for overshadowing of the heritage site;
 - the colours and textures of materials proposed to be used in the development;
 - the landscaping and fencing of the proposed development;
 - the location of car parking spaces and access ways into the development;
 - the impact of any proposed advertising signs or structures;
 - the maintenance of the existing streetscape, where the particular streetscape has particular significance to the heritage site;
 - the impact the proposed use would have on the amenity of the heritage site; and
 - the effect the construction phase will have on a heritage building.
4. Refer to **Section 8.0** for Special Area Controls for Box Hill House, Box Hill Inn, Marklye and The Hunting Lodge.

BYPASSED SECTION OF OLD PITT TOWN ROAD

5. The location of the Bypassed Section of Old Pitt Town Road is shown in **Figure 54**.
6. No road is to be created off the Bypassed Section of Old Pitt Town Road.
7. Prior to any development that affects the Bypassed Section of Old Pitt Town Road, a Heritage Impact Statement is to be prepared, including impacts to archaeological potential.

BOX HILL / NELSON COMMUNITY HALL

8. The location of the Box Hill / Nelson Community Hall is shown in **Figure 54**.

IDENTIFIED ARCHAEOLOGICAL SITES

9. The location of identified potential archaeological sites is shown in **Figure 54**.

10. Prior to granting consent for development that will be carried out on archaeological sites that have non-Aboriginal heritage significance the consent authority must:

- consider a Heritage Impact Statement explaining how the proposed development will affect the conservation of the site and any relic known or reasonable likely to be located at the site, and
- Be satisfied that any necessary excavation permit required by the Heritage Act 1977 has been granted.




Figure 54 Location of heritage items

7.4 Bush Fire Hazard Management

OBJECTIVES

- a. To prevent loss of life and property due to bushfires, by discouraging the establishment of incompatible uses in bushfire-prone areas.
- b. To ensure adequate fuel management of asset protection zones in accordance with the Rural Fire Service (RFS) fuel management standards.
- c. To define construction standards that applies to lots within 100m of bushfire prone vegetation.

CONTROLS

1. Subject to detailed design at Development Application stage, the indicative location and widths of Asset Protection Zones (APZs) are to be provided generally in accordance with the following:
 - are to be located wholly within the Precincts;
 - may incorporate roads and flood prone land;
 - are to be located wholly outside of vegetation shown in the Core Riparian Zone of the riparian corridors and fuel management not impacting on vegetation within these areas in any way;
 - may be used for open space and recreation subject to appropriate fuel management;
 - are to be maintained in accordance with Planning for Bushfire Protection 2006 (NSW Rural Fire Service);
 - may incorporate private residential land, but only within the building setback;
 - are not to burden public land; and
 - are to be generally bounded by a perimeter fire trail/road that is linked to the public road system at regular intervals in accordance with Planning for Bushfire Protection 2006.
2. Reticulated water is to meet the standards contained within *Planning for Bushfire Protection 2006*. Water supply is to be via a ring main system, engineered to the requirements of Australian Standard AS 2419.1 – Fire Hydrant Installations.
3. Vegetation management within public parks and community title areas is to be subject to completion of a Fuel Management Plan that is to be integrated within the Park Plan of Management.
4. Landscaping and property maintenance for lots within 100 m of bushland are to be in accordance with measures described in Appendix 5 of *Planning for Bushfire Protection 2006*.
5. Buildings adjacent to APZs (refer **Figure 55**) are to be constructed in accordance with the requirements of Appendix 3 of *Planning for Bushfire Protection 2006* and Australian Standard 3959-2009 - Construction of Buildings in Bushfire Prone Areas.
6. Where an allotment fronts and partially incorporates an APZ (refer **Figure 55**) it shall have an appropriate depth to accommodate a dwelling with private open space and the minimum required APZ. The APZ will be identified through a Section 88b instrument.

7. Temporary APZs, identified through a Section 88b instrument, will be required where development is proposed on allotments next to undeveloped land. Once the adjacent stage of development is undertaken, the temporary APZ will no longer be required and shall cease.
8. Roads are to be designed in accordance with acceptable solutions as defined within *Planning for Bushfire Protection 2006*.




Figure 55 Indicative APZ requirements

7.5 Tree and Bushland Protection

The retention of trees and bushland in new development areas provides a range of benefits including a contribution to the character of the neighbourhood, spatial definition and environmental values.

OBJECTIVES

- a. To ensure bushland is substantially retained and protected and that development enhances and complements this bushland.
- b. To ensure through appropriate protection mechanisms that development and subdivision adjacent to bushland do not detrimentally affect the continued survival of that bushland.
- c. Provide a basis for increasing lot areas and altering lot shapes to enable the retention of trees and bushland.

CONTROLS

1. Where it is likely that mature trees will be removed either through the creation of a residential lot or through its subsequent development Council will require:
 - The lot area to be increased beyond the minimum lot size so as to ensure mature tree(s) are retained; or
 - The lot boundaries to be rearranged to ensure mature tree(s) are retained.
2. Prior to submission of a development application for the purposes of subdivision, the applicant is to prepare a Tree Management Plan utilising the services of a qualified arborist. This report will ensure an understanding of the condition of existing trees, which will assist in analysing the site opportunities, and is to be submitted at subdivision application stage. The Tree Management Plan must incorporate a survey of all trees as defined under Council's Tree Management Plan and all bushland, as defined by SEPP 19 - Bushland in Urban Areas.
3. Protective fencing is to be provided around trees and bushland to be retained to prevent damage. Fences are to be constructed at the drip-line of existing vegetation as a minimum to prevent damage within the drip-line/protection zone by limiting access into it.

7.6 Contamination Management

OBJECTIVES

- a. To minimise the risks to human health and the environment from the development of potentially contaminated land.
- b. To ensure that potential site contamination issues are adequately addressed at the subdivision stages.

CONTROLS

1. For all proposed development a Stage 1 – Preliminary Site Contamination Investigation is required unless it can be demonstrated that such an investigation is not required, such as in bushland areas where it can be established that there has been no previous development. A Stage 2 assessment will be required where the Stage 1 report identifies that the site is potentially contaminated. A Remediation Action Plan (RAP) will be required for areas identified as contaminated land in the Stage 2 Investigation.
2. An assessment for asbestos should be undertaken on all properties prior to residential development. An Asbestos Management Plan may be required for the site to guide demolition works and also during ground excavations for construction.
3. All investigation, reporting and identified remediation works must be in accordance with the protocols of the NSW EPA's (now OEH) Guidelines for Consultants Reporting on Contaminated Sites and SEPP 55 – Contaminated Land.
4. Prior to granting development consent, the Council must be satisfied that the site is suitable, or can be made suitable, for the proposed use. As detailed under SEPP 55, Category 1 remediation works identified in any Remediation Action Plan (RAP) requires Council consent prior to the works commencing; and Category 2 remediation works require Council to be notified.
5. Council may require a Site Audit Statement (SAS) (issued by an OEH Accredited Site Auditor) where remediation works have been undertaken to confirm that a site is suitable for the proposed use.
6. Council may require a Hazardous Material Survey to be prepared and included with the development application where there are existing buildings, sheds and structures on site.

7.7 Geotechnical

OBJECTIVES

- a. To ensure proposed development does not result in movement or slip.
- b. To ensure soil movement or land slip does not adversely affect proposed development.
- c. To ensure that buildings are designed to respond to limitations in relation to land capability.

CONTROLS

1. A geotechnical assessment must be prepared and submitted with a Development Application as per **Tables 2 and 3** in **Section 1.8.2**.
2. The localised steep banks of the water courses should undergo individual assessments where they are to be upgraded.
3. Where heavy structures such as bridges and culverts are required in the flood plain of the Killarney Chain of Ponds specific geotechnical testing will be required once the construction proposal is known, as any proposed works in this area will potentially encounter water table issues and soft soils. A structural engineer should take into consideration the Land Capability, Salinity and Contamination Project, Box Hill Precincts prepared by WSP Environment and Energy dated February 2011.
4. Where drainage works are proposed to existing natural drainage lines, the following issues must be considered:
 - any realignment of the existing natural drainage will require back filling and remediation work, which must include removing all soft strata from the drainage line;
 - remedial works should ensure that in future wet periods, the backfill does not become any wetter than the adjacent natural ground;
 - the backfill should not be compacted to an extent that it will act as a barrier to sub-surface and groundwater flow, resulting in waterlogging and salinity impacts; and
 - alluvial clayey silt should not be used as a structural fill for recompaction.
5. When filling in areas of the flood plain the following issues must be considered and development specific geotechnical testing may be required:
 - Any proposed filling should not inhibit creek flow in wet periods;
 - Topsoil must be excluded from the area;
 - The influence of the water table and its variations from wet to dry seasons on the overlying fill must be considered; and
 - Some strata at depth in the flood plain / low lying areas is only soft to firm, which may not have sufficient strength to support the proposed new loads applied from retaining walls, fill loads and structural loads.

6. Development applications on land where existing dams are present will require the submission of a geotechnical assessment to establish the suitability of land for the proposed development, as well as back filling of the dams and remediation work.

7.8 Subdivision Earthworks

OBJECTIVES

- a. To minimise topsoil and vegetation removal and “land-shaping” on land where residential subdivisions are being constructed.

CONTROLS

1. Earthworks shall be minimised to locations where the construction of roads require earthworks to be undertaken.
2. Such earthworks may extend into the proposed allotments for the purpose of providing suitable vehicle access to the identified building platform referred to in **Section 4**.
3. Vegetation and topsoil are not to be removed or disturbed in areas outside of the above areas of proposed construction.
4. All proposed public open space areas are to be fenced and are not to be disturbed or used for any purpose during the construction of a subdivision.
5. Subdivision applications must provide a plan showing the existing pre-development and proposed finished ground levels to enable an assessment of the extent of earthworks proposed and assessment of the relationship between the finished road levels and proposed building platform levels.

7.9 Cut and Fill

OBJECTIVES

- a. To provide a landform that is capable of supporting a range of residential, business and industrial uses.
- b. To minimise the impact of earthworks on the stormwater regime, salinity and groundwater.
- c. To ensure that the extent of cut and fill required for large scale development does not detract from the appearance and design.
- d. To ensure that development is capable of visual integration with the surrounding environment.
- e. To ensure that any imported fill material to a site is clean and complies with the contamination and salinity provisions of this section.
- f. To ensure land is appropriately stabilised and retained.
- g. To ensure that the extent of cut and fill does not encroach within, or adversely affect the efficiency, integrity and stability of any open space area.
- h. To minimise the need to cut and fill at the subdivision phase of development.
- i. To ensure accessibility where necessary.

CONTROLS

1. Fill will only be permitted in the designated areas shown in **Figure 51** and **Section 7** of this DCP for the floodplain.
2. A Fill Plan must be prepared in accordance with **Tables 2 and 3** in **Section 1.8.2** of this DCP.
3. A cut and fill works shall be in accordance with Council's Design Guidelines Subdivisions/ Developments and Works Specification Subdivisions/ Developments.
4. All landfilled areas must comprise clean material free from contamination. Imported material shall be certified "Virgin Excavated Natural Material (VENM)".
5. Landfilled areas must be suitably compacted and stabilised with density tests to verify that compaction was achieved in accordance with Council requirements.
6. Land filled areas must be revegetated where appropriate.
7. Embankment batters shall have a maximum slope of 1:6.
8. Embankment batters and retaining walls are to be landscaped to reduce erosion and provide a suitable screen. They should be vegetated preferably with native ground covers and small native trees with mature height of up to 10m.

7.10 Salinity Management

OBJECTIVES

- a. To manage and mitigate the impacts of development on salinity and vice versa;
- b. To maintain a natural water balance;
- c. To maintain good drainage;
- d. Avoid disturbance or exposure of sensitive soils;
- e. Retain or restore native vegetation on areas with high groundwater recharge potential or where protecting salt affected land in potential discharge zones; and
- f. Implement building controls and engineering response where appropriate.

CONTROLS

1. Applications are required to demonstrate an understanding of the site salinity in order to prepare appropriate strategies for developing the site.
2. Erosion is to be mitigated and managed during the construction stage of development as detailed in Sections 4 and 5 of the Landcom (2006) *Managing Urban Stormwater, Soils and Construction – Volume 1, 4th Edition* document.
3. Given the saline nature of the groundwater it is considered that extraction for irrigation purposes should not occur within the Precincts.
4. Stormwater and drainage impacts on salinity are to be managed as follows:
 - Implementation of measures to avoid the infiltration of storm water;
 - Permanent surface water infrastructure such as water features, ponds and dams should be lined and regularly maintained to limit infiltration;
 - Underground water carrying pipes are to be properly installed to eliminate leaks. Existing pipes and systems should be checked for damage or leaks. Rubber sealed pipes or superior equivalent should be used for water carrying pipes to minimise the risk of leakage;
 - Avoid over irrigation with the installation of an efficient irrigation system, apply 'waterwise' principles with procedures designed to avoid excessive infiltration through the soil;
 - Consideration given to salinity and infiltration when designing and installing swimming pools;
 - Minimise the disturbance to natural drainage patterns;
 - Infrastructure such as slabs, foundations and retaining walls should be designed to allow good drainage and minimise water logging. The design and layout of retaining walls, driveways and underground services should have minimal cut, minimise impediment of natural groundwater flow and provide good drainage. Design and construction is to be carried out in accordance with Australian Standards and Building Codes, to ensure current best practices are occurring; and
 - Guttering and down pipes are to be properly connected and maintained.

5. The impact of vegetation and landscaping on salinity is to be managed as follows:
- Areas of established vegetation should be maintained as much as practical. Deep-rooting, salt tolerant plants, and water efficient turf should be planted to use the groundwater source and reduce infiltration;
 - Landscaping plans apply to 'waterwise' gardening principles. However, procedures designed to encourage excessive infiltration through the soil should be avoided. In certain landscaping situations, infiltration measures to be incorporated may include a subsurface drain and liner when rapid infiltration to groundwater is likely to occur;
 - Irrigation systems should be properly installed to avoid leakage and 'smart' sprinkler systems should be considered; and
 - Damp proof courses should be properly installed during the construction of infrastructure, and maintained throughout construction and landscaping.
6. During construction impacts to salinity are to be managed as follows:
- Consideration should be made to use salt resistant bricks and construction materials as a preventative measure for infrastructure degradation. Susceptible construction material, such as seconds and porous material should be avoided;
 - Areas of cut and fill on sites should be restricted to building envelope;
 - Existing areas of water logging and poor drainage should be avoided or remediate, with consideration to shrink swell hazard;
 - Erosion / disturbance are to be minimised and re-vegetated with appropriate species. Construction techniques should minimise site disturbance and the exposure of sensitive soil material;
 - Damp proof membrane should be installed under slabs;
 - Reduce the exposure of materials to corrosive soils; and
 - Implementation of mitigation measures to address potential soil erosion during construction due to sodic and exposed soils.

MANDATORY BUILDING REQUIREMENTS:

7. The following measures must be used for house slabs and footings: For slab on ground construction, a layer of sand at least 50mm deep under the slab must be provided;
8. A damp proof membrane (rather than a vapour proof membrane) must be laid under the slab (NSW BCA 3.2.2.6);
9. The damp proof membrane must be extended to the outside face of the external edge beam up to the finished ground level. *(as per clause 3.2.2.6 and figure 3.2.2.3 of the BCA)*;
10. Class 32 Mpa (N32) concrete must be used OR a sulphate resisting Type SR cement with a water cement ratio of 0.5 must be used;
11. Slabs must be vibrated and cured for a minimum of three days;

12. The minimum cover to reinforcement must be 50mm from unprotected ground;
13. The minimum cover to reinforcement must be 30mm from a membrane in contact with the ground;
14. The minimum cover to reinforcement must be 50mm for strip footings and beams irrespective of whether a damp proof membrane is used; and
15. Admixtures for waterproofing and/or corrosion prevention may be used.
16. The following measures must be used for brickwork:
 - The damp proof course must consist of polyethylene or polyethylene coated metal and be correctly placed, (SA BCA 3.3.4.4);
 - Exposure class masonry units must be used below the damp proof course including for strip footings, (Clause 3.3.1.5 (b) and Table 3.3.1.1 of the BCA);
 - Appropriate mortar and mixing ratio must be used with exposure class masonry units, (clause 3.3.1.6 and Table 3.3.1.2 of the BCA); and
 - Admixtures for waterproofing and/or corrosion prevention may be used.

The following measures must be used for all buildings:

- Once installed the damp proof course or the vapour barrier must not be breached by any later works or additions such as: steps, verandahs, walls, rendering, bagging, pointing, paving or landscaping;
- Appropriate sub-soil drainage must be installed for all slabs, footings, retaining walls and driveways; and
- The dwelling must be designed to suit the sites existing topography and any cut and fill required must not exceed 500mm (unless approved in the Development Application).

RECOMMENDED FOR ALL LANDSCAPED AREAS:

- Landscaping and garden designs should not be placed against walls and minimise the use of water on the site.
- Low water requiring plants and water-wise garden designs are preferred.
- The use of grey water for the watering of lawns and gardens should be monitored to avoid water logging, as grey water can be high in salts. The use of low salt detergents is recommended.

7.11 Waste Management

OBJECTIVES

- a. To ensure sufficient storage and collection of wastes and recyclables during demolition and construction stages of development.
- b. To minimise waste generation and disposal to landfill via use of the waste hierarchy and careful source separation, reuse and recycling.
- c. To ensure the provision of adequate and appropriate storage areas for waste and recyclables.

CONTROLS

1. A Waste Management Plan is to be submitted with all development, with the exception of single dwelling housing. The Plan is to address:
 - best practise recycling and reuse of construction and demolition materials;
 - how recycled material, garbage and other waste generated by clearing, excavation and construction are to be stored and controlled;
 - the type and volume of waste expected to be generated during construction; and
 - handling methods and location of waste storage areas, including that such handling and storage has no negative impact on the streetscape, building presentation or amenity of occupants and pedestrians.
2. Provide adequate space within the main building for separation of waste material for recycling. Locate such facilities away from windows to habitable rooms.
3. Garbage storage areas must be located so as to not cause any negative impacts, in terms of visual appearance, noise or smell, to adjoining properties, or to the street.
4. Separate garbage from recycling chutes so that waste is divided into separate waste streams in order to recycle materials.
5. Where present, rear lanes are to be used for garbage collection.
6. Utilise ventilation stacks wherever possible to vent shops and basements.

7.12 Riparian Corridors and Environmental Conservation Areas

OBJECTIVES

- a. To protect, restore and enhance the environmental values and functions of water courses and riparian corridors.
- b. To ensure that the development has a neutral or beneficial impact on the quality and quantity of water and water courses.
- c. To allow for some limited use of riparian corridor buffers for low impact recreation activities such as walking and cycling.
- d. To maintain a stable naturally functioning watercourse that supports a viable naturally occurring local aquatic community.
- e. To provide, restore, rehabilitate and maintain the riparian corridor with the local provenance vegetation community.
- f. To provide a continuous riparian corridor that links to established stands of remnant vegetation and provides extensive habitat and connectivity for naturally occurring terrestrial fauna.
- g. To ensure vegetation in the CRZ is at a density that would occur naturally for the riparian ecotone.
- h. To minimise the number of road crossings to maintain riparian connectivity.
- i. To maintain riparian connectivity through the use of piered crossings on Category 1 watercourses (other than for utilities).

CONTROLS

1. Riparian corridors are to be provided in accordance with **Figure 56** and designed in accordance with the specific objectives and controls set out in **Table 29**.
2. Maintain a stable naturally functioning watercourse that supports a viable naturally occurring local aquatic community.
3. A Vegetation Management Plan (as described in **Table 3**) is to be submitted to Council as part of the residential subdivision DA for any land within a lot that has or partly has an E2 zoning. Where wetlands are proposed, a wetland management plan outlining, initial condition, maps, design specifications, monitoring, management and maintenance requirements, techniques, timelines, pest management, ownership, ongoing management, annual maintenance costs and initial development costs shall be submitted with any development application.
4. Infrastructure services, stormwater infrastructure, water quality treatment ponds, flood compatible activities (i.e. playing fields), pedestrian and cycleways, and asset protection zones are to be located outside of the CRZ. These uses are permitted within the vegetated buffer if the impact on riparian functions is minimal and its integrity maintained. Water quality treatment devices are permissible within the CRZ providing that they are vegetated dry basins, are above top of bank and do not increase flood levels.

5. Minimise the number of watercourse crossings to maintain riparian connectivity. It is recommended that both during construction and post construction the following measures be undertaken to reduce impacts:
 - Minimise the disturbance footprint during construction (offsets may be required to any impacts on ENV outside of the road corridor);
 - Fencing to minimise the area disturbed during construction and operation;
 - Weed control and management;
 - Erosion and sediment control; and
 - Revegetation and rehabilitation of disturbed areas using local provenance species.
6. Locate access ways to and within a riparian protection area so that they do not compromise the environmental objectives for that watercourse or stream bed and/or be stability and are also consistent with NSW State Government Guidelines (e.g. protection of fish habitat, water quality, water stability).
7. All CRZs are to be rehabilitated and revegetated with appropriate native vegetation having regard to its drainage function and vegetation management for bushfire protection. Vegetation within the CRZ is to be at a density that would occur naturally for the riparian ecotone.
8. The riparian corridor is to remain, or become vegetated, with native vegetation (trees, shrubs and groundcover species) according to the appropriate local provenance vegetation community.
9. Environmental protection works, drainage (outlet pipes only) and crossings (e.g. roads, service utilities and paths) are permitted with consent within the riparian protection area.
10. The APZ, or any part of the APZ, must not be located within the Core Riparian Zone.
11. Stormwater runoff must be treated before being discharged into riparian zones or watercourses.
12. Structures for water quality and flood detention purposes must be located outside the riparian corridor unless otherwise approved by ORH. It must also be demonstrated that the impact on riparian functions is minimal and its integrity maintained. Unless it can be demonstrated that they can be fully vegetated, and the intent of the riparian corridor is not compromised, all water quality structures must be located outside the riparian corridors.
13. Measures to contain and attenuate low flow events (less than 5 year) are permitted providing they are fully vegetated and it can be demonstrated that the required environmental outcomes can be achieved.
14. Development consisting of crossings of riparian protection areas or watercourses, includes but is not limited to roads, paths, cycleways and the laying of service utilities. Each of these activities must be minimised and designed and constructed in accordance with OEH guidelines to minimise ecological impacts. For all lands located within the riparian protection areas a VMP must be prepared. The plan must include a monitoring and maintenance strategy which must be prepared collaboratively by key stakeholders. A report on the monitoring and maintenance of the works must be submitted to council at six monthly intervals for the first year and then yearly intervals for the following year or for a period of time that is to the satisfaction of all parties.
15. No battering is permitted within the riparian corridor unless within approved online detention areas.

16. All works proposed in, on or under “waterfront land” as defined under the *Water Management Act 2000* must comply with the requirements of the Act and may require a “controlled activity” approval from the NSW Office of Water.
17. Waterway crossings are required to have a minimum opening width equating to 50% of the width of the relevant riparian corridor.

Development within the E2 Environmental Conservation Zone

18. Permitted uses under the Growth Centres SEPP, except essential infrastructure such as road crossings and Sydney Water works should only be located in areas outside the Riparian Protection Area as illustrated in **Figure 56** and **Figure 57**.
19. Perimeter roads as illustrated in the Indicative Layout Plan are the preferred development option along the edge of the Riparian Corridors. Refer to **Figure 58**.


Table 29 Riparian corridors objectives and controls

Specific objectives	Specific controls
Category 1	
<ul style="list-style-type: none"> (1) To provide a continuous, riparian corridor for the movement of flora and fauna species through and beyond the catchment. (2) To provide extensive habitat and connectivity for naturally occurring terrestrial fauna. (3) To maintain the viability of native riparian vegetation. 	<ul style="list-style-type: none"> (1) For the Killarney Chain of Ponds and First Ponds Creek is a riparian corridor of at least 100m width (50m each side of watercourse), including Core Riparian Zone (CRZ) of an average 80m measured from top of bank (TOB), 20m Vegetated Buffer (VB) and an additional width that equals the width of the channel between the top of banks. (2) Links to established stands of remnant vegetation where possible. (3) Restore and rehabilitate the CRZ with local provenance native vegetation. (4) Ensure vegetation in the CRZ and vegetated buffer is at a density that would occur naturally. (5) Minimise the number of road crossings. (6) Maintain riparian connectivity by using pierced crossings (other than for utilities). (7) Ensure lateral connectivity for in-stream function.
Category 2	
<ul style="list-style-type: none"> (1) To maintain and restore the natural functions of a stream and its aquatic and terrestrial qualities. (2) To maintain the viability of native riparian vegetation. (3) To provide extensive habitat and connectivity for naturally occurring terrestrial fauna. 	<ul style="list-style-type: none"> (1) For Category 2 watercourses is a riparian corridor of at least 60m width (30m each side of watercourse), including Core Riparian Zone (CRZ) of an average 20m measured from top of bank (TOB) and an additional width that equals the width of the channel between the top of banks. For the upstream section of Killarney Chain of Ponds this it to be increased to a 40m CRZ and 10m VB each side of the channel, measured from the top of bank. (2) Links to established stands of remnant vegetation where applicable. (3) Restore and rehabilitate the CRZ with local provenance native vegetation. (4) Ensure vegetation in the CRZ and vegetated buffer is at a density that would occur naturally. (5) Minimise the number of road crossings and ensure riparian connectivity is maintained. (6) Provide lateral connectivity for in-stream function.
Category 3	

Specific objectives	Specific controls
<p>(1) To retain, maintain and restore where possible the natural functions of a stream, including bed and bank stability to protect local water quality.</p> <p>(2) To provide extensive habitat and connectivity for naturally occurring terrestrial fauna.</p>	<p>(1) For category 3 watercourses is a riparian corridor of at least 20m width, including 10m CRZ each side measured from the TOB and an additional width that equals the width of the channel between the top of banks.</p> <p>(2) Links to established stands of remnant vegetation where applicable.</p> <p>(3) Emulate or preserve, wherever possible, a naturally functioning stream.</p> <p>(4) Engineered drainage solutions are to be used as a last resort within CRZs with the appropriate WSUD approaches to be used within sensitive areas.</p>



Figure 56 Riparian corridors






Figure 58 Perimeter roads and subdivision pattern along Riparian Corridors

7.13 Noise and Vibration

OBJECTIVES

- a. To minimise the impact of noise and vibration and minimise adverse impacts on surrounding land uses.
- b. To ensure that development is designed to protect occupants from noise and vibration from the proposed development and surrounding uses.
- c. To ensure that development is designed in a manner that minimises the impact of noise and vibration.

CONTROLS

1. A noise assessment or acoustic report as detailed in **Table 3** is to be submitted where:
 - new development is proposed that will create noise and or vibration impacts either during construction or operation that impacts on adjoining developments;
 - a new noise-sensitive development is proposed in an area where existing noise sources are present or identified within the ILP (**Figure 59**) including development adjacent to arterial roads, sub-arterial roads and collector roads (**Figure 60**); and
 - a new development that will generate traffic that may create noise and or vibration impacts on adjoining developments.
2. A Construction Noise and Vibration Management Plan (CNVMP) is to be submitted with development applications that have the potential to adversely impact existing receiver locations, in particular heritage items. The CNVMP should be prepared as described in **Table 3** of this DCP.
3. Noise impacts from road traffic noise onto residential development should be assessed in accordance with the OEH's ECRTN. **Table 30** and **Figure 61** through to **Figure 65** identifies planning strategies for minimising road traffic noise.
4. Road traffic noise impact for sensitive development should be in accordance with OEH's ECRTN and **Table 31**.
5. Road traffic noise impact for commercial / industrial development should be in accordance with AS2107:2000.
6. Industrial noise
 - Noise emission from all industrial noise generating development should be assessed in accordance with the OEH's Industrial Noise Policy (INP) document.
 - The amenity goals for individual industrial developments should be set to 10dB below the Acceptable Noise Amenity levels so as to ensure cumulative impacts meet the 'acceptable' noise levels in Table 2.1 of the INP. Consideration however may be given to alternative amenity noise goals with provision of a detailed acoustic report (e.g. the number of industrial developments with the potential to impact upon nearby receiver locations may be considered for specific cases).






Table 30 Road traffic noise planning strategies

Principle	
Land use planning	
(1)	Situate less sensitive buildings in particular high rise developments and land uses along the busy road corridor.
(2)	Situating higher density, particularly less sensitive uses along the road corridor can provide acoustic shielding and substantial buffer distance to sensitive developments behind.
Building setbacks	
(1)	Building setback may not be sufficient to reduce noise impacts to satisfactory levels without the use of other methods.
(2)	If used in combination with a noise barrier (solid boundary fence), may provide satisfactory and usable outdoor amenity on the 'affected' side of the building.
(3)	Reduce implications of necessary building construction upgrades.
Earth mounds as a noise barrier	
(1)	Continuous lengths of earth mounds can be the ideal solution where moderate reductions of traffic noise are required and external areas are sited on the 'affected' side of lots (refer to Figure 65).
Building orientation and layout	
(1)	Locate less sensitive areas on 'affected' side of building (refer Figure 61 , Figure 62 , Figure 63 and Figure 64).
(2)	Where sensitive uses are ideally located on the affected side of building (for other design aspects), give provision for ventilation from opposite side of the dwelling to minimise potential requirements for mechanical ventilation.
(3)	Negative impacts of lot orientations are best addressed during subdivision layout stages to ensure site access permits improved outcomes for dwelling layout.
(4)	Use of standard height boundary fences should be considered when determining building orientation.
(5)	A continuous frontage (using a solid wall to extend to the boundary if necessary) is one way to lower noise levels across the rest of the property (refer to Figure 58).
(6)	Ancillary buildings such as sheds, garages etc. may be used to acoustically shield internal courtyards.
Building envelope construction	
(1)	According to the OEHs ECRTN, building treatment should only be considered for dwellings where the set external criteria ('base' criteria) is exceeded and other noise mitigation measures are either exhausted or are not cost effective.
(2)	Minimise extent of glazing and other openings on the noise affected façades.
(3)	Where external noise levels are less than 10dB(A) above the ECRTN 'base' criteria, the internal 'base' criteria may be achieved with windows closed.
(4)	Where external noise levels are more than 10dB(A) above the ECRTN 'base' criteria, acoustic grade seals would need to be installed on windows and perimeter doors exposed to road traffic.
(5)	Upgraded windows and glazing and the provision of solid core doors may also be required on the façades exposed to the road.

Figure 3.5: Single Dwr
from road noise




Figure 61 Locating noise sensitive rooms away from the noise source




Figure 62 Single storey residences



Figure 63 Double storey residences




Figure 64 Continuous non-sensitive use frontage



Figure 65 Service road for buffer and access to residential premises

Table 31 Guidelines for sensitive development

Specific development	Specific controls
Licensed premises	(1) Premises with a liquor licence are required to comply with the standard noise criteria issued by the Office of Liquor Gaming and Racing (OLGR).
School facilities	(1) Reference should be made to the NSW INP for activities within the school buildings. (2) The location of outdoor play areas and sporting fields should be separated from common boundaries of residential premises. (3) Access for buses and car drop off should be separated from common boundaries of residential premises.
Child care centres	(1) Refer to The Hills Development Control Plan 2012 Part B Section 6 - Business (Appendix E).
Multi purpose-halls	(1) Reference should be made to the intrusive criteria in Section 2.1 of the NSW INP and Section 2.4.1 of the NGLG December 2004 to assess potential noise impacts at nearby residential receiver locations. (2) Where entertainment is to be provided reference should be made to the standard noise criteria issued by the OLGR.

7.14 Odour

Odour is legislated by the *Protection of the Environment Operations Act 1997* and managed by the NSW Government. Currently the only methods of controlling odour impacts are applying buffers around odour generating activities and Industry Best Management Practices.

Prior to the commencement of this DCP the Precincts were mostly zoned for rural purposes. The Precincts, and nearby rural areas, contain a number of existing rural uses that have the potential to generate odour and other associated impacts that may affect the amenity of nearby urban areas.

While these activities may cease operation at some point in the future (such as when the land is rezoned and developed for urban purposes) the timing of cessation of odour generating land uses is not known nor able to be controlled by Council or the Department of Planning & Infrastructure. Developers and buyers of property within the Precincts should be aware that their property may be subject to odour impacts from these uses for an indeterminate period of time.

Where land is affected by an odour buffer or adjacent to odour generating activities Council will consider whether the type of development in this area is appropriate and will also consider the need for the applicant to provide additional supporting information with the Development Application.

8.0

Special Area Controls

8.0 SPECIAL AREA CONTROLS

8.1 Centres

Special Area Controls outline the objectives and design principles relating to areas that require detailed planning including the Box Hill Town Centre, Mt Carmel Village, Box Hill Inn Village, Nelson Road Village and Neighbourhood Centres.

8.1.1 Overall controls

The overall controls apply to the retail and commercial development within Box Hill Town Centre, Mt Carmel Village, Box Hill Inn Village, Nelson Road Village and Neighbourhood Centres.

8.1.1.1 Active Street Frontages and Address

OBJECTIVES

- a. To promote pedestrian activity and safety in the public domain.
- b. To maximise active street fronts in the local, village and neighbourhood centres.
- c. To define areas where active streets are required.
- d. To provide an identifiable and desirable street address to residential buildings outside of areas where active street fronts are required.
- e. To clearly and consistently define the street edge.
- f. To allow for outlook to and surveillance of the street.

CONTROLS

ACTIVE STREET FRONTAGES

1. Active frontage uses are defined as any of the following at street level:
 - entrance to retail;
 - shop front;
 - glazed entries to commercial and residential lobbies occupying less than 50% of the street frontage, to a maximum of 12m frontage;
 - café or restaurant if accompanied by an entry from the street;
 - active office uses, such as reception, if visible from the street; and/or
 - public building if accompanied by an entry.
2. Active street fronts, built to the street alignment, are required on the ground level of all retail and commercial development, and on areas identified in **Figure 66** through to **Figure 69**.
3. Large format retail such as supermarkets and parking areas are to be sleeved or hidden by retail and commercial uses as shown in **Figure 66**.

4. Ground floor residential uses (other than entries to lobbies to residential uses above ground level) are not permitted on the town centre Main Street.
5. Active ground floor uses are to be at the same general level as the footpath and be accessible directly from the street.
6. Restaurants, cafes and the like are to consider providing openable shop fronts.
7. Only open grill or transparent security shutters (at least 50% visually transparent) are permitted to retail and commercial frontages.
8. On corner sites, shop fronts are to wrap around the corner.
9. Entrances are to be visible to the street and well lit.

STREET ADDRESS

10. Street address is defined as:
 - a building that is not raised more than an average of 700mm above street level, up to a maximum of 1m;
 - contains entries, lobbies and habitable rooms with clear glazing overlooking the street; and
 - excludes car parking areas.
11. Provide multiple entrances for large developments including an entrance on each street frontage.
12. Provide direct 'front door' access to ground floor residential units.
13. Residential buildings are to provide not less than 65% of the lot width as street address.
14. In mixed-use buildings, a separate street address is required to retail, commercial and residential uses.

8.1.1.2 Awnings

OBJECTIVES

- a. To provide shelter for public streets where most pedestrian activity occurs.
- b. To address the streetscape by providing a consistent street frontage in the centres.

CONTROLS

1. Provide continuous street frontage awnings to all new commercial and retail developments within the town centre and village centres.
2. Wrap awnings around corners on street corner buildings.
3. Cantilever awnings from buildings are to have a minimum soffit height of 3.6m and a maximum of 4m.
4. Low profile awnings with slim vertical fascias and/or eaves (not to exceed 300mm) are encouraged.
5. Awnings are to be a minimum of 3m deep (dependant on street width) and setback from the kerb a minimum of 1.2m to allow clearance for street furniture, trees, etc. At any signalised intersections (on local roads or classified roads), awnings should be set back a minimum of 1.5m from the kerb for a distance of up to 100m from the signalised intersection.

6. Awnings must be complementary to each other and maintain continuity.
7. Steps for design articulation or to accommodate sloping streets are to be integrated with the building design and should not exceed 700mm.
8. Vertical canvas drop blinds are permissible along the street edge, but they are not to carry advertising or signage.
9. Provide under awning lighting to facilitate night use as well as improve public safety. Lighting is to be recessed into the soffit of the awning, or wall mounted onto the building.
10. Any under awning signage is to maintain a minimum clearance of 2.8m from the level of the pavement.
11. All residential buildings are to be provided with awnings or other weather protection at their main entrance area.

8.1.1.3 Signage

OBJECTIVES

- a. To permit adequate identification and business advertising that achieves a very high level of design quality in terms of graphic design, its relationship to the architectural design of buildings and the character of streetscapes.
- b. To promote signage that complements the scale and character of a building.
- c. To avoid the creation of visual clutter on buildings and streetscapes.
- d. To ensure compatibility with the desired urban character of adjacent land uses.
- e. To consider the amenity of residential development and the visual quality of the public domain.
- f. To ensure that advertising signs do not adversely affect the safety of motorists and other road users.

CONTROLS

GENERAL SIGNAGE

1. Signage must be integrated into the building façade and achieve a high degree of compatibility with the architectural design of the supporting building having regard to its composition, fenestration, materials, finishes and colours. Architectural features of the building are not to be obscured.
2. One under-awning sign is permitted on each shop or commercial premises at a rate of one sign per 8m of shop front.
3. Signs including real estate signs and temporary signs are not allowed to stand on the top of awnings.
4. The total area of all signs is not to exceed 1m² of advertising area per 1m of shop frontage. This includes signs painted on blinds or windows.
5. Signs that contain additional advertising promoting products or services not related to the approved use of the premises or site (such as the logos of brands or products) are not permitted.

6. Signs painted on, or applied to the roof, are prohibited.
7. Signs in excess of a total of 50m² in area are to be considered on their merits.
8. Directional signage and public notices are to have a coordinated appearance and help to establish the town centre as a unique destination and place.

ILLUMINATED SIGNS

9. Illumination (including cabling) of signs is to be:
 - concealed; or
 - integral with the sign; or
 - provided by means of carefully designed and located remote or spot lighting.
10. The ability to adjust the light intensity of illuminated signs is to be installed where the consent authority considers necessary.
11. Restricted hours shall be imposed on the operation of illuminated signs where continuous illumination is considered to impact adversely on the amenity of residential buildings, serviced apartments or other visitor accommodation, or have other adverse environmental effects.
12. Up-lighting of signs is prohibited. Any external lighting of signs is to be downward pointing and focussed directly on the sign and is to prevent or minimise the escape of light beyond the sign.

SIGNAGE AND ROAD SAFETY

13. Signs are regarded as prejudicial to the safety of road users if they:
 - obscure or interfere with road traffic signs and signals or with the view of a road hazard, oncoming vehicles, or any other vehicle or person, or an obstruction which should be visible to drivers or other road users,
 - give instructions to traffic by use of the word 'stop' or other directions, which could be confused with traffic signs,
 - are of such a design or arrangement that any variable messages or intensity of lighting impairs drivers' vision or distracts drivers' attention, and
 - are situated at locations where the demands on drivers' concentration due to road conditions are high such as at major intersections or merging and diverging lanes.

8.1.1.4 Parking

OBJECTIVES

- a. To provide an appropriate level of on-site car and bicycle parking provision in Box Hill Growth Centre Precincts to cater for a mix of development types and location.
- b. To minimise the visual impact of on-site parking.
- c. To integrate parking facilities with the overall site planning and landscape.

- d. To encourage the use of bicycles.

CONTROLS

1. On-site car and bicycle parking is to be provided in accordance with the standards set out in **Table 32** and **Table 33**.
2. The parking area per vehicle is to be in accordance with AS 2890:1.
3. All outdoor parking areas shall be appropriately screened by planting and/or fencing.
4. At grade car parks shall provide landscaping and tree planting in accordance with The Hills DCP 2012 Part C Section 1 - Parking.
5. Basement parking must be provided for Mixed Use Development. Basements are not to be raised more than 1m above ground level.
6. In the local centre and neighbourhood centres, parking and servicing is to be located to the rear of buildings, or below grade, to minimise impacts on the streetscape and pedestrian amenity.
7. Above ground parking structures are not permitted except in the central mixed use blocks in the local centre. Where fronting a street or public space (excluding service lanes), above ground parking is to be set a minimum of 8m behind the building façade.
8. Rear lanes should be utilised where possible to access parking areas.
9. All bicycle parking is to be in secure and accessible locations. Bicycle parking for employees is to have weather protection.
10. Refer **Section 5.4** of this DCP for residential flat building and multi dwelling housing parking provisions.
11. Refer to The Hills DCP 2012 Part C Section 1 – Parking for shop top housing parking provisions.

Table 32 On site car parking for commercial/retail premises

Use	Requirement
Retail Uses	1 space per 25m ² GFA (Gross Floor Area) for supermarkets and Discount Department Stores. 1 per 50m ² GFA for main street, village centre and other retail.
Commercial	1 space per 50m ² GFA.
Educational Establishments	1 space per full-time employee or classroom, whichever is greater, plus 1 space per 10 students over the age of 17 years. Where development includes the provision of a church or community facilities in conjunction with a school, additional parking must be provided at half the applicable rate.

Table 33 On site bicycle parking for commercial/retail premises

Use	Requirement
Retail	Provide the following minimum rates of bicycle parking. Supermarkets:

Use	Requirement
	<ul style="list-style-type: none"> 1 space per 750m² of GFA for employees. 1 space per 1000m² of GFA for shoppers. Speciality shops: <ul style="list-style-type: none"> 1 space per 300m² of GFA for employees. 1 space per 300m² of GFA for shoppers. Neighbourhood shops: <ul style="list-style-type: none"> 8 bicycle spaces minimum.
Commercial	Provide the following minimum rates of bicycle parking. Employee: <ul style="list-style-type: none"> 1 space per 150m² of GFA. Visitor: <ul style="list-style-type: none"> 1 space per 750m² of GFA.
Community Centres	<ul style="list-style-type: none"> 6 bicycle spaces at the community centre.
Parks	<ul style="list-style-type: none"> 16 bicycle spaces at sports grounds.
Primary and High Schools	<ul style="list-style-type: none"> One bicycle space per 5 students above Grade 4 at primary and high schools.

8.1.1.5 Site Servicing

OBJECTIVES

- To ensure that site facilities are functional and accessible to all residents and are easy to maintain.
- To ensure that site facilities are thoughtfully integrated into the development and are visually and physically unobtrusive.
- To minimise the impact of service access on pedestrians and retail, commercial and residential frontage.
- To minimise the visual and acoustic impact of site servicing.

CONTROLS

COMMERCIAL / RETAIL PREMISES AND MIXED USE DEVELOPMENT

- Garbage, mail box structures, service meters and the like are to be integrated with the overall design of the buildings and/or landscaping. Garbage storage areas are not permitted along the primary street frontage.
- Provide adequate space within any new development for the unloading and loading of service vehicles.
- Loading facilities must be located to the rear of each development.
- Ventilation stacks are to be utilised wherever possible to vent shops and basements.
- All service areas are to be screened from existing developments.
- Service access is permitted from rear lanes, side streets or right of ways.
- Vehicles must be able to enter/exit in a forward direction.
- Provide truck turning facilities.

8.1.2 Box Hill Town Centre

OBJECTIVES

- To create a vibrant Town Centre that provides amenity to the Box Hill and Box Hill Industrial Precincts.
- To ensure that the detailed design of the Town Centre is undertaken in a coordinated manner in order to achieve a high quality urban design outcome.
- To create a sense of place through the relationship of the Town Centre to the landscape.
- To promote a pedestrian friendly main street through the Town Centre.
- To ensure that the Town Centre is centrally located and easily accessible by pedestrians, cyclists and public transport users.
- To ensure that the Box Hill Town Centre is well served by public transport and has connections to the major transport nodes of Rouse Hill and Riverstone.
- To provide a good range of retail and commercial services for the future communities of the Precincts whilst minimising risk of oversupply and adverse economic impact on existing centres.
- To promote a Town Centre that is financially viable and easy to stage.



Figure 66 Indicative layout of Box Hill Town Centre

CONTROLS

1. The Box Hill Town Centre is to be located generally in accordance with **Figure 2**. An indicative layout plan of the Town Centre is shown at **Figure 66**.
2. The Town Centre is to be consistent with the following principles.

FUNCTION AND USES

3. A maximum of 30,000 m² GFA for retail and commercial premises (note: additional floor space for retail and commercial premises and/or other employment uses will be considered subject to an assessment of demand as part of any future application).
4. Incorporate a range of retail and commercial uses to serve the needs of the community.
5. Incorporate higher density housing and mixed use development.
6. Concentrate intensive retail uses along and fronting Mason Road.
7. Locate active uses at ground floor throughout the Town Centre, in particular fronting the Main Street.
8. Provide a mix of uses that promote an active and vibrant town centre.

BUILT FORM

9. Provide a range of building heights, up to a maximum of six storeys with a transition in heights to surrounding residential areas.
10. Relate building heights to street widths and functions to promote a comfortable urban scale of development.
11. Define streets and open spaces with buildings that are generally built to the street edge, have a consistent street wall height and provide a continuous street frontage along all key streets.
12. Sleeve all large format retail premises and decked parking areas with active uses. Blank walls visible from the public domain are to be avoided.
13. Promote diversity and activity along the main street with a variety of frontage widths for retail shops.
14. Building heights are to take into account view lines and solar access to the public domain.
15. Residential and mixed use development is to be consistent with the guidelines and principles outlined in *SEPP No. 65 – Residential Flat Development and the Residential Flat Design Code* (Urban Design Advisory Service and Planning NSW 2002).
16. A high quality built form and energy efficient architectural design that promotes a 'sense of place' and modern character for the Town Centre.
17. Waste storage and collection areas are to be accommodated and designed appropriately to minimise impacts, in particular within mixed use development.

PARKING AND ACCESS

18. Access to parking, loading docks and waste collection areas must not be provided from Mason Road (Main Street) frontages.

19. Basement, semi-basement or decked parking is preferred over large expanses of at-grade parking.
20. At grade parking areas are to be generally located behind building lines and within the centre of street blocks away from street corners. Notwithstanding this, Council will consider transitional arrangements for parking where an application is supported by a staging plan that indicates compliance with the above desired parking location principles upon ultimate development.
21. Parking is to be provided in accordance with The Hills Development Control Plan 2012 Part C Section 1 - Parking. Opportunities for shared parking provision for complementary uses within the town centre are to be provided.
22. On-street parking is to be provided on all streets within the Town Centre to contribute to street life and surveillance and designed in accordance with AS 2890.5-1993.

PUBLIC DOMAIN

23. Parks and plazas are to act as a focal point for the Town Centre and community activities and are to be designed to ensure adaptability and flexibility in use and function over time.
24. Incorporate a town square / civic plaza, adjacent to the main street which provides an urban landscape setting and a civic focus for the community.
25. Provide high amenity, pedestrian streets with generous footpath widths.
26. Incorporate the principles of Crime Prevention Through Environmental Design (CPTED) and Safer by Design (NSW Police) into all development within the Town Centre.
27. Weather protection for pedestrians is to be provided in key locations.
28. Provide a high quality landscape design including a co-ordinated package of street furniture and lighting that enhances the character of the Town Centre.
29. Provide street tree and open space planting that establishes generous shade for pedestrians.
30. Design all signage and advertising in a co-ordinated manner.
31. Site servicing and loading facilities, waste storage and other infrastructure are to be designed to minimise visual impact on the public domain and impacts on neighbours.

8.1.3 Mt Carmel Village

OBJECTIVES

- a. To create a vibrant, mixed use village that provides a range of small-scale retail, business and community uses which serve the needs of people who live and work in the surrounding area.
- b. To ensure that the detailed design of the village is undertaken in a co-ordinated manner in order to achieve a high quality urban design outcome.
- c. To create a vibrant village adjacent to residential areas and a school.



Figure 67 Indicative layout of Mt Carmel Village

CONTROLS

1. The Mt Carmel Village is to be located generally in accordance with **Figure 2**.
2. The village is to be consistent with the indicative layout shown in **Figure 67** and the following principles -

FUNCTION AND USES

3. Provide for a maximum of 6,000m² GFA for retail and commercial premises within the village centre to cater for the needs of the local population.
4. Incorporate a range of local retail, commercial and community uses to serve the needs of the local community.

BUILT FORM

5. Provide a range of building heights, up to a maximum of three storeys.
6. Buildings are to define the entry to the residential areas and open spaces adjacent to the village and are to be generally built to the street edge.
7. Avoid blank walls visible from surrounding streets and the public domain. Large format retail premises are to be sleeved where appropriate with active uses.
8. Residential and mixed use development is to be consistent with the guidelines and principles outlined in *SEPP No. 65 – Residential Flat Development* and the *Residential Flat Design Code* (Urban Design Advisory Service and Planning NSW 2002).
9. Establish a high quality built form and energy efficient architectural design that promotes a 'sense of place' and modern character for the village.

PARKING AND ACCESS

10. Locate at grade parking areas generally behind building lines and screened from streets and public open space.
11. Opportunities for shared parking provision for complementary uses within the village centre are to be provided.
12. On-street parking is to be provided within the village centre and designed in accordance with AS 2890.5-1993.

PUBLIC DOMAIN

13. Provide a high quality landscape design including a co-ordinated package of street furniture and lighting that enhances the character of the village.
14. Provide street tree and open space planting that establishes generous shade for pedestrians.
15. Incorporate the principles of Crime Prevention through Environmental Design (CPTED) and Safer by Design (NSW Police) into all development within the village centre.
16. Site servicing and loading facilities, waste storage and other infrastructure are to be designed to minimise visual impact on the public domain and impacts on neighbours.

8.1.4 Box Hill Inn Village

OBJECTIVES

- a. To create a vibrant, mixed use village that provides a range of small-scale retail, business and community uses which serve the needs of people who live and work in the surrounding area.
- b. To provide local services for the Business Park and surrounding area.
- c. To ensure that the detailed design of the village is undertaken in a co-ordinated manner in order to achieve a high quality urban design outcome.



Figure 68 Indicative layout plan of Windsor Road Village

CONTROLS

1. The village is to be located generally in accordance with **Figure 2**.
2. The village is to be consistent with the indicative layout shown in **Figure 68** and the following principles.

FUNCTION AND USES

3. Provide for a supermarket as part of a maximum of 7,000m² GFA for retail premises within the village to cater for the needs of the local area.

4. Incorporate a range of local retail, and community uses to serve the needs of the Business Park and local community.

BUILT FORM

5. Maximum building height is three storeys stepping back to two storeys in the vicinity of Windsor Road Village.
6. Avoid blank walls visible from surrounding streets and the public domain.
7. Residential and mixed use development is to be consistent with the guidelines and principles outlined in *SEPP No. 65 – Residential Flat Development* and the *Residential Flat Design Code* (Urban Design Advisory Service and Planning NSW 2002).
8. Establish a high quality built form and energy efficient architectural design that promotes a 'sense of place' and modern character for the village.

PARKING AND ACCESS

9. Access to parking, loading docks and waste collection areas must not be provided from Windsor Road.
10. Parking is to be provided in accordance with The Hills Development Control Plan 2012 Part C Section 1 - Parking. Opportunities for shared parking provision for complementary uses within the village are to be provided.
11. On-street parking is to be provided within the village and designed in accordance with AS 2890.5-1993.
12. Access arrangements to the village centre from Mt Carmel Road will be addressed during a future DA process with Council.

PUBLIC DOMAIN

13. Landscaping is to be used to define the entry to the Business Park surrounding the village centre.
14. Incorporate the principles of Crime Prevention through Environmental Design (CPTED) and Safer by Design (NSW Police) into all development within the village.
15. Environmental conservation land is to act as a focal point for the village. Transparent materials and voids should be used to strengthen the relationship (visual and otherwise) with environmental conservation to the west.
16. Common areas (such as food courts and circulation spaces) within the village are to maximise the outlook towards environmental conservation land to the west.
17. Site servicing and loading facilities, waste storage and other infrastructure are to be designed to minimise visual impact on the public domain and impacts on neighbours.

8.1.5 Nelson Road Village

OBJECTIVES

- a. To create a vibrant, mixed use village that provides a range of small-scale retail, business and community uses which serve the needs of people who live and work in the surrounding area.
- b. To ensure that the detailed design of the village is undertaken in a co-ordinated manner in order to achieve a high quality urban design outcome.
- c. To create a vibrant village adjacent to residential areas and a school.



Figure 69 Indicative layout plan of Nelson Road Village

CONTROLS

1. The Nelson Road Village is to be located generally in accordance with **Figure 2**.
2. The village is to be consistent with the indicative layout shown in **Figure 69** and the following principles.

FUNCTION AND USES

3. Provide for a maximum of 6,000m² GFA for retail and commercial premises within the village to cater for the needs of the local population.

4. Incorporate a range of local retail and commercial uses to serve the needs of the local community.

BUILT FORM

5. Provide a range of building heights, up to a maximum of three storeys.
6. Buildings are to define the entry to the residential areas and open spaces adjacent to the neighbourhood centre and are to be generally built to the street edge.
7. Avoid blank walls visible from surrounding streets and the public domain. Large format retail premises are to be sleeved where appropriate with active uses.
8. Residential and mixed use development is to be consistent with the guidelines and principles outlined in *SEPP No. 65 – Residential Flat Development* and the *Residential Flat Design Code* (Urban Design Advisory Service and Planning NSW 2002).
9. Establish a high quality built form and energy efficient architectural design that promotes a 'sense of place' and modern character for the village.

PARKING AND ACCESS

10. Locate at grade parking areas generally behind building lines and screened from streets and public open space.
11. Opportunities for shared parking provision for complementary uses within the village are to be provided.
12. On-street parking is to be provided within the village and designed in accordance with AS 2890.5-1993.

PUBLIC DOMAIN

13. Provide a high quality landscape design including a co-ordinated package of street furniture and lighting that enhances the character of the village.
14. Provide street tree and open space planting that establishes generous shade for pedestrians.
15. Incorporate the principles of Crime Prevention through Environmental Design (CPTED) and Safer by Design (NSW Police) into all development within the village.
16. Site servicing and loading facilities, waste storage and other infrastructure are to be designed to minimise visual impact on the public domain and impacts on neighbours.

8.1.6 Neighbourhood Centres

OBJECTIVES

- a. To provide a walkable local centre for the provision of services for the surrounding area.
- b. To ensure that the detailed design of the Neighbourhood Centre is undertaken in a co-ordinated manner in order to achieve a high quality urban design outcome.
- c. To create a vibrant Neighbourhood Centre adjacent to residential areas.

CONTROLS

1. Neighbourhood Centres are to be located generally in accordance with **Figure 2**.
2. The Neighbourhood Centre is to be consistent with the following principles.

FUNCTION AND USES

3. Provide for a maximum of 1,000m² GFA for retail and commercial premises within the Neighbourhood Centre to cater for the needs of the local population.
4. Incorporate a range of local retail, commercial and community uses to serve the needs of the local community.

BUILT FORM

5. Provide a range of building heights, up to a maximum of two storeys.
6. Buildings are to define the entry to the residential areas and open spaces adjacent to the Neighbourhood Centre and are to be generally built to the street edge.
7. Avoid blank walls visible from surrounding streets and the public domain. Large format retail premises are to be sleeved where appropriate with active uses.
8. Residential and mixed use development is to be consistent with the guidelines and principles outlined in *SEPP No. 65 – Residential Flat Development* and the *Residential Flat Design Code* (Urban Design Advisory Service and Planning NSW 2002).
9. Establish a high quality built form and energy efficient architectural design that promotes a 'sense of place' and modern character for the Neighbourhood Centre.

PARKING AND ACCESS

10. Access to parking, loading docks and waste collection areas must not be provided from Boundary Road.
11. Locate at grade parking areas generally behind building lines and screened from streets and public open space.
12. On-street parking is to be provided within the Neighbourhood centre and designed in accordance with AS 2890.5-1993.

PUBLIC DOMAIN

13. Provide a high quality landscape design including a co-ordinated package of street furniture and lighting that enhances the character of the Neighbourhood Centre.
14. Provide street tree and open space planting that establishes generous shade for pedestrians.
15. Incorporate the principles of Crime Prevention through Environmental Design (CPTED) and Safer by Design (NSW Police) into all development within the Neighbourhood Centre.
16. Site servicing and loading facilities, waste storage and other infrastructure are to be designed to minimise visual impact on the public domain and impacts on neighbours.

8.1.7 Box Hill House

OBJECTIVES


- a. To conserve the heritage significance of Box Hill House.
- b. To protect the heritage curtilage of Box Hill House.
- c. To ensure that the development around Box Hill House respects the heritage value of the building and landscape.

CONTROLS


1. Development within the Box Hill House State Heritage Register curtilage should be in accordance with the requirements of the NSW *Heritage Act 1977* and will require concurrent approval of the Heritage Council. Additionally, development should take into account the heritage provisions of the Growth Centres SEPP.
2. Development within the State Heritage Register curtilage and the Precinct Plan Control Area (**Figure 70**) should be accompanied by a Heritage Impact Statement as described in **Table 2** to address the significance of the House. The following matters must be considered in the Heritage Impact Statement:
 - The character, siting, bulk, height and external appearance of the development;
 - The visual relationship between the proposed development and Box Hill House;
 - The colours and textures of materials proposed to be used in the development;
 - The landscaping and fencing of the proposed development;
 - The location of car parking spaces and access ways into the development;
 - The impact of any proposed advertising signs or structures; and
 - The impact the proposed use would have on the amenity of Box Hill House.
3. Development within the Precinct Plan Control Area should respect the character of Box Hill House in accordance with the general principles of the height limitations in **Figure 71** and the Height of Buildings map in the Growth Centres SEPP.
4. The visual impact of structures within the Precinct Plan Control Area should be minimised through appropriate siting, landscaping and use of materials. Roof and wall colours are to be selected from the colour pallet in Appendix C. Prior to development within the Precinct Plan Control Area, archival recording should be undertaken to capture the current views and landscape setting. The recording must be in accordance with the guidelines issued by Heritage Branch, Department of Planning & Infrastructure *How to prepare archival records* (Heritage Office 1998) and *Photographic Recording of Heritage Items using Film or Digital Capture* (Heritage Office 2006).



Figure 70 Precinct Plan Control Area for Box Hill House



Box Hill House: Visual Assessment Section A



Box Hill House: Visual Assessment Detail Plan

Figure 71 Cross section of Box Hill House to Rouse Hill House

8.1.8 The Hunting Lodge

OBJECTIVES

- a. To conserve the heritage significance of The Hunting Lodge.
- b. To protect and enhance the heritage curtilage of The Hunting Lodge.
- c. To ensure that the development around The Hunting Lodge respects the heritage value of the building.
- d. To encourage the maintenance of the Hunting Lodge through an appropriate use.

CONTROLS

1. Development in and around The Hunting Lodge should be in accordance with the requirements of the NSW *Heritage Act 1977* and will require concurrent approval from the Heritage Council. Additionally, development should take into account the heritage provisions of the Growth Centres SEPP.
2. Development within the State Heritage Register curtilage and the Precinct Plan Control Area should be accompanied by a Heritage Impact Statement addressing the impact to the significance of The Hunting Lodge. The following matters must be considered in the Heritage Impact Statement:
 - The character, siting, bulk, height and external appearance of the development;
 - The visual relationship between the proposed development and the Hunting Lodge;
 - The potential for overshadowing of the Hunting Lodge;
 - The colours and textures of materials proposed to be used in the development;
 - The landscaping and fencing of the proposed development;
 - The location of car parking spaces and access ways into the development;
 - The impact of any proposed advertising signs or structures;
 - The impact the proposed use would have on the amenity of the Hunting Lodge; and
 - The effect the construction phase will have on the Hunting Lodge.
3. Housing to the north and east of the Hunting Lodge, across the proposed road, should be set back 5m from the property boundary.
4. The visual impact of structures within the Precinct Plan Control Area of The Hunting Lodge should be minimised through appropriate siting, landscaping and use of materials.
5. Consideration will be given to applications to alter the use of The Hunting Lodge to allow for commercial, retail or community uses.
6. Development, including subdivision within the Precinct Plan Control Area of The Hunting Lodge must comply with that outlined in **Figure 72**, unless accompanied by a Heritage Impact Statement demonstrating the merits of the proposed alternative.



Figure 72 Precinct Plan Control Area for the Hunting Lodge

8.1.9 Box Hill Inn

OBJECTIVES

- a. To conserve the heritage significance of the Box Hill Inn.
- b. To protect and enhance the heritage curtilage of the Box Hill Inn.
- c. To ensure that the development around the Box Hill Inn respects the heritage value of the building.
- d. To encourage the maintenance of the Box Hill Inn through an appropriate use.

CONTROLS

1. All development in and around Box Hill Inn should be in accordance with the requirements of the *NSW Heritage Act 1977* and will require concurrent approval from the Heritage Council. Additionally, development should take into account the heritage provisions of the Growth Centres SEPP.
2. Development within the State Heritage Register curtilage and the Precinct Plan Control Area (**Figure 73**) should be accompanied by a Heritage Impact Statement to address the significance of the Hunting Lodge and the following matters:
 - The character, siting, bulk, height and external appearance of the development;
 - The visual relationship between the proposed development and the Box Hill Inn;
 - The potential for overshadowing of the Box Hill Inn;
 - The colours and textures of materials proposed to be used in the development;
 - The landscaping and fencing of the proposed development;
 - The location of car parking spaces and access ways into the development;
 - The impact of any proposed advertising signs or structures;
 - The impact the proposed use would have on the amenity of the Box Hill Inn;
 - The archaeological potential and impact; and
 - The effect the construction phase will have on the Box Hill Inn.
3. Development respecting the character of the Box Hill Inn is encouraged in the Precinct Plan Control Area and should be limited to three storeys within 20 metres of the State Heritage Register curtilage.
4. It is recommended that development within the Precinct Plan Control Area should be limited or placed on the northern boundary. Surrounding development should be set back from the curtilage to create an area of open space and a plaza around the Box Hill Inn.
5. The Inn on the west, north and east sides should not be fenced to encourage a sense of integration with the surrounding development and to allow unimpeded access.
6. The visual impact of structures within the Precinct Plan Control Area of Box Hill Inn should be minimised through appropriate siting, landscaping and use of materials. A materials and colour palette is included in **Appendix C**.
7. Consideration is to be given to applications to alter the use of Box Hill Inn to allow for commercial, retail or community users.



Figure 73 Precinct Plan Control Area for Box Hill Inn

8.1.10 Marklye

OBJECTIVES

- a. To conserve the heritage significance of 18 Nelson Road, Marklye.
- b. To protect the heritage curtilage of Marklye.
- c. To ensure that the development around Marklye respects the heritage value of the building.

CONTROLS

1. Development within the Precinct Plan Control Area (**Figure 74**) should be accompanied by a Heritage Impact Statement to address the significance of Marklye and the following matters:
 - The character, siting, bulk, height and external appearance of the development;
 - The visual relationship between the proposed development and Marklye;
 - The potential for overshadowing of Marklye;
 - The colours and textures of materials proposed to be used in the development;
 - The landscaping and fencing of the proposed development;
 - The location of car parking spaces and access ways into the development;
 - The impact of any proposed advertising signs or structures;
 - The impact the proposed use would have on the amenity of Marklye;
 - The archaeological potential and impacts; and
 - The effect the construction phase will have on Marklye.
2. The visual impact of structures around Marklye should be minimised through appropriate siting, landscaping and use of materials. A suggested colour palette is provided in Appendix C.




Figure 74 Precinct Plan Control Area for Marklye

Appendix A

Glossary

APPENDIX A: Glossary

Note: definitions for terms are also included in the Dictionary contained within the Growth Centres SEPP.

“Abutting Dwelling” is a building containing one dwelling, on a single block of land, that is designed and constructed on a zero lot line immediately adjacent to another dwelling on a different lot that is also built to the zero lot line and is structurally independent of any other dwelling. See **Figure 1**.

“Articulation Zone” is the area that provides relief from blank façades and can include verandahs, porches, awnings, shading devices, bay windows, pergolas and the like. A carport is not considered part of the articulation zone.

“Building footprint” means the area of land measured at finished ground level that is enclosed by the external walls of a building.

“Detached Dwelling” is a building containing one dwelling, on a single block of land, that is not attached to any other dwelling. See **Figure 1**.

“Flood Planning Levels (FPLs)” are the combinations of flood levels (derived from significant historical flood events or floods of specific AEPs) and freeboards selected for floodplain risk management purposes, as determined in management studies and incorporated in management plans. Flood planning area is the area of land below the FPL and thus subject to flood related development controls. The concept of flood planning area generally supersedes the ‘flood liable land’ concept in the 1986 Manual. Flood Prone Land is land susceptible to flooding by the PMF event. Flood Prone Land is synonymous with flood liable land.

“Gross floor area” means the sum of the floor area of each storey of a building measured from the internal face of external walls, or from the internal face of walls separating the building from any other building, measured at a height of 1.4 metres above the floor, and includes:

- a. the area of a mezzanine within the storey, and
- b. habitable rooms in a basement, and
- c. any shop, auditorium, cinema, and the like, in a basement or attic,
- d. but excludes:
- e. any area for common vertical circulation, such as lifts and stairs, and
- f. any basement:
 - storage, and
 - vehicular access, loading areas, garbage and services, and
- g. plant rooms, lift towers and other areas used exclusively for mechanical services or ducting, and
- h. car parking to meet any requirements of the consent authority (including access to that car parking), and
- i. any space used for the loading or unloading of goods (including access to it), and
- j. terraces and balconies with outer walls less than 1.4 metres high, and
- k. voids above a floor at the level of a storey or storey above.

“Manor Home” means a 2-storey building containing 4 dwellings, where:

- (a) each storey contains 2 dwellings, and
- (b) each dwelling is on its own lot (being a lot within a lot within a strata scheme or community title scheme), and
- (c) access to each dwelling is provided through a common or individual entry at ground level,

but does not include a residential flat building or multi-dwelling housing.

“Net Residential Density” means the ratio of the number of dwellings to the area of land they occupy including internal access lanes and half the width of adjoining access roads that provide vehicular access to the relevant dwellings, but excluding public open space and drainage corridors.

“Principal dwelling” means the largest dwelling house on a lot, measured by gross floor area.

“Principal private open space” means the portion of private open space which is conveniently accessible from a living zone of the dwelling, and which receives the required amount of solar access.

“Private open space” means the portion of private land which serves as an extension of the dwelling to provide space for relaxation, dining, entertainment and recreation. It includes an outdoor room.

“Residential net developable area” means the land occupied by development, including internal streets plus half the width of any adjoining access roads that provide vehicular access, but excluding public open space and other non-residential land.

“Studio Dwelling” means a dwelling that:

- (a) Is established in conjunction with another dwelling (the **principal dwelling**), and
- (b) Is on its own lot of land, and
- (c) Is erected above a garage that is on the same lot of land as the principal dwelling, whether the garage is attached to, or separate from, the principle dwelling.

but does not include a demi-detached dwelling.

“Zero lot line dwelling” is a building containing one dwelling, on a single block of land, that is constructed with an exterior wall on one of its side boundaries but is not attached or abutting to any other dwelling. See **Figure 1**.




Figure 1 Detached, zero lot line, abutting and attached dwellings

Appendix B ***List of Preferred Plant*** ***Species***

APPENDIX B: List of Preferred Plant Species

Table B1: Preferred Species for General Planting

Indigenous Species Suitable for Planting in the Hills Shire						
Botanical Name	Common Name	Plant Community				
		Bird Attracting	Shale Cap Forest	Sandstone Soils	Cumberland Plain Woodland	Transition Forest
<i>Allocasuarina littoralis</i>	Black She-Oak			■	■	■
<i>Allocasuarina torulosa</i>	Forest Oak		■	■		■
* <i>Angophora costata</i>	Sydney Red Gum	■		■		■
<i>Angophora floribunda</i>	Rough-barked Apple	■	■	■		■
<i>Banksia serrata</i>	Old Man Banksia	■		■		
<i>Casuarina cunninghamiana</i>	River She Oak				■	
<i>Casuarina glauca</i>	Swamp She Oak			■	■	
* <i>Ceratopetalum gummiferum</i>	NSW Christmas Bush	■		■		
<i>Corymbia gummifera</i>	Red Bloodwood	■		■		
* <i>Corymbia maculata</i>	Spotted Gum					■
* <i>Elaeocarpus reticulatus</i>	Blueberry Ash	■	■			
<i>Eucalyptus crebra</i>	Narrow-leafed Ironbark	■			■	■
<i>Eucalyptus fibrosa</i>	Broad-leafed Ironbark	■			■	■
<i>Eucalyptus gummifera</i>	Red Bloodwood	■		■		
* <i>Eucalyptus haemastoma</i>	Scribbly Gum	■		■		
<i>Eucalyptus moluccana</i>	Grey Box	■			■	■
<i>Eucalyptus paniculata</i>	Grey Ironbark	■	■	■		■
<i>Eucalyptus pilularis</i>	Blackbutt	■	■	■		
* <i>Eucalyptus punctata</i>	Grey Gum	■		■		■
<i>Eucalyptus robusta</i>	Swamp Mahogany	■		■		
<i>Eucalyptus saligna</i>	Sydney Blue Gum	■	■	■		

Indigenous Species Suitable for Planting in the Hills Shire

Botanical Name	Common Name	Plant Community				
		Bird Attracting	Shale Cap Forest	Sandstone Soils	Cumberland Plain Woodland	Transition Forest
<i>Eucalyptus tereticornis</i>	Forest Red Gum	■			■	■
<i>Melaleuca decora</i>	White Feather Honey Myrtle	■			■	
<i>Syncarpia glomulifera</i>	Turpentine	■	■	■		■
* <i>Tristania laurina</i>	Water Gum	■		■		
<i>Shrubs</i>						
* <i>Acacia binervia</i>	Wattle			■		
* <i>Acacia decurrens</i>	Sydney Green Wattle				■	■
* <i>Acacia elata</i>	Mountain Cedar Wattle			■		
* <i>Acacia floribunda</i>	White Sallow Wattle			■	■	
* <i>Acacia implexa</i>	Hickory		■	■	■	■
* <i>Acacia longifolia</i>	Sydney Golden Wattle			■		
* <i>Acacia parramattensis</i>	Parramatta Green Wattle			■	■	■
<i>Banksia spinulosa</i>	Hairpin Banksia	■		■		■
* <i>Callicoma serratifolia</i>	Black Wattle			■		
<i>Callistemon citrinus</i>	Crimson Bottlebrush	■		■		
<i>Callistemon linearis</i>	Narrow-leafed Bottlebrush	■		■	■	
<i>Callistemon pinifolius</i>	Bottlebrush	■		■		
<i>Callistemon salignus</i>	Willow Bottlebrush	■		■		
<i>Davesia ulicifolia</i>	Pea			■		■
<i>Dodonaea triquetra</i>	Common Hop Bush			■	■	
<i>Dodonaea viscosa</i>	Hop Bush				■	
* <i>Grevillea mucronulata</i>	Green Spider Flower	■		■		
* <i>Grevillea linearifolia</i>	White Spider Flower	■		■		

Indigenous Species Suitable for Planting in the Hills Shire						
Botanical Name	Common Name	Plant Community				
		Bird Attracting	Shale Cap Forest	Sandstone Soils	Cumberland Plain Woodland	Transition Forest
*Hakea salicifolia	Willow-leaved Hakea	■		■		
*Hakea sericea	Bushy Needlebush	■		■	■	■
Hibbertia diffusa	Guinea Flower				■	
*Indigofera australis	Indigofera		■	■	■	■
Kunzea ambigua	Tick Bush	■		■		■
Leptospermum polygalifolium	Lemon-scented Tea Tree	■		■	■	
Leucopogon juniperus	Bearded Heath		■			■
*Lomandra longifolia	Mat Rush		■	■	■	■
Melaleuca linearifolia	Snow In Summer	■		■	■	
Melaleuca nodosa	Ball Honey Myrtle	■		■	■	
Melaleuca styphelioides	Prickly-leaved Paperbark	■		■	■	
Melaleuca thymifolia	Honey Myrtle	■		■	■	
Oxylobium ilicifolium	Native Holly			■		
Pimelia linifolia	Rice Flower			■		■
*Pittosporum revolutum	Sweet Pittosporum	■		■		
*Polyscias sambucifolia	Elderberry Panax	■		■		
Pultanaea villosa	Bush Pea				■	■
Groundcovers						
Adiantum aethiopicum	Maidenhair Fern		■	■		
Danthonia sp.	Wallaby Grass			■	■	■
*Dianella caerulea var caerulea	Blue Flax Lily	■		■	■	■
*Dianella revoluta	Mauve Flax Lily	■		■	■	

Indigenous Species Suitable for Planting in the Hills Shire						
Botanical Name	Common Name	Plant Community				
		Bird Attracting	Shale Cap Forest	Sandstone Soils	Cumberland Plain Woodland	Transition Forest
<i>Dichelachne crinita</i>	Longhair Plume Grass			■	■	
<i>Dichelachne micrantha</i>	Shorthair Plume Grass			■	■	
<i>Gahnia aspera</i>	Saw Sedge	■		■		
<i>Gahnia clarkei</i>	Saw Sedge	■		■		
<i>Gahnia melanocarpa</i>	Saw Sedge	■		■		
<i>Gahnia seiberana</i>	Saw Sedge	■		■	■	
<i>Geranium solanderi</i>	Native Geranium			■	■	
<i>Lepidosperma laterale</i>	Sword Sedges			■		
<i>Microlaena stipioides</i>	Weeping Meadow Grass		■	■	■	■
<i>Poa</i>	Tussock Grass		■	■		
<i>Pratia purpurascens</i>	Pratia			■	■	
<i>Stipa</i> sp.	Spear Grass			■	■	
<i>Themeda australis</i>	Kangaroo Grass		■	■	■	■
<i>Viola</i> sp.	Native Violet			■	■	
<i>Wahlenbergia communis</i>	Native Bluebell			■	■	
<i>Climbers</i>						
* <i>Clematis aristata</i>			■	■	■	
* <i>Clematis glycinioides</i>	Old Mans Beard			■	■	
<i>Glycine clandestina</i>	Love Creeper		■			■
<i>Hardenbergia violacea</i>	False Sarsaparilla		■	■	■	■
<i>Hibbertia scandens</i>	Golden Guinea Flower		■			

Indigenous Species Suitable for Planting in the Hills Shire						
Botanical Name	Common Name	Plant Community				
		Bird Attracting	Shale Cap Forest	Sandstone Soils	Cumberland Plain Woodland	Transition Forest
<i>Kennedia rubicunda</i>	Dusky Coral Pea			■	■	
* <i>Pandorea pandorana</i>	Wonga Wonga Vine		■	■		

Non-Indigenous Species Suitable for Planting in the Hills Shire

Botanical Name	Common Name
Trees	
<i>Agonis flexuosa</i>	Willow Myrtle
<i>Banksia integrifolia</i>	Coastal Banksia
<i>Bauhinia purpurea</i>	Butterfly Tree
<i>Betula penula</i>	Silver Birch
<i>Brachychiton populneus</i>	Kurrajong
<i>Callistemon viminalis</i>	Weeping Bottlebrush
<i>Callitris columellaris</i>	White Cypress Pine
<i>Callitris rhomboidea</i>	Port Jackson Cypress
<i>Calodendron capense</i>	Cape Chestnut
<i>Casuarina littoralis</i>	Black She-Oak
<i>Cornus florida</i>	Flowering Dogwood
<i>Cupressus glabra</i>	Arizona Cypress
<i>Cupressus sempervirens</i> 'Stricta'	Italian Cypress
<i>Eucalyptus cladocalyx</i> 'Nana'	Dwarf Sugar Gum
<i>Eucalyptus elata</i>	Willow Peppermint
<i>Eucalyptus eximia</i>	Yellow Bloodwood
<i>Eucalyptus ficifolia</i>	Scarlet-flowering Gum
<i>Eucalyptus leucoxylon</i>	White Ironbark
<i>Eucalyptus melliodora</i>	Yellow Box
<i>Eucalyptus nicholii</i>	Willow-leaf Peppermint
<i>Eucalyptus scoparia</i>	Willow Gum
<i>Fraxinus Americana</i>	White Ash
<i>Fraxinus excelsior</i> 'Aurea'	Golden Ash
<i>Fraxinus</i> 'Raywoodii'	Claret Ash
<i>Hakea laurina</i>	Pin-cushion Hakea
<i>Leptospermum petersonii</i>	Lemon-scented Tea Tree
<i>Leptospermum laevigatum</i>	Coastal Tea Tree
<i>Magnolia grandiflora</i>	White Magnolia
<i>Malus floribunda</i>	Flowering Crab Apple
<i>Melaleuca armillaris</i>	Giant Honey Myrtle
<i>Melaleuca liniifolia</i>	Flax-leaf Paper Bark

Non-Indigenous Species Suitable for Planting in the Hills Shire	
Botanical Name	Common Name
Melaleuca stypheloides	Prickly Paper Bark
Nyssa sylvatica	Tupelo
Photinia glabra 'Robusta'	Photinia
Photinia glabra 'Rubens'	Red-leaf Photinia
Quercus coccinea	Scarlet Oak
Quercus ilex	Holly Oak
Quercus palustris	Pin Oak
Schinus molle var ariera	Peppercorn Tree
Ulmus parvifolia	Chinese Elm
<i>Shrubs</i>	
Abelia grandiflora	Glossy Abelia
Aucuba japonica	Japanese Laurel
Azalea sp.	Azalea
Bauera rubroides	Native Dog Rose
Berberis thunbergii 'Atropurpurea'	Japanese Berberis
Boronia floribunda	Pink Boronia
Brunfelsia latifolia	Yesterday, Today and Tomorrow
Callistemon citrinus	Crimson Bottlebrush
Callistemon speciosus	Albany Bottlebrush
Choisya ternata	Mexican Orange Blossom
Coleonema pulchrum	Pink Diosma
Coprosma repens	Mirror Bush
Correa alba	White Correa
Cyathea cooperii	Rough-barked Tree Fern
Daphne odora	Winter Daphne
Epacris longiflora	Fuchsia Heath
Epacris obtusifolia	Bluntleaf Heath
Gardenia sp.	Gardenia
Grevillea hybrids	
Hebe 'Blue Gem'	Veronica
Hibiscus rosa-sinensis	Chinese Hibiscus
Hydrangea macrophylla	Hydrangea

Non-Indigenous Species Suitable for Planting in the Hills Shire	
Botanical Name	Common Name
<i>Juniperus chinensis</i> 'Japonica'	Chinese Juniper
<i>Juniperus communis</i> 'Hibernica'	Irish Juniper
<i>Lagerstroemia indica</i>	Crepe Myrtle
<i>Lambertia formosa</i>	Mountain Devil
<i>Leptospermum scoparium</i>	Manuka
<i>Leptospermum squarrosum</i>	Peach Flowered Tea Tree
<i>Magnolia soulangeana</i>	Japanese Magnolia
<i>Melaleuca bracteata</i>	
<i>Melaleuca incana</i>	Grey Honey Myrtle
<i>Melaleuca nesophila</i>	
<i>Michelia figo</i>	Port Wine Magnolia
<i>Murraya paniculata</i>	Orange Jessamine
<i>Rhododendron indicum</i>	Rhododendron
<i>Russelia equisetiformis</i>	Coral Bush
<i>Thuja occidentalis</i>	Common Yew
<i>Viburnum tinus</i>	Laurestinus
<i>Westringia fruticosa</i>	Coastal Rosemary
<i>Acacia brownii</i>	Heath Wattle
<i>Coprosma kirkii</i>	
<i>Grevillea fasciculata</i>	Grevillea
<i>Grevillea</i> 'Gaudichaudi'	Grevillea
<i>Grevillea</i> 'Poorinda Royal Mantle'	Grevillea
<i>Juniperus conferta</i>	Shore Juniper
<i>Parthenocissus quinquefolia</i>	Virginia Creeper
<i>Pyrostegia venusta</i>	Orange Trumpet Creeper
<i>Trachelospermum jasminoides</i>	
<i>Viola hederacea</i>	Native Violet
<i>Wistaria sinensis</i>	Wistaria

Table B2: Preferred Species for Street Tree Planting

Indigenous Species to The Hills Shire				
Tree Species	Common Name	Plant where No Footpath	Plant next to Footpaths & Cycleway	Soils
<i>Acmena smithii</i>	Lilly Pilly (Not CVs)		✓	Clay loams adaptable to sand
<i>Angophora floribunda</i>	Thin-Leaved Stringybark	✓		Clay loam and adaptable
<i>Backhousia citriodora</i>	Lemon Myrtle		✓	Clay loam to sandy loam
<i>Backhousia myrtifolia</i>	Grey Myrtle		✓	Alluvial soils and clay loams
<i>Brachychiton populneum</i>	Kurrajong		✓	Sand or sandy loam
<i>Callistemon 'Kings Park Special'</i>	Weeping bottlebrush		✓	Sandy loam
<i>Callistemon salignus</i>	White Bottlebrush		✓	Sandy loam
<i>Callitris columnaris</i>	White Cypress Pine		✓	Sandy to transitional soils
<i>Callitris rhomboidea</i>	Port Jackson Pine		✓	Sandy to transitional soils
<i>Cupaniopsis anacardiodes</i>	Tuckeroo	✓		Sandy soils adapted to clay loams
<i>Elaeocarpus eumundii</i>	Eumundi Quandong	✓		Well drained loam
<i>Elaeocarpus reticulatus</i>	Blueberry Ash	✓		Adaptable
<i>Eucalyptus crebra</i>	Narrow-Leaved Ironbark	✓		Clay and sandy loams
<i>Eucalyptus elata</i>	River Peppermint	✓		Alluvial soils
<i>Eucalyptus eugenioides</i>	Thin-Leaved Stringybark	✓		Clay loam adaptable to sandstone
<i>Eucalyptus fibrosa</i>	Broad-leaved Ironbark	✓		Clay loam to heavy clay, tolerates sandy soils
<i>Eucalyptus microcorys</i>	Tallow wood	✓		Adaptable
<i>Eucalyptus moluccana</i>	Grey Box	✓		Clay loams
<i>Eucalyptus paniculata</i>	Grey Ironbark	✓		Heavy clay and transitional soils
<i>Eucalyptus punctata</i>	Grey Gum	✓		Transitional

Indigenous Species to The Hills Shire

Eucalyptus tereticornis	Forest Red Gum	✓		Adaptable
Glochidion ferdinandii	Cheese Tree		✓	Sandy loam adaptable clay loam
Jacaranda mimosifolia	Jacaranda		✓	
Leptospermum petersonii	Tea Tree		✓	Sandy and clay loams
Leptospermum polygalifolia	Tantoon		✓	Sandy and clay loams
Lophostemon confertus	Queensland Box		✓	Adaptable
Melaleuca bracteata 'Revolution'	Revolution Green	✓		Sandy Loam
Melaleuca decora	Feather Honey Myrtle		✓	Heavy clay
Melaleuca lineariifolia	Snow in Summer	✓		Clay loam
Melaleuca styphelioides	Prickly Paperbark		✓	Sandy loam, adaptable to clay loam
Michelia doltsopa	Sweet Michelia	✓		Sandy to clay loam
Syzygium luehmannii	Riberry		✓	Clay loam to Alluvial - Adaptable
Tristaniopsis laurina	Water Gum	✓		Sandy loam adaptable to heavy clay
Tristaniopsis laurina 'Luscious'	Watergum - Luscious		✓	
Waterhousia floribunda	Weeping Lilli Pilli	✓		

Non-Indigenous Species Suitable for Planting in The Hills Shire

Tree Species	Common Name	Plant where No Footpath	Plant next to Footpaths & Cycleways	Soils
Medium Size				
Acer buergeranum			✓	
Acer platanoides 'Crimson Sentry'	Maple		✓	
Acer rubrum 'October Glory'	October Glory	✓		
Acer x freemanii 'Jeffersred'	Maple	✓		
Angophora bakeri			✓	Sandstone soils

Indigenous Species to The Hills Shire

Angophora costata	Sydney Red Gum	✓		Sandstone and Transitional soils
Calodendrum capense	Cape Chestnut		✓	
Flindersia australis	Australian Teak	✓		
Franklinia axilaris	Fried egg plant		✓	
Fraxinus pennsylvanica 'Urbdel'- Urbanite™	Ash		✓	
Fraxinus Raywood	Claret Ash	✓		
Lagerstroemia indica	Crepe Myrtle		✓	
Nyssa sylvatica	Tupelo	✓		
Pistacia chinensis	Chinese pistachio	✓		
Prunus campanulata			✓	
Prunus cerasifera 'Oakville Crimson Spire'	Ornamental Plum Fastigate CV		✓	
Prunus x blireana	Flowering plum		✓	
Pyrus calleryana 'Capital'	Ornamental Pear	✓		
Pyrus salicifolia	Weeping Pear		✓	
Quercus palustris 'Pringreen' Green Pillar®	Fastigate Pin Oak	✓		
Syncarpia glomulifera	Turpentine	✓		Adaptable
Ulmus parvifolia 'Todd'	Chinese Weeping elm	✓		
Zelkova serrata		✓		

Appendix C Materials and finishes colour palette

APPENDIX C: Materials and finishes colour palette



Bilby PG2 · B6




Baton P12 · D7



Carriage P13 · B7

Walls



Yarwood PG2 · A7



Burnished Bark P05 · D8



Aegina PG2 · H8

Detailing



Briar PG1 · D8



Noble Brown PG2 · B8

Fencing



Raku PG2 · C7



Aegina PG2 · H8

Roof

Source: Dulux Colour Palette