

15 September 2017

Project No. 00013808

FDC Construction & Fitout (NSW) Pty Ltd
22 - 24 Junction Street
FOREST LODGE NSW 2037

ATTENTION Ms Katrina Rollason
katrinar@fdcbuilding.com.au

Dear Katrina

SYDNEY OLYMPIC PARK PUB | STORMWATER DRAINAGE PHILOSOPHY

Site Description

The site is located within Sydney Olympic Park, to the east of ANZ Stadium. The Nearmaps image below shows the location of the proposed pub.



The subject site portioned off for the proposed development is approximately 970m². In its current state, the entire 970m² is imperviously paved area with a few tree plots located within. Runoff from the existing pavement is either discharged via sheet flow to the northeast, or captured in the existing stormwater drainage network.


It is proposed that a new pub will be constructed on the site. The proposed stormwater management philosophy will include:

- Capture roofwater with a series of gutters and downpipes and convey via subsurface pipe to the existing surface stormwater drainage network;
- Capture surface runoff via series of surface inlet pits; and
- Modify existing surface levels as required in order to provide overland flow paths to safe points of discharge.

SOPA Guidelines

A review was undertaken of the Sydney Olympic Park Authority (SOPA) Stormwater Management and Water Sensitive Urban Design Policy (WSUD Policy) to understand the requirements the proposed pub would need to meet.

It was determined that the site was located within the blue shaded area. See image below.



The blue area represents the WRAMS stormwater harvesting catchment.

Consultation with SOPA

Several discussions were undertaken between Lindsay Dynan, FDC and SOPA to understand the site specific water management requirements. Following these discussions, guidance was provided by Ben Woods, SOPA's Director of Property Development. It was concluded that:

- Provided the development can meet its demands using the WRAMS recycled water network, rainwater tanks will not be required. A water balance will need to be provided to support this.
- As the site is impervious in its current state, water quality treatment measures may be minimal, however, a MUSIC model must be provided to show the "Post-Development" pollutant levels are less than or equal to the existing site pollutant levels.
- As the site is impervious in its current state, provided the proposed development reduces the area of impervious portion, onsite detention will not be required.

Water Balance

The proposed development water balance has been undertaken using recorded rainfall data from the closest available weather station. The following table summarises the annual rainfall from Station 66212.

Summary statistics for all years

[Information about climate statistics](#)

Statistic	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Annual
Lowest	18.4	6.2	64.0	24.8	4.8	31.2	15.0	10.6	26.0	17.2	27.6	32.8	943.8
Highest	343.6	152.6	363.2	412.8	116.8	327.0	83.4	257.2	93.0	92.0	171.6	224.2	1303.8

The table below demonstrates how this rainfall data is converted to volume of runoff from the site catchment area.

Site Area	970 m ²	970 m ²
Annual Rainfall	943.8 mm	1303.8 mm
Runoff Volume	0.915 ML/year	1.265 ML/year

As can be seen in the table above, the anticipated runoff volume leaving the site and being collected within the WRAMS system is calculated to be between 0.915 and 1.265 ML/year.


The water usage was estimated using the Managing Urban Stormwater Part E – Water Sensitive Urban Design, Potable Water Guide Calculator for a Commercial development.

	Demand Type	Quantity	Usage Assumption	Demand (KL/yr/item)	Volume (KL/yr)
Non-Potable	Toilet	18	-	23	414
Non-Potable	Urinal	8	-	0.73	5.84
Non-Potable	Landscaping	75 m ²	-	0.72	54.75
Potable	Wash Basin	16	320	0.9125	292

The results in the table above indicate the volume of non-potable demands per year does not exceed the total volume produced per year within the catchment area. The volume of runoff from the site, contributing to the WRAMS recycled water supply is conservatively 440.4 kL/yr in excess of the non-potable demand.

Water Quality

A MUSIC model was prepared to determine the impact the proposed development will have on the quality of the water runoff, and compare this to the existing conditions. A screenshot of the model and the results can be seen below.



Treatment Train Effectiveness - Post-Development Node						
	Sources		Residual Load		% Reduction	
	Pre	Post	Pre	Post	Pre	Post
Flow (ML/yr)	0.626	0.624	0.626	0.624	0	0
Total Suspended Solids (kg/yr)	139	76.6	139	76.6	0	0
Total Phosphorus (kg/yr)	0.265	0.181	0.265	0.181	0	0
Total Nitrogen (kg/yr)	1.96	1.67	1.96	1.67	0	0
Gross Pollutants (kg/yr)	17.1	17.1	17.1	17.1	0	0

☒ Include Pre-Development

As can be seen in the screenshots above, the Post-Development pollutant loads were less than or equal to the Existing Development pollutant loads. This result was expected as the majority of the impervious pavement areas will be converted to impervious roof areas, producing less pollutants during rainfall events.

The MUSIC file has been provided with this letter for review.

Stormwater Peak Discharge

The existing site is considered 100% impervious, and therefore, the proposed development will not increase the impervious area of the site. As such, peak flows will be less than or equal to the existing peak flows leaving the site.

Conclusions

This letter has been developed based on the SOPA WSUD Policy, and following consultation with SOPA's Mr Ben Woods. As demonstrated above, it can be concluded that:

- The runoff from the site being discharged in to the existing WRAMS system exceeds the non-potable demand from the proposed development. As such, rainwater tanks will not be required for the proposed development.
- The water quality from the proposed development will be an improvement on the water quality of the runoff from the existing site. As such, no water quality treatment measures are proposed.
- The peak discharge from the proposed development will be equal to or less than the peak discharge from the existing site conditions. As such, onsite detention has not been proposed for this development.

The proposed stormwater drainage plans will be developed based on the philosophy above.



Should you require any further advice or clarification of any of the above, please do not hesitate to contact us.

Yours faithfully
LINDSAY DYNAN
CONSULTING ENGINEERS PTY LIMITED

Mathew McNamara
Associate Civil Engineer

Attachments

- (i) MUSIC model



PROJECT
**PROPOSED
SYDNEY OLYMPIC PARK PUB
HOMEBUSH NSW**

CLIENT
**FDC CONSTRUCTION AND
FITOUT PTY LTD**

NOTES

THE POSITION OF ALL EXISTING SERVICES SHOWN SHOULD BE REGARDED AS APPROXIMATE AND NOT NECESSARILY COMPREHENSIVE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE EXACT LOCATIONS OF ALL EXISTING SERVICES (WHETHER SHOWN OR NOT) AND INFORM ALL RELEVANT AUTHORITIES PRIOR TO ANY EXCAVATION.

DURING CONSTRUCTION, THE STRUCTURE SHALL BE MAINTAINED IN A STABLE CONDITION AND NO PART OF THE STRUCTURE SHALL BE OVER-STRESSED. TEMPORARY STRUCTURES, FORMWORK, FALSEWORK, TEMPORARY BRACING, SHORING AND THE LIKE SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

THE STABILITY OF TEMPORARY BATTERS SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

CONTRACTOR TO VERIFY SETOUT BEFORE COMMENCING EARTHWORKS. REFER ANY DISCREPANCIES TO ENGINEER.

WHERE SITE IS IN CUT ADJACENT TO SITE BOUNDARY, TOP OF RETAINING WALLS TO BE CONSTRUCTED FLUSH WITH EXISTING SURFACE OF NEIGHBOURING PROPERTIES TO AVOID IMPOUNDING WATER ON NEIGHBOURING PROPERTIES.

ALL EXPOSED/DISTURBED AREAS TO BE TREATED IN ACCORDANCE WITH COUNCIL'S REQUIREMENTS.

BULK EARTHWORKS CONTOURS ARE SHOWN AT 0.1m INTERVALS.

EXISTING CONTOURS ARE SHOWN AT 0.25m INTERVALS.

LEGEND

	BULK EARTHWORKS SPOTLEVEL
	EXISTING SPOTLEVEL
	BULK EARTHWORKS CONTOUR
	EXISTING CONTOUR
	EXISTING SEWER LINE
	EXISTING STORMWATER LINE
	BOUNDARY LINE

BULK EARTHWORKS LEVELS SHOWN ARE NOMINAL ONLY. ALL LEVELS TO BE CONFIRMED DURING DETAIL DESIGN.

C	15/09/17	RE-ISSUED FOR DEVELOPMENT APPLICATION	M.B. M.M.
B	31/08/17	RE-ISSUED FOR DEVELOPMENT APPLICATION	M.B. M.M.
A	18/08/17	ISSUED FOR DEVELOPMENT APPLICATION	J.F. M.M.
REV	DATE	DRAWING STATUS	DRN APP
TITLE			


BULK EARTHWORKS PLAN

DRAWING STATUS			SHEET SIZE
FOR APPROVAL			A1
DRAWN	DESIGNED	APPROVED	SCALE
M.Bector	S.Keverian	M.McNamara	1:100
PROJECT No.		DRAWING No.	REVISION

13808 DA - 0001 C

NOT FOR CONSTRUCTION

BULK EARTHWORKS PLAN
SCALE 1:100



PROJECT

**PROPOSED
SYDNEY OLYMPIC PARK PUB
HOMEBUSH NSW**

CLIENT

**FDC CONSTRUCTION AND
FITOUT PTY LTD**

NOTES

FOR BULK EARTHWORKS REFER TO DRAWING 13808-DA-0001

THE ARRANGEMENT OF SEDIMENT AND EROSION CONTROL MEASURES SHOWN ARE INDICATIVE ONLY AND RELATE TO A PARTICULAR STAGE OF THE CONSTRUCTION WORKS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DESIGN, CONSTRUCT AND MAINTAIN ANY ADDITIONAL MEASURES THAT MAY BE REQUIRED FOR THE CONTRACTOR'S CONSTRUCTION METHODOLOGIES, IN ORDER TO MEET ALL CONDITIONS AND REQUIREMENTS IMPOSED BY ANY STATUTORY AUTHORITY.

THE POSITION OF ALL EXISTING SERVICES SHOWN SHOULD BE REGARDED AS APPROXIMATE AND NOT NECESSARILY COMPREHENSIVE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE EXACT LOCATIONS OF ALL EXISTING SERVICES (WHETHER SHOWN OR NOT) AND INFORM ALL RELEVANT AUTHORITIES PRIOR TO ANY EXCAVATION.

DURING CONSTRUCTION, THE STRUCTURE SHALL BE MAINTAINED IN A STABLE CONDITION AND NO PART OF THE STRUCTURE SHALL BE OVER-STRESSED. TEMPORARY STRUCTURES, FORMWORK, FALSEWORK, TEMPORARY BRACING, SHORING AND THE LIKE SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

THE STABILITY OF TEMPORARY BATTERS SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

CONTRACTOR TO VERIFY SETOUT BEFORE COMMENCING EARTHWORKS. REFER ANY DISCREPANCIES TO ENGINEER.

WHERE SITE IS IN CUT ADJACENT TO SITE BOUNDARY, TOP OF RETAINING WALLS TO BE CONSTRUCTED FLUSH WITH EXISTING SURFACE OF NEIGHBOURING PROPERTIES TO AVOID IMPOUNDING WATER ON NEIGHBOURING PROPERTIES.

ALL EXPOSED/DISTURBED AREAS TO BE TREATED IN ACCORDANCE WITH COUNCIL'S REQUIREMENTS.

EXISTING CONTOURS ARE SHOWN AT 0.25m INTERVALS.

LEGEND

■■■■	SEDIMENT CONTROL FENCE, REFER TO DRAWING 13808-DA-0003 FOR DETAILS
GT □	GEOTEXTILE INLET FILTER, REFER TO DRAWING 13808-DA-0003 FOR DETAILS
□	APPROXIMATE AREA OF CONSTRUCTION SITE COMPOUND, FINAL LOCATION TO BE DETERMINED ON-SITE
15.00	EXISTING SPOTLEVEL
15.00	EXISTING CONTOUR
8	EXISTING SEWER LINE
SW	EXISTING STORMWATER LINE
- / -	PROPOSED CONSTRUCTION SITE FENCE
- . - . -	BOUNDARY LINE

C	15/09/17	RE-ISSUED FOR DEVELOPMENT APPLICATION	M.B. M.M.
B	31/08/17	RE-ISSUED FOR DEVELOPMENT APPLICATION	M.B. M.M.
A	18/08/17	ISSUED FOR DEVELOPMENT APPLICATION	M.B. M.M.

REV	DATE	DRAWING STATUS	DRN	APP
TITLE				

**EROSION & SEDIMENT
CONTROL PLAN**

DRAWING STATUS			SHEET SIZE	
FOR APPROVAL			A1	
DRAWN	DESIGNED	APPROVED	SCALE	
M.Bector	S.Keverian	M.McNamara	1:300	
PROJECT No.		DRAWING No.	REVISION	
13808		DA - 0002	C	

NOT FOR CONSTRUCTION



EROSION & SEDIMENT CONTROL PLAN





SCALE 1:300

PROJECT

PROPOSED
SYDNEY OLYMPIC PARK PUB
HOMEBUSH NSW

CLIENT

FDC CONSTRUCTION AND
FITOUT PTY LTD



C	15/09/17	RE-ISSUED FOR DEVELOPMENT APPLICATION	M.B.	M.M.
B	31/08/17	RE-ISSUED FOR DEVELOPMENT APPLICATION	M.B.	M.M.
A	18/08/17	ISSUED FOR DEVELOPMENT APPLICATION	M.B.	M.M.

REV	DATE	DRAWING STATUS	DRN	APP
TITLE				

EROSION & SEDIMENT
CONTROL DETAILS

DRAWING STATUS			SHEET SIZE	
FOR APPROVAL			A1	
DRAWN M.Bector	DESIGNED S.Keverian	APPROVED M.McNamara	SCALE NTS	
PROJECT No.		DRAWING No.	REVISION	

13808 DA - 0003 C

NOT FOR CONSTRUCTION

Monday, 28 August 2017

Project No. 00013808

FDC Construction and Fitout Pty Ltd
22-24 Junction Street
Forrest Lodge NSW 2037

ATTENTION Mrs Katrina Rollason
katrinar@fdcbuilding.com.au

**SYDNEY OLYMPIC PARK DESIGN COMPETITION | PUB
STORMWATER SYSTEM MAINTENANCE SCHEDULES**

In accordance with the Sydney Olympic Park Authority Policy (Attachment 4: Policy compliance checklist), provided in Appendix A, Table 1 is the maintenance schedule for the stormwater network installed on site.

This schedule sets out the minimum requirements to be undertaken on the site.

Should you require any further advice or clarification of any of the above, please do not hesitate to contact us.

Yours faithfully
LINDSAY DYNAN
CONSULTING ENGINEERS PTY LIMITED

Reviewed by

Shant Keverian
Civil Engineer

Mathew McNamara
Project Team Leader

Appendix A

Table 1 Stormwater Network Maintenance Schedule

Maintenance Action	Frequency	Performed By	Procedure
Inspect pit sump and remove any sediment/sludge	Six Monthly *	Maintenance Contractor	Remove grate and screen. Remove sediment/sludge build-up.
Inspect grate for damage or blockage	Six Monthly *	Maintenance Contractor	Check both sides of grate for corrosion, (especially corners and welds) Damage or blockage.
Inspect and remove any blockage of pipes	Six Monthly *	Maintenance Contractor	Remove any debris/material or blockages around pipe
Inspect and remove debris/litter/mulch	Six Monthly *	Maintenance Contractor	Remove blockages from grate and check if pit blocked.
Inspect pit walls (internal and external, if appropriate) for cracks or spalling	Annually	Maintenance Contractor	Remove grate to inspect internal walls. Repair as required. Clear vegetation from external walls if necessary and repair as required.
Check step irons for corrosion	Annually	Maintenance Contractor	Remove grate. Examine step irons and repair any corrosion or damage.
Check fixing of step irons is secure	Six Monthly	Maintenance Contractor	Remove grate and ensure fixings secure prior to placing weight on step iron
Landscape	Annually *	Maintenance Contractor	Annual inspections of the landscaping shall be undertaken to ensure that the system operates as required.

* And after every major storm event